

#### **5.14.1.2.5 CONCRETE STRENGTH**

This provision of the code shall not be used without the prior approval of the Bridge Engineer and Materials Engineer.

#### **Commentary**

Since most of the precast elements that are used are steam cured and the mix designs given in the ITD Standard Construction Specifications has replaced cement with fly-ash at a greater rate than one to one, the values as listed in this specification will not be correct.