

APPROVED POINTS, SHOES, BOOTS, AND SPLICERS

Approved points, shoes, boots, and splicers for pipe and H piles prepared by the Materials Section are listed in the Tables on the following pages. Manufacturers' names, addresses, and telephone numbers used in the tables are listed below.

The Contractor shall make his own arrangements to purchase preapproved accessories listed in the following Tables, or approved equals.

MANUFACTURERS' NAMES, ADDRESSES, AND TELEPHONE NUMBERS

APF

Associated Pile & Fitting Corp.

Tel # 800-526-9047

ICE

International Construction Equipment, Inc.

Tel # 888-893-7453

PAI

Piling Accessories Inc

Part of APF

VERSABITE

Versabite Foundation Accessories

Part of APF

VERSA STEEL

Versa Steel, Inc. Pile Accessories Division

Tel # 800-678-0814

CONSTRUCTION SUPPLY COMPANY

Tel # 503-620-2971

APPROVED H-PILE ACCESSORIES**TIP PROTECTORS**

POINT TYPE	APF	ICE	VERSA STEEL	EAGLE FOUNDRY COMPANY / CONSTRUCTION SUPPLY
Common point for Gravels	77750-B 7780-B* PAR-T Series	HPH Series		
Common point with teeth for rock or gravels with boulders	77600-B PAR-T Series	HPH-RB Series	VS-300N Series	HT-3300
Rock Point - slim section w/teeth	77750-B 7780-B* PAR-T Series	HPH-RB Series		

*Available only for 12" H piles.

SPLICERS

APF	ICE	VERSA STEEL	EAGLE FOUNDRY COMPANY / CONSTRUCTION SUPPLY
HP-30000	HSA Series	VS 400	HS-1000

APPROVED PIPE-PILE ACCESSORIES

60° CONICAL POINT

	APF	VERSA STEEL	EAGLE FOUNDRY COMPANY / CONSTRUCTION SUPPLY
Inside Fit	P-13006 VB-900 Series	VS-900 Series	CP-9900
Inside Fit (Bullet Nose)	P-14006		CP-9900B

OPEN-END CUTTING SHOE

	APF	VERSA STEEL	EAGLE FOUNDRY COMPANY / CONSTRUCTION SUPPLY
Inside Fit	O-14001 VB-700 Series	VS-700 Series	CS-7700

CLOSURE BOOT

APF
PB-20000

OUTSIDE FIT SPLICERS

APF	EAGLE FOUNDRY COMPANY / CONSTRUCTION SUPPLY	VERSA STEEL
S-20000 S-40000 Backing Ring	PS 8800	VS 800 Series

There are no approved inside fit prefabricated splicers.

Revisions:

June 2006	Split Footing Layout & Pile Notes and Approved Points, Shoes, Boots, & Splicers into separate articles
July 2009	Revised data based on Materials list of February 2009.
Feb 2012	Revised data based on Materials list of February 2012.
Sept 2012	Revised data based on Materials list of August 2012.
June 2013	Labeled pipe pile prefabricated splicer table as “outside fit”. Added note that there are no approved prefabricated inside fit splicers for pipe piles.
May 2014	Revised data based on Materials list of January 2014.
June 2014	Revised data based on Materials list of June 2014. Added statement for use of “approved equal” accessories.
Mar 2015	Revised data based on Materials list of October 2014.