

Temporary erosion control management involves the use of the following BMPs:

Temporary Erosion Control Management Best Management Practices	Typical Highway Construction Activities																											
	Demolish Pavement/Structures	Clear and Grub	Construct Access Road	Grading (inc. cut and fill slopes)	Channel Excavation	Channel Paving	Trenching/Underground Drainage	Underground Drainage Facility Installation	Drainage Inlet Modification	Utility Trenching	Utility Installation	Subgrade Preparation	Base Paving	AC Paving	Concrete Paving	Saw Cutting	Joint Sealing	Grind/Groove	Structure Excavation	Erect Falsework	Bridge/Structure Construction	Remove Falsework	Striping	Miscellaneous Concrete Work	Sound Walls/Retaining Walls	Planting and Irrigation	Contractor Activities	Treatment BMP Construction
EC-1 Scheduling/Sequencing of Construction Activities	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X		X		X	X	X	X	X	X	X
EC-2 Preservation of Existing/Natural Vegetation		X	X	X			X	X		X									X	X		X			X			
EC-3 Cofferdam			X		X		X														X							
EC-4 Diversion Channels/Ditches		X	X	X																	X							
EC-5 Slope Drains				X																	X							
EC-6 Hydraulic Mulch	X	X		X	X																X					X		X
EC-7 Hydroseeding	X	X		X	X																X					X		X
EC-8 Soil Binders	X	X		X	X														X		X					X		X
EC-9 Straw Mulch	X	X	X	X	X		X	X		X		X							X		X					X		X
EC-10 Wood Mulching	X	X	X	X	X		X	X		X		X							X		X					X		X
EC-11 Geotextiles, Plastic Covers & Erosion Control Blankets/Mats	X	X	X	X	X		X	X		X		X							X		X					X		X

Temporary Erosion Control Management Best Management Practices	Typical Highway Construction Activities																												
	Demolish Pavement/Structures	Clear and Grub	Construct Access Road	Grading (inc. cut and fill slopes)	Channel Excavation	Channel Paving	Trenching/Underground Drainage	Underground Drainage Facility Installation	Drainage Inlet Modification	Utility Trenching	Utility Installation	Subgrade Preparation	Base Paving	AC Paving	Concrete Paving	Saw Cutting	Joint Sealing	Grind/Groove	Structure Excavation	Erect Falsework	Bridge/Structure Construction	Remove Falsework	Striping	Miscellaneous Concrete Work	Sound Walls/Retaining Walls	Planting and Irrigation	Contractor Activities	Treatment BMP Construction	
EC-12 Vegetation/Seeding		X		X																						X		X	
EC-13 Dust Control	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X				X				X						
EC-14 Wind Erosion Control		X	X	X	X		X			X		X	X	X												X		X	
EC-15 Snow Management		X																									X		