

Temporary sediment control management involves the use of the following BMPs:

Temporary Sediment Control Management Best Management Practices	Typical Highway Construction Activities																											
	Demolish Pavement/Structures	Clear and Grub	Construct Access Road	Grading (inc. cut and fill slopes)	Channel Excavation	Channel Paving	Trenching/Underground Drainage	Underground Drainage Facility Installation	Drainage Inlet Modification	Utility Trenching	Utility Installation	Subgrade Preparation	Base Paving	AC Paving	Concrete Paving	Saw Cutting	Joint Sealing	Grind/Groove	Structure Excavation	Erect Falsework	Bridge/Structure Construction	Remove Falsework	Striping	Miscellaneous Concrete Work	Sound Walls/Retaining Walls	Planting and Irrigation	Contractor Activities	Treatment BMP Construction
SC-1 Dikes and Berms	X	X	X	X	X		X			X											X					X		X
SC-2 Check Dam	X	X		X	X		X																					X
SC-3 Gravel Bag Berm	X	X	X	X	X		X			X											X					X		X
SC-4 Street Sweeping and Vacuuming	X	X	X	X	X		X	X		X	X	X	X	X	X			X	X		X				X	X	X	X
SC-5 Sandbag Barrier	X	X	X	X	X		X			X		X							X		X					X		X
SC-6 Inlet/Outlet Protection	X	X	X	X	X		X	X	X	X		X	X			X	X	X	X								X	X
SC-7 Silt Fence	X	X	X	X	X		X			X		X							X		X					X		X
SC-8 Fiber Rolls	X	X	X	X	X		X			X											X					X		X
SC-9 Sediment/Desilting Basin	X	X	X	X	X																X					X		X
SC-10 Sediment Trap	X	X	X	X	X		X			X		X							X		X					X		X
SC-11 Temporary Construction Entrances		X	X	X																						X		X
SC-12 Temporary Roads		X	X	X																								
SC-13 Entrance/Outlet Tire Wash		X	X	X																					X	X		