



3311 State Street
Boise, Idaho 83707
Phone: 208-334-8000
www.itd.idaho.gov

ADDENDUM NO. 1

Date:	June 6, 2018	Owner:	ITD
Project:	Downey Brine Making Facility		
Project No.:	18-501	No. of Pages	5

NOTICE TO ALL BIDDERS

You are hereby notified of the following clarifications of and/or revisions to the Drawings and Specifications for the above referenced project.

THIS ADDENDUM is hereby made a part of the project requirements and contract documents for referenced project. **BE SURE** to acknowledge it in your Bid Proposal form.

ITEM NO.

1. QUESTION: Will ITD pay for building permits?
RESPONSE: Yes, ITD will pay for building permits. Contractor is responsible for trade permits.
2. QUESTION: How should the bid envelope be addressed?
RESPONSE: The bid envelope should be addressed to:

IDAHO TRANSPORTATION DEPARTMENT
3311 STATE STREET
BOISE, IDAHO 83707
ATTENTION: TONY PIRC
BID PROPOSAL: DOWNEY BRINE MAKING FACILITY

3. ATTACHMENTS:
Addendum #1, dated June 6, 2018, JHS Architects

END OF ADDENDUM NO. 1



June 6, 2018

ADDENDUM NO. ONE (1)

PROJECT: ITD # 18-501
Idaho Transportation Department
Brine Making Facility
Downey, Idaho

To: **All Bidders**

This addendum forms a part of the contract documents and modifies the original bidding documents as noted below. Except as affected by data included herein, all other parts of the contract documents shall remain in full force and effect. It shall be the sole responsibility of the bidder to appropriately disseminate this data to all concerned prior to the bid time and date. Acknowledge receipt of this addendum in the space provided on the bid form. Failure to do so may subject the bidder to disqualification.

This addendum consists of 3 pages and 1 pg. attachment for a total of 4 pages.

GENERAL ITEMS:

- Item G1 Petra is the CM for this project up through Bidding and Contract Negotiations only. Petra will not be involved in the performance of Work by the General Contractor.
- Item G2 Contractor shall pay for any local trade permits as required.
- Item G3 Concrete foundations, walls and S.O.G. at salt hopper area are base bid. Only the steel structure, metal wall and roof system at the salt hopper area is Alternate No. 1.
- Item G4 Excess excavation materials unsuitable for backfill shall be stock piled on site. Coordinate location with ITD.

Item G5 Pre-Bid Conference meeting attendance is attached.

ARCHITECTURAL ITEMS:

Item A1 Building finish floor elevation shall be 8” above highest existing grade elevation before any excavations. New exterior finish grade shall slope at 2% away from building and containment yard out to a point 10-ft from structure.

Item A2 Structural fill and base material is not available on site and shall be any material ¾” minus that is compactable to 90%.

Item A3 At Sectional Doors Specification 08 3613-3, 2.02 C.1, Delete subsections a, b, c, and d indicating buildings that are not part of this project. All overhead doors shown on drawings are to be Standard Lift Track.

Item A4 Structural concrete for foundations, S.O.G., and walls shall be 4500 psi at 28 days.

Item A5 Holding tank concrete containment area shall be enlarged by extending east end 10’-0” to the east. Holding tanks shall also shift to the east and final location shall be coordinated with Architect.

PLUMBING ITEMS:

Item P1 Plumbing Contractor to provide and install the following eyewash: Acorn Model S 0440-BF. Wall mounted eye/face wash, barrier free, ½” NPT chrome plated brass stay open ball valve w/stainless steel handle and in-line strainer, chrome plated brass, 1 ¼” tailpiece, stainless steel 11-3/4” diameter bowl, steel wall brackets w/yellow powder coated finish ANSI universal compliant sign and water proof test card. Run ½” cold water line to eyewash. Mount the unit at 36” off the finished floor level to the bottom of eye nozzles. Locate eyewash at south end of boiler and over floor sink. Indirect waste to floor sink w/airgap. Field verify exact location with engineer and architect.

Item P2 Containment yard will be extended 10’ with the brine tanks shifted to the end. Allow additional piping for this move.

ELECTRICAL ITEMS:

- Item E1 Provide and install an LED yard light on each side of containment area near loading controls (Hubbell #DDL-56L-4K-1). Provide and install a 20 ft. wooden utility pole (Bury 54"). Install yard light on pole (15'-0" above grade). Provide and install a ¾" conduit with two (2) #12 AWG with one #12 ground between yard lights and on to Panel "A". Obtain power from spare Circuit 21.
- Item E2 Provide in electrical bid, an allowance of \$8,045.00 to be paid to Rocky Mountain Power for installation of service. Electrical contractor shall be reimbursed upon submission of receipt showing payment made to Rocky Mountain Power. Receipt shall be submitted with schedule of values item on Contractor pay Application.
- Item E3 Rocky Mountain Power will set a new utility pole at northeast corner of property. Electrical Contractor shall include 600 feet of 4" conduit in base bid. Conduit route and actual length shall be coordinated with Rocky Mountain Power, after bid.

END OF ADDENDUM NO. 1

**Downey Brine Making Facility
Idaho Department of Transportation
Meeting Sign In**

Subject: Pre-Bid Conference

DATE: May 31, 2018

Name

Company/Phone Number

Debra Curtis

ITD

Boyd M. Davis

ITD

Nathan Wheeler

Petra, Inc.

JHS STROPSHIRE

JHS ARCHITECTS.