



## **ADDENDUM #1**

**(MECHANICAL/ELECTRICAL)**

Date: 11/18/2020  
Job Number: 20-229  
Prepared By: Chris Dyke & Matt Bradley  
Sheet: 1 of 1

**Project: ITD D5 Lab Modification**

**NOTICE TO BIDDERS:** THIS ADDENDUM IS HEREBY MADE A PART OF THE PROJECT REQUIREMENTS AND CONTRACT DOCUMENTS FOR THE PROJECT REFERENCED ABOVE.

1. The existing roof is currently under warranty. Please contact Dan at Smith Roofing and Siding in Idaho Falls at 208-317-7989 for more information.
2. Remove existing plastic ties holding the copper water line feeding the emergency shower. Replace with pipe hangers and properly support them per specification section 220100-2.2.E.
3. The spaces that are included in the scope of work do not contain asbestos. The building was abated in 2014.
4. Add 2" floor drain in Oven Lab near existing emergency eyewash. An existing 4" main waste line is located approximately 3' away. Contractor shall sawcut concrete floor to tie in new 2" waste, run new 2" vent exposed inside room to roof, provide and seal new roof penetration, and provide trap primer to new floor drain from nearest water source at sink approximately 10' away. Contractor shall verify site conditions prior to installation to verify drain location.
  - a. Basis of design: Sioux Chief series number 832-25DNR, post-construction leveling floor drain, no-hub outlet, 5-1/2" round, adjustable nickel bronze strainer and trap primer port. Install top of drain 1/8" below finish floor and caulk edge.
5. The sign-in sheet for the pre-bid is attached.

