


SEDIMENT TRAP BASIN



NOTES

1. SEE THE GENERAL NOTES FOR TEMPORARY EROSION CONTROL STANDARD DRAWINGS ON 212-1.
2. DETERMINE SEDIMENT TRAP SIZE ON A 2-YEAR 24-HOUR STORM DESIGN OR 3,600 CU. FT./ACRE. THE MAXIMUM DRAINAGE AREA PER SEDIMENT TRAP IS 5 ACRES.
3. LOCATE SEDIMENT TRAP OUTSIDE OF THE SLOPE STAKE LIMITS AND CONSTRUCT PRIOR TO THE START OF EXCAVATION OR REMOVAL OF EXISTING VEGETATION.
4. ENSURE THAT RIPRAP MATERIAL IS IN ACCORDANCE WITH 711.04 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
5. PROVIDE TYPE II RIPRAP/EROSION CONTROL GEOTEXTILE IN ACCORDANCE WITH SUBSECTION 718.06 OF THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
6. ENTIRE TRAP MAY BE ROCK LINED IF NECESSARY.
7. NOT TO SCALE.

ORIGINAL STORED
AT: ITD,
Headquarters
3311 West State
Boise, Idaho

ORIGINAL SIGNED BY:
J. CALEB LAKEY
DATE ORIGINAL SIGNED:
NOVEMBER 20, 2013

REVISIONS								
NO.	DATE	BY	NO.	DATE	BY	NO.	DATE	BY
1	09-93	MSM						
2	02-96	MSM						
3	10-10	KEH						
4	10-11	KEH						
5	11-13	RDL						

SCALES SHOWN
ARE FOR 11" X 17"
PRINTS ONLY

CADD FILE NAME:
212-4_1113.dgn

DRAWING DATE:
APRIL, 1993

**IDAHO
TRANSPORTATION
DEPARTMENT**



BOISE IDAHO

ORIGINAL SIGNED BY: TOM COLE for
HIGHWAYS PROGRAM OVERSIGHT ENGINEER

ORIGINAL SIGNED BY: TOM COLE
CHIEF ENGINEER

STANDARD DRAWING

**TEMPORARY EROSION AND
SEDIMENT CONTROL
SEDIMENT TRAP**

REQUIRES STD. DWG. 212-1

English

STANDARD DRAWING NO.
212-4

SHEET 1 OF 1