

1. PROVIDE $\frac{7}{8}$ "Ø ASTM A449 HIGH STRENGTH TIE RODS. 2. PROVIDE AN INITIAL MINIMUM TENSION OF 39,250 LBS. FOR THE RODS. 3. MEASURE BOLT TENSION BY THE USE OF DIRECT TENSION INDICATORS. PROVIDE D.T.I. THAT CONFORM TO ASTM F959 AND HARDENED STEEL WASHERS THAT 4. PROVIDE BEARING PLATES THAT CONFORM TO ASTM A36. 5. PROVIDE NUTS THAT CONFORM TO ASTM A563 GRADE DH 6. HOT DIP GALVANIZE TIE RODS, NUTS, WASHERS AND BEARING PLATES AFTER FABRICATION. APPLY AN ANTIGALLING LUBRICANT TO THE THREADS BEFORE 7. PROVIDE CONCRETE STRENGTH AS SHOWN ON THE PLANS. 8. PROVIDE CONCRETE THAT CONFORM TO 502 EXCEPT THAT ENTRAINED AIR WILL BE 5% \pm 1%. SELF CONSOLIDATING CONCRETE MAY BE USED IN 9. PROVIDE GROUT THAT CONFORM TO TYPE "B", CLASS I NON-METALLIC NON-SHRINK 10. SANDBLAST, CLEAN, AND GROUT LEVEL WITH SURROUNDING GIRDER SURFACES, KEYWAYS AND BLOCKOUTS. PROVIDE A BACKER ROD AS A SEAL FOR THE GROUT. 11. NO VEHICULAR TRAFFIC ALLOWED ON THE STRUCTURE UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENGTH OF 4,000 PSI. 12. PROVIDE SHOP DRAWING DETAILS THAT CONFORM TO CURRENT AASHTO SPECIFICATIONS. SHOW DETENSIONING SEQUENCE AND GIRDER LIFT POINTS ON 13. SUBMIT SHOP DRAWINGS IN ACCORDANCE WITH 506.03 AND 105.02. 14. KEEP THE PRESTRESSED SLAB IN A FLAT POSITION (TOP SURFACE UPWARDS) DURING TRANSPORTATION AND ERECTION AND LIFT ONLY BY MEANS OF THE LIFTING DEVICES PROVIDED. SUBMIT THE PROVISION FOR SUPPORT POINTS TO BE USED DURING TRANSPORTATION TO THE JOB SITE FOR APPROVAL. 15. DIMENSIONS ARE HORIZONTAL DIMENSIONS. CORRECT THE FINISHED SLAB LENGTH FOR GRADE AND PROVIDE AN ALLOWANCE FOR BEAM SHORTENING. 17. FINISH THE TOP SURFACE OF THE SLAB IN ACCORDANCE WITH 502.03, 18. SLAB ERECTION ASSUMED TO OCCUR 60-90 DAYS AFTER SLAB FABRICATION. 19. DESIGN BASED UPON 0.6" DIA. AASHTO M203 LOW RELAXATION STRAND.

20. DO NOT SHIP PRESTRESSED CONCRETE MEMBERS UNTIL TESTS ON CONCRETE CYLINDERS MANUFACTURED FROM THE SAME CONCRETE AND CURED UNDER THE SAME CONDITIONS AS THE GIRDERS INDICATE THAT THE CONCRETE OF THE PARTICULAR MEMBER HAS ATTAINED A COMPRESSIVE STRENGTH EQUAL TO THE SPECIFIED DESIGN 28 DAY COMPRESSIVE STRENGTH.

21. PRESTRESSING CONCRETE MEMBERS IS INCIDENTAL TO PRECAST AND PRESTRESSED PAY ITEMS IN 502.

TAILS	BRIDGE I	PLANS
	BRIDGE KEY NO.	
	COUNTY	KEY NO.
5G	BRIDGE DWG. NO.	SHEET OF