

DESIGN NOTES

DESIGN SPECIFICATIONS

IN ACCORDANCE WITH : "AASHTO LRFD BRIDGE DESIGN SPECIFICATION" 4th EDITION, WITH THE 2008 INTERIMS.

DESIGN LOADS

PERMANENT LOADS

DC	UNIT WEIGHT OF REINFORCED CONCRETE	0.150	kc
DW	FUTURE WEARING SURFACE	0.028	ksf
EV	UNIT WEIGHT OF SOIL	xxx	kc
	FILL DEPTH	x.xx	ft
EH	ACTIVE PRESSURE	xxx	kc
	AT REST PRESSURE	xxx	kc
ES	EARTH LOAD SURCHARGE AT HEAD WALL	x.xx	ft

TRANSIENT LOADS

LL	HL-93
IM	DYNAMIC ALLOWANCE APPLIED TO TRUCK & TANDEM

FOOTING DESIGN LOADS FOR HEADWALLS

STRENGTH LIMIT STATE

NOMINAL BEARING RESISTANCE $q_n = X$ ksf
EFFECTIVE FOOTING WIDTH $B' = xx$ ft
EFFECTIVE FOOTING LENGTH $L' = xx$ ft
RESISTANCE FACTOR $\phi_b = X$
FACTORED BEARING RESISTANCE $q_R = q_n \phi_b = xx$ ksf
FACTORED APPLIED LOAD $\gamma Q/(B'L') = xx$ ksf
SLIDING
NOMINAL SLIDING RESISTANCE $R_n = X$ kips
RESISTANCE FACTOR $\phi = xx$
FACTORED SLIDING RESISTANCE $R_R = R_n \phi = xx$ kips
FACTORED APPLIED LOAD $\gamma V = xx$ kips

SERVICE LIMIT STATE

PRESUMPTIVE BEARING CAPACITY $q_p = X$ ksf
BASED UPON FOOTING SETTLEMENT = X inches OR LESS
EFFECTIVE FOOTING WIDTH $B' = xx$ ft
EFFECTIVE FOOTING LENGTH $L' = xx$ ft
RESISTANCE FACTOR $\phi = 1.0$
FACTORED PRESUMPTIVE BEARING RESISTANCE $\phi q_p = xx$ ksf
FACTORED APPLIED LOAD $\gamma Q/(B'L') = xx$ ksf

GENERAL NOTES

CONSTRUCTION SPECIFICATIONS

MATERIALS, CONSTRUCTION AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE STATE OF IDAHO TRANSPORTATION DEPARTMENT, "STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION", 2004 EDITION, THE PROJECT PLANS AND SPECIFICATIONS.
THE ENGLISH UNITS SYSTEM OF MEASUREMENT SHALL BE USED AS STANDARD.

MATERIAL

CONCRETE : HEAD WALLS - CLASS 40B $f'c = 4$ ksi
METAL REINFORCEMENT : AASHTO M31, GRADE 60 $fy = 60$ ksi

PLAN DIMENSIONS AND ELEVATIONS

ALL EXPOSED EDGES OF CONCRETE SHALL BE BEVELED $\frac{3}{4}$ " UNLESS NOTED OTHERWISE.
ALL DIMENSIONS TO REINFORCING STEEL ARE TO CENTERLINE OF BAR UNLESS NOTED OTHERWISE.
CONCRETE COVER MEASURED FROM THE FACE OF THE CONCRETE TO THE FACE OF ANY REINFORCING BAR SHALL BE 2", UNLESS SHOWN OTHERWISE ON THE DRAWINGS.

CONSTRUCTION

CONSTRUCTION JOINTS WILL BE PERMITTED ONLY AT THE LOCATIONS SHOWN ON THE PLANS OR AS APPROVED BY THE ENGINEER.
THE DIFFERENCE IN ELEVATION OF THE BACKFILL MATERIAL ON BOTH SIDES OF THE STRUCTURE SHALL NOT EXCEED 2 FEET DURING BACKFILL OPERATIONS.
SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER IN ACCORDANCE WITH SECTION 504 AND SHALL INCLUDE COMPLETE DIMENSIONS AND DETAILS OF FABRICATION INCLUDING AN ERECTION DIAGRAM. MATERIALS BEING USED SHALL BE CLEARLY SPECIFIED. BEFORE PROJECT COMPLETION, THE CONTRACTOR SHALL FURNISH THE ENGINEER A 22" X 34" REPRODUCIBLE MYLAR COPY OF THE OF THE SHOP DRAWINGS.
FABRICATION AND INSTALLATION SHALL CONFORM TO SECTION 26 OF THE AASHTO LRFD BRIDGE CONSTRUCTION SPECIFICATIONS.
SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER IN ACCORDANCE WITH SUBSECTION 504.01G.

INCIDENTAL ITEMS

ALL ITEMS SHOWN OR NOTED ON PLANS WHICH ARE NOT SPECIFICALLY BID ITEMS ARE CONSIDERED INCIDENTAL ITEMS. THE COST OF FURNISHING AND INSTALLING ALL INCIDENTAL ITEMS WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE BID FOR OTHER ITEMS, UNLESS NOTED OTHERWISE.

R E V I S I O N S				DESIGNED	SCALES SHOWN ARE FOR 34" X 22" PRINTS ONLY	ORIGINAL SIGNED BY:	IDAHO TRANSPORTATION DEPARTMENT		English	DESIGN AND GENERAL NOTES	BRIDGE PLANS		
NO.	DATE	BY	DESCRIPTION	DESIGN CHECKED							BRIDGE LRFD MANUAL, PAGE B17.2D		
				DETAILED							CADD FILE NO. \\prj00000\bridge\ b17_2d.dgn	COUNTY	KEY NO.
				DWG. CHECKED								BRIDGE DRAWING NO.	SHEET
				CORRECTIONS								OF	
					DRAWING DATE: APR 2008	DATE SIGNED: <u>DATE</u>	INTERNAL-STORED-AT-ITD-BRIDGE SECTION						