

Key No. 12099 - INT HAWTHORNE & W QUINN ROADS, CHUBBUCK
Bannock County

Item No	Description	QTY	Unit
201-005A	CLEARING & GRUBBING	0.86	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	11.00	EACH
203-015A	REM OF BITUMINOUS SURF	4,673.00	SY
203-025A	REM OF CATCH BASIN	2.00	EACH
203-050A	REM OF CONC HEADWALL	5.00	EACH
203-060A	REM OF CONC SIDEWALK	246.00	SY
203-070A	REM OF CURB & GUTTER	742.00	FT
203-075A	REM OF FENCE	870.00	FT
203-105A	REM OF MISC IRR STR	5.00	EACH
203-125B	REM OF MISCELLANEOUS ITEMS - Hydrant	2.00	EA
203-125C	REM OF MISCELLANEOUS ITEMS - IRR Pipe	434.00	FT
203-135A	REMOVAL OF SIGN	6.00	EACH
205-005A	EXCAVATION	6,159.00	CY
205-040A	GRANULAR BORROW	738.00	CY
205-060A	WATER FOR DUST ABATEMENT	503.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	616.00	CY
212-011A	FIBER WATTLE	1,641.00	FT
212-060A	STABILIZED CONST ENTRANCE	4.00	EACH
212-095A	INLET PROTECTION	14.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	10,000.00	CA
301-005A	GRANULAR SUBBASE	4,686.00	TON
303-022A	3/4" AGGR TY B FOR BASE	2,552.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	294.00	GAL
405-240A	MISC PAV	268.00	SY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	1,312.00	TON
604-025A	12" IRR PIPE	247.00	FT
604-055A	30" IRR PIPE	747.00	FT
605-025A	12" STORM SEWER PIPE	278.00	FT
605-035A	18" STORM SEWER PIPE	362.00	FT
605-200A	STORM SEWER PIPE - 18" Perforated	172.00	FT
605-635A	ADJUST MANHOLE COVERS	9.00	EACH
605-640A	ADJUST VALVE COVERS	5.00	EACH
608-025A	12" APRON FOR PIPE	4.00	EACH
609-025A	MINOR STR - Headwall for Single Pipe	1.00	EACH
610-020A	FENCE TY 2 (OBSOLETE 2019)	496.00	FT
610-035A	FENCE TY 4	405.00	FT
614-015A	SIDEWALK	992.00	SY
614-020A	DRIVEWAY	233.00	SY
614-025A	CURB RAMP	117.00	SY
615-330A	GUTTER - ISPWC SD-708	66.00	FT
615-492A	CURB & GUTTER TYPE 2	2,188.00	FT
616-010A	SIGNS TY B	81.65	SF

616-050A	BRKAWY STL SIGN POST TY E	581.94	LB
616-070A	BRKAWY STL SIGN POST INST TY E	18.00	EACH
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	644.00	SF
626-035A	BARRICADE TY 2	8.00	EACH
626-040A	BARRICADE TY 3	8.00	EACH
626-105A	TRAF CNTL MAINTENANCE	120.00	HR
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	1,243.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	5,127.00	FT
634-005A	MAILBOX	5.00	EACH
640-005A	DRAINAGE GEOTEXTILE	966.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	5,900.00	SY
651-010A	LAWN CONST (SODDED)	1,544.00	SF
652-005A	UNDERGROUND SPRINKLER SYS	1.00	LS
656-005A	TRAF SIGNAL INSTALLATION	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	4,000.00	CA
675-015A	DIRECTED SURVEYING CREW	8,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S209-05A	DITCH	192.00	FT
S501-15A	RETAINING WALL - Modular Concrete Block	601.00	SF
S600-20A	FIRE HYDRANT ASSEMBLY	3.00	EACH
S656-15A	MULTIPLE APPROACH RADAR DETECTION SYSTEM	1.00	LS
S703-10A	SPECIAL AGGREGATE - FILTER SAND	207.00	TON
S703-10B	SPECIAL AGGREGATE - 2" DRAIN ROCK	1,059.00	TON
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS SITE WORK	35,000.00	CA
S900-51A	CONTINGENCY AMOUNT - POWER SUPPLY AND CONNECTION	5,000.00	CA
S901-05A	SP - CATCH BASIN (PSD-601)	9.00	EACH
S901-05B	SP - MANHOLE (PSD-612)	4.00	EACH
S901-05C	SP - MANHOLE (PSD-609)	7.00	EACH
S901-05D	SP - HYDRODYNAMIC SEPARATOR	3.00	EACH
S901-05E	SP - IRR STAND PIPE	1.00	EACH
S901-05F	SP - CLEAN OUT EXISTING INLET & PIPE	1.00	EACH
S901-05G	SP - IRRIGATION DIVERSION STRUCTURE	1.00	EACH
S901-05H	SP - REM & RESET GATE	1.00	EACH
S901-05I	SP - REM & RESET SIGN	4.00	EACH
S901-05J	SP - RELOCATE WATER METER ASSEMBLY	5.00	EACH
S901-05K	SP - WATER LINE CROSSING	6.00	EACH
S901-05L	SP - GROUND WATER OBSERVATION WELL	6.00	EACH
S904-05A	SP - PTZ CAMERA SYSTEM	1.00	LS
Z629-05A	MOBILIZATION	1.00	LS