

Key No. 13014 - SMA-7674, MOUNTAIN VIEW ROAD, MOSCOW  
Latah County

Item No	Description	QTY	Unit
201-005A	CLEARING & GRUBBING	2.07	ACRE
203-005A	REM OF OBSTRUCTIONS	1.00	LS
203-060A	REM OF CONC SIDEWALK	719.00	SY
203-070A	REM OF CURB & GUTTER	1,180.00	FT
203-075A	REM OF FENCE	131.00	FT
203-080A	REM OF GUARDRAIL/BARRIER	206.00	FT
203-090A	REM OF INLET	7.00	EACH
203-095A	REM OF MANHOLE	2.00	EACH
203-125B	REM OF MISCELLANEOUS ITEMS - OVERHEAD LIGHT	2.00	EA
203-125C	REM OF MISCELLANEOUS ITEMS - PIPE	601.00	FT
205-005A	EXCAVATION	6,208.00	CY
205-040A	GRANULAR BORROW	754.00	CY
205-060A	WATER FOR DUST ABATEMENT	150.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	600.00	CY
209-005A	SMALL DITCH	523.00	FT
212-011A	FIBER WATTLE	3,603.00	FT
212-020A	SILT FENCE	216.00	FT
212-060A	STABILIZED CONST ENTRANCE	4.00	EACH
212-095A	INLET PROTECTION	28.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	15,000.00	CA
303-022A	3/4" AGGR TY B FOR BASE	8,112.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	507.00	GAL
405-425A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-2	2,811.00	TON
502-065A	CONC CL 40 AF	49.00	CY
504-040A	COMB PED/BICYCLE & TRAF RAILING	56.00	FT
605-025A	12" STORM SEWER PIPE	692.00	FT
605-035A	18" STORM SEWER PIPE	412.00	FT
605-455A	MANHOLE TY A	13.00	EACH
605-500A	CATCH BASIN TY 1	21.00	EACH
605-635A	ADJUST MANHOLE COVERS	9.00	EACH
605-640A	ADJUST VALVE COVERS	16.00	EACH
608-025A	12" APRON FOR PIPE	6.00	EACH
608-035A	18" APRON FOR PIPE	2.00	EACH
610-005A	FENCE A (DOWELED WOOD)	59.00	FT
610-005B	FENCE B (CEDAR WOOD)	36.00	FT
612-005D	W-BEAM GUARDRAIL	239.00	FT
612-115B	GUARDRAIL TERMINAL, FLARED	4.00	EACH
612-120A	GUARDRAIL TRANSITION, LOW SPEED	4.00	EACH
614-015A	SIDEWALK	2,234.00	SY
614-020A	DRIVEWAY	68.00	SY
614-025A	CURB RAMP	269.00	SY
615-256A	CURB TYPE 1	475.00	FT

615-492A	CURB & GUTTER TYPE 2	4,746.00	FT
616-010A	SIGNS TY B	331.00	SF
616-050A	BRKAWY STL SIGN POST TY E	1,260.00	LB
616-070A	BRKAWY STL SIGN POST INST TY E	51.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
620-005A	TOPSOIL	37.00	CY
621-005A	SEED BED PREPARATION	1.80	ACRE
621-010A	SEEDING	1.80	ACRE
621-015A	MULCHING	1.80	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	1.80	ACRE
621-035A	FERTILIZING	1.80	ACRE
624-005A	LOOSE RIPRAP	10.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,311.00	SF
626-040A	BARRICADE TY 3	14.00	EACH
626-105A	TRAF CNTL MAINTENANCE	240.00	HR
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	1,279.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	2,917.00	FT
634-005A	MAILBOX	1.00	EACH
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	36.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	10,129.00	SY
641-005A	BIAXIAL GEOGRID	10,129.00	SY
651-010A	LAWN CONST (SODDED)	966.00	SF
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	5,000.00	CA
675-015A	DIRECTED SURVEYING CREW	5,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-15A	RETAINING WALL	762.00	SF
S600-20A	FIRE HYDRANT ASSEMBLY	1.00	EACH
S616-10A	Rectangular Rapid Flashing Beacon (RRFB)	1.00	EA
S619-05A	JUNCTION BOX	5.00	EACH
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	20,000.00	CA
S901-05A	SP BICYCLE RAMP	5.00	EACH
S901-05B	SP DOMESTIC WATER METER	1.00	EACH
S911-05A	SP TRUCK APRON CURB & GUTTER	263.00	FT
S911-05B	SP DOUBLE ROLLED CURB	179.00	FT
S911-05C	SP UTILITY CONDUIT (3" PAIR)	217.00	FT
Z629-05A	MOBILIZATION	1.00	LS