

Key No. 19028 - GOLDEN VALLEY ROAD; 1500 W TO 1100 W & 950 W TO 900 W
Cassia County

Item No	Description	QTY	Unit
201-005A	CLEARING & GRUBBING	9.46	ACRE
203-125B	REM OF MISCELLANEOUS ITEMS	6.00	EA
205-005A	EXCAVATION	917.00	CY
205-030A	BORROW	3,022.00	CY
209-005A	SMALL DITCH	276.00	FT
212-011A	FIBER WATTLE	610.00	FT
212-105A	WATER POLLUTION AND EROSION CONTROL	5,000.00	CA
303-022A	3/4" AGGR TY B FOR BASE	31,295.00	TON
308-005A	CEM RECYCLED ASPH BASE STAB	64,250.00	SY
308-010A	PORTLAND CEM	600.00	TON
308-015A	PULVERIZE EXISTING SURF	49,220.00	SY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	3,090.00	GAL
402-020A	EMUL ASPH FOR PRIME COAT	50.00	TON
405-245A	APPROACH	40.00	EACH
405-260A	WEDGE MILLING	1,600.00	SY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	18,850.00	TON
602-025A	12" PIPE CULV	1,011.00	FT
602-035A	18" PIPE CULV	110.00	FT
608-035A	18" APRON FOR PIPE	4.00	EACH
616-010A	SIGNS TY B	67.00	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	60.00	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.15	MFBM
618-025A	STREET MONUMENT	7.00	EACH
621-005A	SEED BED PREPARATION	6.50	ACRE
621-010A	SEEDING	6.50	ACRE
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,024.00	SF
626-050A	DRUMS	40.00	EACH
626-100B	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	150.00	HR
626-120A	FLAGGER CONTROL	1,750.00	HR
626-125A	PILOT CAR	500.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	300.00	EACH
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	94,664.00	FT
634-005A	MAILBOX	1.00	EACH
640-015A	SUBGRADE SEPARATION GEOTEXTILE	200.00	SY
651-010A	LAWN CONST (SODDED)	850.00	SF
654-025A	COMPOST	13.00	ACRE
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	5,000.00	CA
675-015A	DIRECTED SURVEYING CREW	5,000.00	CA
Z629-05A	MOBILIZATION	1.00	LS