

Key No. 19134 - US-93, 100 SOUTH RD, JEROME COUNTY
Jerome County

Item No	Description	QTY	Unit
110-005A	TRAINING	1,600.00	HR
201-005A	CLEARING & GRUBBING	50.84	ACRE
203-005A	REM OF OBSTRUCTIONS	1.00	LS
203-015A	REM OF BITUMINOUS SURF	51,429.00	SY
203-075A	REM OF FENCE	5,915.00	FT
203-080A	REM OF GUARDRAIL/BARRIER	238.00	FT
203-105A	REM OF MISC IRR STR - VALVE	4.00	EACH
203-125C	REM OF MISCELLANEOUS ITEMS - PIPE	1,649.00	FT
203-130B	REMOVAL OF PAV MARKINGS	129.00	SF
203-135A	REMOVAL OF SIGN	42.00	EACH
205-010A	EXCAVATION SCHEDULE NO.1	122,587.00	CY
205-015A	EXCAVATION SCHEDULE NO.2	21,633.00	CY
205-020A	CONTROLLED BLASTING	4,200.00	FT
205-040A	GRANULAR BORROW	96,332.00	CY
205-060A	WATER FOR DUST ABATEMENT	250.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	1,200.00	CY
212-011A	FIBER WATTLE	10,530.00	FT
212-060A	STABILIZED CONST ENTRANCE	6.00	EACH
212-095A	INLET PROTECTION	4.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	40,000.00	CA
301-005A	GRANULAR SUBBASE	114,136.00	TON
303-022A	3/4" AGGR TY B FOR BASE	66,131.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	5,643.00	GAL
405-245A	APPROACH	9.00	EACH
405-410A	SUPERPAVE HMA PAV CL SP-T	2,819.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	36,663.00	TON
431-005A	COLD MILLING	137.00	SY
602-025A	12" PIPE CULV	350.00	FT
602-030A	15" PIPE CULV	90.00	FT
602-035A	18" PIPE CULV	447.00	FT
602-045A	24" PIPE CULV	2,125.00	FT
605-630A	INLET TY 8	4.00	EACH
608-025A	12" APRON FOR PIPE	2.00	EACH
608-035A	18" APRON FOR PIPE	6.00	EACH
608-045A	24" APRON FOR PIPE	20.00	EACH
610-015A	FENCE TY 1 B	628.00	FT
616-010A	SIGNS TY B	488.00	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	527.00	LB
616-055A	BRKAWY WOOD SIGN POST TY D	1.81	MFBM
617-005A	DELINEATOR TY 1	118.00	EACH
617-050A	MILEPOST TY 1	4.00	EACH
621-005A	SEED BED PREPARATION	32.95	ACRE

621-010A	SEEDING	32.95	ACRE
624-005A	LOOSE RIPRAP	249.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,074.00	SF
626-050A	DRUMS	400.00	EACH
626-076A	ARROW BOARD TY C	1,000.00	HR
626-093A	TEMP PAV MARKING - WATERBORNE	196,131.00	FT
626-100B	MISC TEMPORARY TRAF CONT ITEMS	20,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	690.00	HR
626-110A	TEMP FLEX RAISED PAV MARKER	680.00	EACH
626-114A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	2,000.00	HR
626-120A	FLAGGER CONTROL	400.00	HR
630-020A	PAV MKG - WATERBORNE	741.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	79,431.00	FT
631-010A	RUMBLE STRIPS	0.59	MILE
634-005A	MAILBOX	1.00	EACH
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	7,210.00	SY
645-010A	C3 FIELD LAB	1.00	LS
654-025A	COMPOST	32.95	ACRE
656-005A	TRAF SIGNAL INSTALLATION (FLASHING BEACON)	1.00	LS
656-005B	TRAF SIGNAL INSTALLATION (HAZARD BEACON)	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	15,000.00	CA
675-015A	DIRECTED SURVEYING CREW	15,000.00	CA
S703-10A	SPECIAL AGGREGATE (FILTER SAND)	2,491.00	TON
S900-50B	CONTINGENCY AMOUNT - BLASTING MONITORING & EXPENSES	5,000.00	CA
S901-05C	SP JUNCTION BOX	42.00	EACH
S901-05D	SP UTILITY/FIBER OPTIC VAULT	6.00	EACH
S901-05F	SP RWIS - POLE, TOWER, AND CABINET RELOCATI ON	1.00	EACH
S902-05A	SP BLASTING CONSULTANT	100.00	HR
S911-05A	SP TRAF SIGNAL CONDUIT	4,112.00	FT
S911-05B	SP UNDERGROUND CONDUIT - FIBER OPTIC COMMUN ICATIONS	13,994.00	FT
S911-05C	SP REMOVAL OF ABANDONED IRRIGATION	600.00	FT
Z629-05A	MOBILIZATION	1.00	LS