

Key No. 19292 - MAIN ST/SILVER VALLEY RD BRIDGE
Shoshone County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
201-010A	CLEARING & GRUBBING	1.00	LS
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	11.00	EACH
203-006A	REMOVAL OF SIGN	5.00	EACH
203-010A	ASBESTOS REMOVAL AND DISPOSAL	15,000.00	CA
203-080A	REMOVAL OF GUARDRAIL	217.00	FT
203-080B	REMOVAL OF BARRIER	113.00	FT
205-005A	EXCAVATION	1,450.00	CY
212-011A	FIBER WATTLE	157.00	FT
212-105A	WATER AND POLLUTION	10,000.00	CA
215-005A	GEOSYNTH REINFORCED ABUTMENT BACKFILL	107.00	CY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	10,000.00	CA
303-021A	3/4" AGGREGATE TYPE A FOR BASE	200.00	TON
307-005A	OPEN-GRADED BASE CLASS I	84.00	CY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	140.00	TON
504-010B	STRUCTURAL STEEL - TUBE RAIL EXTENSION	1.00	LS
510-005A	CONCRETE OVERLAY	36.30	CY
511-005A	CONCRETE WATERPROOF SYSTEM - TYPE C	123.90	SY
560-005A	DEWATERING FOUNDATION	1.00	LS
566-005A	COMPRESSION EXPANSION JOINT - 1"	71.00	FT
569-005A	REMOVAL OF EXPANSION JOINT	71.00	FT
581-005A	CONCRETE CRACK REPAIR PREPARATION	80.00	FT
581-010A	CONCRETE CRACK EPOXY INJECTION	1.60	GAL
587-005A	PAINTING STRUCTURAL STEEL - BRIDGE RAIL, APPROX. 235 FEET	1.00	LS
587-005B	PAINTING STRUCTURAL STEEL - PILING, APPROX. 413 SF	1.00	LS
605-635A	ADJUST MANHOLE COVERS	1.00	EACH
605-640A	ADJUST VALVE COVERS	1.00	EACH
612-005A	W-BEAM GUARDRAIL	201.00	FT
612-085A	GUARDRAIL TERMINAL TYPE 8	1.00	EACH
612-115C	GUARDRAIL TERMINAL, TANGENT	1.00	EACH
612-120A	GUARDRAIL TRANSITION, LOW SPEED	1.00	EACH
612-150A	CONCRETE BARRIER	45.00	FT
612-155A	CONCRETE TERMINAL TYPE A	1.00	EACH
614-015A	SIDEWALK	53.00	SY
614-025A	CURB RAMP	8.00	SY
615-257A	CURB TYPE 2	123.00	FT
616-010A	SIGN TYPE B-1	18.00	SF
616-040J	STEEL SIGN POST TYPE E-1 - E-1	30.00	FT
616-040k	STEEL SIGN POST TYPE E-2 - E-2	17.00	FT
616-080A	REINSTALL SIGN FACE	1.00	EACH
616-085A	REINSTALL SIGN POST	1.00	EACH
624-005A	LOOSE RIPRAP - CLASS VII	1,047.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	226.00	SF
626-040A	BARRICADE TYPE 3	9.00	EACH
626-100A	MISC TEMPORARY TRAF CONT ITEMS	7,000.00	CA

626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	144.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	237.00	DAY
630-005A	T,W,S,A PAVEMENT MARKINGS - WATERBORNE	30.00	SF
630-025A	LONG PAV MKG - WATERBORNE	2,117.00	FT
632-005A	CONC BRIDGE DECK REM CL A	373.00	SY
632-010A	CONC BRIDGE DECK REM CL B	55.00	SY
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	1,004.00	SY
650-005A	TIME-LAPSE CAMERA	1.00	EACH
650-010A	TIME-LAPSE CAMERA SERVICE	3.00	MO
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	5,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-20A	SP BRIDGE - EXTEND DECK DRAINS	12.00	EACH
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	20,000.00	CA
S901-05A	SP - GUARDRAIL TRANSITION TYPE 12	1.00	EACH
S911-05A	SP - UTILITY BEDDING	98.00	FT
Z629-05A	MOBILIZATION	1.00	LS