

Key No. 19338 - I-84, SOUTH JEROME INTERCHANGE
Jerome County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	10,000.00	CA
110-005A	TRAINING	4,957.00	HR
201-005A	CLEARING & GRUBBING	30.00	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	49.00	EACH
203-005A	REM OF OBSTRUCTIONS	1.00	LS
203-020A	REM OF BRIDGE , MULTI-SPAN	1.00	EACH
203-025A	REM OF CATCH BASIN	16.00	EACH
203-050A	REMOVAL OF CONCRETE HEADWALL	1.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	15,000.00	CA
203-060A	REM OF CONC SIDEWALK	285.00	SY
203-070A	REM OF CURB & GUTTER	643.00	FT
203-075A	REM OF FENCE	9,500.00	FT
203-080A	REM OF GUARDRAIL/BARRIER	3,056.00	FT
203-105A	REM OF MISC IRR STR	2.00	EACH
203-125A	REM OF MISCELLANEOUS ITEMS (LUMINAIRES)	1.00	LS
203-125B	REM OF MISCELLANEOUS ITEMS (EXISTING TRAFFIC SIGNALS)	1.00	EA
203-125C	REM OF MISCELLANEOUS ITEMS (PIPE)	2,690.00	FT
203-130A	REMOVAL OF PAV MARKINGS	21,000.00	FT
203-135A	REMOVAL OF SIGN	73.00	EACH
204-006A	OBLITERATION OF OLD ROAD	1.00	LS
205-010A	EXCAVATION SCHEDULE NO.1	144,009.00	CY
205-015A	EXCAVATION SCHEDULE NO.2	4,630.00	CY
205-040A	GRANULAR BORROW	455.00	CY
205-045A	GRANULAR BORROW	373,611.00	TON
205-060A	WATER FOR DUST ABATEMENT	760.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	6,000.00	CY
210-005A	STR EXCAVATION SCH NO. 1	52.00	CY
210-015A	COMPACTING BACKFILL	455.00	CY
212-011A	FIBER WATTLE	18,861.00	FT
212-020A	SILT FENCE	6,182.00	FT
212-060A	STABILIZED CONST ENTRANCE	20.00	EACH
212-095A	INLET PROTECTION	34.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	50,000.00	CA
301-005A	GRANULAR SUBBASE	86,084.00	TON
303-022A	3/4" AGGR TY B FOR BASE	48,345.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	10,295.00	GAL
405-240A	MISC PAV	169.00	SY
405-245A	APPROACH	17.00	EACH
405-410A	SUPERPAVE HMA PAV CL SP-T	3,399.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	19,312.00	TON
409-015A	CONC PAV	16,444.00	SY
431-005A	COLD MILLING	14,703.00	SY

502-015A	CONC CL 30	174.00	CY
502-140A	CONC CL 40-A SCH NO. 1	308.10	CY
502-310A	CONC CL 40 AF SCH NO. 2	656.60	CY
502-380A	PRESTRESSED WF GIRDER , 42" DEPTH	2,013.00	FT
502-435A	APPROACH SLAB	716.60	SY
503-010A	METAL REINF SCH NO. 1	63,356.00	LB
503-015A	METAL REINF SCH NO. 2	42,756.00	LB
503-020A	EPOXY COATED METAL REINF	61,882.00	LB
504-040A	COMB PED/BICYCLE & TRAF RAILING	925.60	FT
507-005A	BRIDGE BEARINGS PLAIN (Size__) 10"x3'-0"x1/2"	48.00	EA
509-005A	NON-STRUCTURAL CONC CLASS 30AF	12.60	CY
520-005A	PREDRILLING FOR PILING IN SOIL	348.20	FT
520-010A	PREDRILLING FOR PILING IN ROCK	224.00	FT
566-005A	COMPRESSION EXPANSION JOINT	200.90	FT
575-005A	TEXTURED CONCRETE SURFACE	198.00	SY
576-005A	(GFRP) REINFORCEMENT GLASS FIBER REINFORCED POLYMER	980.00	FT
577-005A	PILE SLEEVES	416.20	FT
584-005A	TEMPORARY SHORING	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
602-035A	18" PIPE CULV	82.00	FT
602-045A	24" PIPE CULV	10.00	FT
604-055A	30" IRR PIPE	1,014.00	FT
605-025A	12" STORM SEWER PIPE	1,755.00	FT
605-035A	18" STORM SEWER PIPE	1,998.00	FT
605-045A	24" STORM SEWER PIPE	1,346.00	FT
605-055A	30" STORM SEWER PIPE	448.00	FT
605-465A	MANHOLE TY C	5.00	EACH
605-467A	MANHOLE TY D	10.00	EACH
605-600A	INLET TY 3A	7.00	EACH
605-605A	INLET TY 1	30.00	EACH
605-630A	INLET TY 8	13.00	EACH
605-635A	ADJUST MANHOLE COVERS	28.00	EACH
605-640A	ADJUST VALVE COVERS	10.00	EACH
608-025A	12" APRON FOR PIPE	10.00	EACH
608-035A	18" APRON FOR PIPE	6.00	EACH
608-045A	24" APRON FOR PIPE	5.00	EACH
608-055A	30" APRON FOR PIPE	1.00	EACH
609-025A	MINOR STR -IRRIGATION OUTFALL	1.00	EACH
609-025B	MINOR STR	1.00	EACH
610-030A	FENCE TY 3 B	8,606.00	FT
610-035A	FENCE TY 4	687.00	FT
610-250A	BRACES	43.00	EACH
612-005D	W-BEAM GUARDRAIL	7,620.00	FT
612-080A	GUARDRAIL TERMINAL TY 7	4.00	EACH
612-085A	GUARDRAIL TERMINAL TY 8	8.00	EACH
612-115C	GUARDRAIL TERMINAL, TANGENT	20.00	EACH

612-120A	GUARDRAIL TRANSITION, LOW SPEED	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
612-150A	CONCRETE BARRIER	765.00	FT
612-156A	CONCRETE TERMINAL TY B	4.00	EACH
614-015A	SIDEWALK	2,742.00	SY
614-020A	DRIVEWAY	581.00	SY
614-025A	CURB RAMP	262.00	SY
615-330A	GUTTER -MODIFIED	125.00	FT
615-492A	CURB & GUTTER TYPE 2	8,017.00	FT
615-651A	TRAFFIC SEPARATOR TYPE 1	274.00	FT
616-010A	SIGNS TY B	878.00	SF
616-015A	SIGNS TY C	1,843.00	SF
616-030A	OVERHEAD BRIDGE SIGN STRUCTURE	1.00	EACH
616-030B	OVERHEAD BRIDGE SIGN STRUCTURE	1.00	EACH
616-031A	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-031B	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-031C	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-031D	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-035A	SIGN BRACKETS & BRACE ANGLES	848.70	LB
616-040A	BRKAWY STL SIGN POST TY A	4,187.00	LB
616-045A	BRKAWY STL SIGN POST TY B	4,336.00	LB
616-050A	BRKAWY STL SIGN POST TY E	2,804.00	LB
616-060A	BRKAWY STL SIGN POST INST TY A	18.00	EACH
616-065A	BRKAWY STL SIGN POST INST TY B	35.00	EACH
616-070A	BRKAWY STL SIGN POST INST TY E	44.00	EACH
616-080A	REINSTALL SIGNS	1.00	EACH
617-005A	DELINEATOR TY 1	69.00	EACH
617-010A	DELINEATOR TY 2	83.00	EACH
617-045A	DELINEATOR TY 9	19.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
620-025A	PLANTING SHRUB (BARE-ROOT or CONTAINER) GRASS SAA	339.00	EACH
620-025B	PLANTING SHRUB (BARE-ROOT or CONTAINER) GRASS SWB	120.00	EACH
620-025C	PLANTING SHRUB (BARE-ROOT or CONTAINER) PERENNIALS PEF	460.00	EACH
620-025D	PLANTING SHRUB (BARE-ROOT or CONTAINER) PERENNIALS SNM	88.00	EACH
620-025E	PLANTING SHRUB (BARE-ROOT or CONTAINER) PERENNIALS SPB	74.00	EACH
621-005A	SEED BED PREPARATION	24.70	ACRE
621-010A	SEEDING	24.70	ACRE
624-005A	LOOSE RIPRAP	1,047.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,892.00	SF
626-040A	BARRICADE TY 3	16.00	EACH
626-050A	DRUMS	80.00	EACH
626-066A	ARROW BOARD TY A	2,000.00	HR
626-092A	TEMPORARY PAVEMENT MARKING TAPE	60,000.00	FT
626-093A	TEMP PAV MARKING - WATERBORNE	60,000.00	FT
626-100B	MISC TEMPORARY TRAF CONT ITEMS	25,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	700.00	HR

626-113A	FLOOD LIGHTS	1.00	LS
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	1,100.00	DAY
626-116A	TEMP CONCRETE BARRIER	15,100.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	40,000.00	FT
626-118A	TEMP CRASH CUSHION	4.00	EACH
626-120A	FLAGGER CONTROL	500.00	HR
626-121A	R&R TEMP CRASH CUSHION	4.00	EACH
626-135A	WEIGHTED BASE TUBULAR MARKERS	460.00	EACH
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	3,657.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	146,143.00	FT
634-005A	MAILBOX	5.00	EACH
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	5,501.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	45,151.00	SY
645-010A	C3 FIELD LAB	1.00	LS
650-070A	TIME-LAPSE CAMERA	2.00	EACH
650-070B	TIME-LAPSE CAMERA SERVICE	36.00	MO
651-010A	LAWN CONST (SODDED)	850.00	SF
652-005A	UNDERGROUND SPRINKLER SYS	1.00	LS
654-025A	COMPOST	24.70	ACRE
656-005A	TRAF SIGNAL INSTALLATION	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	15,000.00	CA
675-015A	DIRECTED SURVEYING CREW	15,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S209-05A	DITCH	1,065.00	FT
S501-17A	MSE RETAINING WALL WELDED WIRE	11,338.00	SF
S501-17A	MSE RETAINING WALL	11,346.00	SF
S501-20A	SP BRIDGE , DRILLED SHAFT - CROSSHOLE SONIC LOG (C SL) TEST	6.00	EACH
S501-20B	SP BRIDGE , DRILLED SHAFT - THERMAL INTEGRITY PROF ILING (TIP) TEST	6.00	EACH
S501-30A	SP BRIDGE , DRILLED SHAFT - CROSSHOLE SONIC LOG (C SL) ACCESS TUBES	1,404.00	FT
S501-30B	SP BRIDGE , PROTECTIVE FENCE	416.00	FT
S501-40A	SP BRIDGE , DRILLED SHAFT - SOIL EXCAVATION INCLUD ING HAUL	78.00	CY
S501-40B	SP BRIDGE , DRILLED SHAFT - ROCK EXCAVATION INCLUD ING HAUL	134.00	CY
S501-40C	SP BRIDGE , DRILLED SHAFT - SELF-CONSOLIDATING CON CRETE CLASS 40A	190.00	CY
S501-45A	SP BRIDGE , DRILLED SHAFT - METAL REINFORCEMENT	39,717.00	LB
S501-51A	SP BRIDGE , ANTI-GRAFFITI COATING	8,230.00	SF
S501-51A	SP BRIDGE , ANTI-GRAFFITI COATING	9,150.10	SF
S505-10A	FURNISHING AND INSTALLING H-PILES	1,057.00	FT
S620-05A	LANDSCAPING - WEED CONTROL	10,000.00	CA
S626-41A	PORTABLE TRAFFIC SIGNAL	300.00	DAY
S703-10A	SPECIAL AGGREGATE (FILTER SAND)	2,179.00	TON
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	50,000.00	CA
S900-50B	CONTINGENCY AMOUNT CONSTRUCTION PARTNERING	50,000.00	CA

S901-05A	SP NON-POTABLE WATERLINE CROSSING	4.00	EACH
S901-05B	SP 1000 GAL SAND AND GREASE TRAP	1.00	EACH
S901-05D	SP REMOVE AND RESET MONUMENTS	24.00	EACH
S901-05E	SP ADJUST INLET GRATES	6.00	EACH
S904-05A	SP FIBER OPTIC COMMUNICATIONS	1.00	LS
S904-05B	SP AGGREGATE PRODUCTION QUALITY TESTING	1.00	LS
S904-05C	SP SETTLEMENT MONITORING	150,000.00	LS
S904-05C	SP SETTLEMENT MONITORING	0.50	LS
S904-05D	SP TEMP TRAFFIC SIGNAL PHASING	1.00	LS
S911-05A	SP 6" CONCRETE MOWSTRIP	2,702.00	FT
S911-05B	SP ORANGE CONSTRUCTION FENCE	141.00	FT
S911-05C	SP ABANDON PIPE	1,554.00	FT
S911-05D	SP JACK OR BORE PIPE	776.00	FT
S911-05E	SP 48" STEEL PIPE CASING	776.00	FT
S911-05H	SP INFILTRATION SEEPAGE BED	200.00	FT
S912-05A	SP 1 1/2" - 3" DECORATIVE ROCK MULCH WITH F ABRIC	1,205.00	SY
S912-05B	SP 3/4" DECORATIVE ROCK MULCH WITH FABRIC	1,680.00	SY
S912-05C	SP BICYCLE RAMP	47.00	SY
S915-05B	SP DECORATIVE BRICK PAVERS - BASKET WEAVE P ATTERN	2,518.00	SF
S916-05A	SP SP TRAFFIC CONTROL SUPERVISOR	550.00	DAY
Z629-05A	MOBILIZATION	1.00	LS