

Key No. 19637 - YALE RD, STAGE 4; MP 12.4 TO 13.5  
Cassia County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	5,000.00	CA
110-005A	TRAINING	866.00	HR
201-005A	CLEARING & GRUBBING	19.70	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	5.00	EACH
203-006A	REMOVAL OF SIGN	11.00	EACH
203-075A	REMOVAL OF FENCE	1,378.00	FT
203-125A	REMOVAL OF MISCELLANEOUS ITEMS - ROCK WALL	1.00	LS
204-006A	OBLITERATION OF OLD ROAD	1.00	LS
205-005A	EXCAVATION	168,600.00	CY
205-060A	WATER FOR DUST ABATEMENT	3,465.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	500.00	CY
209-005A	SMALL DITCH	94.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	1,215.00	CY
210-015A	COMPACTING BACKFILL	1,416.00	CY
212-011A	FIBER WATTLE	2,180.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	3.00	EACH
212-105A	WATER AND POLLUTION	5,000.00	CA
213-010A	TOPSOIL	71,317.00	SY
301-005A	GRANULAR SUBBASE	16,528.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	10,946.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	1,900.00	GAL
405-245A	APPROACH	10.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 - NMAS 1/2", PG 64-28	5,850.00	TON
502-025A	CONCRETE CLASS 40-A	230.00	CY
503-005A	METAL REINFORCEMENT	33,774.00	LB
511-005A	CONCRETE WATERPROOF SYSTEM - TYPE D	329.00	SY
578-005A	PRECAST CONCRETE CULVERT - 72' x 8' x 6'	1.00	LS
602-025A	12" PIPE CULVERT	393.00	FT
602-035A	18" PIPE CULVERT	207.00	FT
608-035A	18" APRON FOR PIPE	6.00	EACH
610-045A	FENCE TYPE 5 B	116.00	FT
610-250A	BRACES	1.00	EACH
616-010A	SIGN TYPE B-1	82.20	SF
616-055B	WOOD SIGN POST TYPE D-2	110.40	FT
616-055C	WOOD SIGN POST TYPE D-3 - D-3	19.50	FT
616-080A	REINSTALL SIGN FACE	2.00	EACH
616-085A	REINSTALL SIGN POST	3.00	EACH
616-100A	SIGN BRACES	106.20	LB
617-005A	DELINEATOR TYPE 1	78.00	EACH
617-020A	DELINEATOR TYPE 4	2.00	EACH
618-010A	RIGHT-OF-WAY MARKER	35.00	EACH
618-025A	STREET MONUMENT	6.00	EACH
621-005A	SEED BED PREPARATION	6.87	ACRE
621-010A	SEEDING	6.87	ACRE

621-060A	MULCH PLUS TACKIFIER	13.74	ACRE
624-005A	LOOSE RIPRAP	91.30	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	797.00	SF
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	760.00	HR
626-120A	FLAGGER CONTROL	1,500.00	HR
626-125A	PILOT CAR	500.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	100.00	EACH
630-025A	LONG PAV MKG - WATERBORNE	37,981.00	FT
634-005A	MAILBOX - TYPE B ASSEMBLY	2.00	EACH
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	482.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE - TYPE III	36,200.00	SY
641-005A	BIAXIAL GEOGRID - TYPE II	339.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	10,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	5,000.00	CA
Z629-05A	MOBILIZATION	1.00	LS