

Key No. 19973 - I-84, DECLO POE EB
Cassia County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	18,500.00	CA
107-019A	MONUMENT PRESERVATION	10,000.00	CA
110-005A	TRAINING	1,430.00	HR
201-005A	CLEARING & GRUBBING	12.91	ACRE
203-015A	REM OF BITUMINOUS SURF	6,427.00	SY
203-050B	REM AND DISPOSE ASBESTOS	10,000.00	CA
203-055A	REM OF CONC PAV	1,066.00	SY
203-060A	REM OF CONC SIDEWALK	144.00	SY
203-065A	REM OF CURB	297.00	FT
203-075A	REM OF FENCE	3,081.00	FT
203-080A	REM OF GUARDRAIL/BARRIER	738.00	FT
203-125A	REM OF MISCELLANEOUS ITEMS	1.00	LS
203-130A	REMOVAL OF PAV MARKINGS	5,245.00	FT
203-135A	REMOVAL OF SIGN	25.00	EACH
205-005A	EXCAVATION	22,728.00	CY
205-005B	EXCAVATION ROCK REMOVAL	700.00	CY
205-030A	BORROW	3,107.00	CY
205-040A	GRANULAR BORROW	133.00	CY
205-060A	WATER FOR DUST ABATEMENT	2,107.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	1,217.00	CY
210-010A	STR EXCAVATION SCH NO. 2	118.00	CY
210-015A	COMPACTING BACKFILL	39.50	CY
212-011A	FIBER WATTLE	7,944.00	FT
212-040A	BERM	7,778.00	FT
212-060A	STABILIZED CONST ENTRANCE	1.00	EACH
212-095A	INLET PROTECTION	1.00	EACH
301-005A	GRANULAR SUBBASE	42,049.00	TON
303-022A	3/4" AGGR TY B FOR BASE	25,435.00	TON
307-006A	OPEN-GRADED BASE CLASS II	121.00	CY
405-240A	MISC PAV	2,320.00	SY
405-410A	SUPERPAVE HMA PAV CL SP-T	255.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	4,253.00	TON
405-455A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5	11,571.00	TON
409-015A	CONC PAV	400.00	SY
420-015A	GRIND CONCRETE PAVEMENT	400.00	SY
602-035A	18" PIPE CULV	264.00	FT
605-630A	INLET TY 8	1.00	EACH
605-635A	ADJUST MANHOLE COVERS	5.00	EACH
610-030A	FENCE TY 3 B	3,195.00	FT
612-005D	W-BEAM GUARDRAIL	1,595.00	FT
612-110A	GUARDRAIL ANCHOR	2.00	EACH
612-115B	GUARDRAIL TERMINAL, FLARED	3.00	EACH

612-120B	GUARDRAIL TRANSITION, HIGH SPEED	1.00	EACH
612-150A	CONCRETE BARRIER	1,889.00	FT
612-155A	CONCRETE TERMINAL TY A	1.00	EACH
613-015A	CRASH CUSHION, SACRIFICIAL-SAND	3.00	EACH
614-015A	SIDEWALK	111.00	SY
614-025A	CURB RAMP	12.40	SY
615-492A	CURB & GUTTER TYPE 2	316.00	FT
616-010A	SIGNS TY B	214.40	SF
616-015A	SIGNS TY C	607.50	SF
616-031A	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-035A	SIGN BRACKETS & BRACE ANGLES	263.60	LB
616-040A	BRKAWY STL SIGN POST TY A	3,131.20	LB
616-045A	BRKAWY STL SIGN POST TY B	1,933.80	LB
616-060A	BRKAWY STL SIGN POST INST TY A	20.00	EACH
616-065A	BRKAWY STL SIGN POST INST TY B	19.00	EACH
617-005A	DELINEATOR TY 1	59.00	EACH
617-045A	DELINEATOR TY 9	32.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
621-001A	SEED	6.85	ACRE
621-005A	SEED BED PREPARATION	6.85	ACRE
621-010A	SEEDING	6.85	ACRE
621-015A	MULCHING	6.85	ACRE
621-020A	MULCH ANCHORING (MECHANICAL)	5.61	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	1.24	ACRE
621-035A	FERTILIZING	6.85	ACRE
624-005A	LOOSE RIPRAP	71.40	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	760.00	SF
626-040A	BARRICADE TY 3	4.00	EACH
626-050A	DRUMS	75.00	EACH
626-076A	ARROW BOARD TY C	1,500.00	HR
626-100B	MISC TEMPORARY TRAF CONT ITEMS	2,500.00	CA
626-105A	TRAF CNTL MAINTENANCE	1,500.00	HR
626-111A	TEMP RIGID RAISED PAVEMENT MARKERS	230.00	EACH
626-116A	TEMP CONCRETE BARRIER	4,475.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	2,325.00	FT
626-135A	WEIGHTED BASE TUBULAR MARKERS	175.00	EACH
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	52,136.00	FT
631-010A	RUMBLE STRIPS	0.23	MILE
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	214.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	56,761.00	SY
645-015A	C4 SP3 & SP5 FIELD LAB	1.00	LS
654-025A	COMPOST	6.85	ACRE
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	5,000.00	CA
675-015A	DIRECTED SURVEYING CREW	5,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS

S501-15A	RETAINING WALL	6,087.00	SF
S901-05A	SP J-BOX SIZE C	26.00	EACH
S901-05B	SP J-BOX SIZE D	2.00	EACH
S901-05C	SP REM & RESET SIGN	1.00	EACH
S901-05D	SP FUSION SPLICE	20.00	EACH
S901-05E	SP TEST FIBER	5.00	EACH
S901-05F	SP FIBER TERMINATION	5.00	EACH
S901-05H	SP 4.5" Orifice Plate	1.00	EACH
S901-05I	SP REMOTE DISPLAY	1.00	EACH
S901-05J	SP TRAFFIC SIGNAL	2.00	EACH
S901-05M	SP WEIGH-IN-MOTION AND CONSTRUCTION	1.00	EACH
S904-05A	SP TRUCK CONTAINMENT PAD	1.00	LS
S904-05B	SP POE BUILDING	1.00	LS
S904-05C	SP SEPTIC SEWER SYSTEM	1.00	LS
S904-05D	SP SCALE & SCALE PIT	1.00	LS
S904-05F	SP LED OPEN CLOSED SIGN	1.00	LS
S904-05G	SP WATER SYSTEM	1.00	LS
S911-05A	SP 2-INCH CONDUIT	11,735.00	FT
S911-05F	SP INFILTRATON TRENCH	5,225.00	FT
S911-05G	SP FIBER OPTIC CABLE	594.00	FT
S911-05H	SP 18" PIPE JACKING	136.00	FT
S913-05A	SP LANDSCAPE ROCK	18.64	CY
Z629-05A	MOBILIZATION	1.00	LS