

Key No. 20083 - I-15, FORT HALL IC #80  
Bannock & Bingham County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	10,000.00	CA
110-005A	TRAINING	2,500.00	HR
201-010A	CLEARING & GRUBBING	1.00	LS
203-005A	REM OF OBSTRUCTIONS	1.00	LS
203-020A	REM OF BRIDGE	1.00	EACH
203-035A	REM OF CONC CULV (MONOLITHIC)	6.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	50,000.00	CA
203-075A	REM OF FENCE	2,136.00	FT
203-080A	REM OF GUARDRAIL/BARRIER	6,698.00	FT
203-135A	REMOVAL OF SIGN	51.00	EACH
204-006A	OBLITERATION OF OLD ROAD	1.00	LS
205-010A	EXCAVATION SCHEDULE NO.1	42,468.00	CY
205-015A	EXCAVATION SCHEDULE NO.2	13,300.00	CY
205-040A	GRANULAR BORROW	13,277.00	CY
205-095A	SOFT SPOT REPAIR	7,500.00	CA
209-005A	SMALL DITCH	3,534.00	FT
210-005A	STR EXCAVATION SCH NO. 1	6,895.00	CY
210-015A	COMPACTING BACKFILL	5,633.00	CY
212-011A	FIBER WATTLE	3,000.00	FT
251-005A	MIGRATORY BIRD COMPLIANCE	10,000.00	CA
301-010A	GRANULAR SUBBASE	39,444.00	CY
303-052A	3/4" AGGR TY B FOR BASE	16,145.00	CY
405-245A	APPROACH	4.00	EACH
405-410A	SUPERPAVE HMA PAV CL SP-T	7,197.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	14,807.00	TON
502-165A	CONC CL 40 AF SCH NO. 1	106.00	CY
502-385A	PRESTR DECK BULB TEE GIRDER (71" W x 49" D)	2,867.00	FT
502-430A	CONC PARAPET 42" SINGLE SLOPE W/FENCE	262.00	FT
502-430B	CONC PARAPET MEDIAN	262.00	FT
502-430C	CONC PARAPET FOR COMBINATION RAILING W/FENCE	262.00	FT
502-435A	APPROACH SLAB	411.00	SY
503-010A	METAL REINF SCH NO. 1	13,572.00	LB
503-015A	METAL REINF SCH NO. 2	6,863.00	LB
503-020A	EPOXY COATED METAL REINF	20,863.00	LB
505-105A	PROV&DRIV 14" DIA STEEL SHELL PILE	3,195.00	FT
505-155A	PROV&DRIV TEST STEEL SHELL PILE (14")	155.00	FT
505-215B	SPLICE STEEL PILE DURING DRIVING	2.00	EACH
507-010A	BRIDGE BEARINGS LAMINATED (Size__ ) 2"x8"x24"	52.00	EA
509-005A	NON-STRUCTURAL CONC CLASS 15F	13.00	CY
511-005A	CONC WATERPROOF SYS TYPE C	440.00	SY
511-005B	CONC WATERPROOF SYS TYPE D	1,763.00	SY
521-005A	DYNAMIC PILE TESTING	2.00	EA

521-010A	CAPWAP ANALYSIS	4.00	EA
522-005A	CONTROLLED DENSITY FILL	980.00	CY
551-005A	PREPARED & PLACED PPC OVERLAY	2,445.30	SY
551-010A	PPC OVERLAY MATERIAL	50.90	CY
566-005A	COMPRESSION EXPANSION JOINT	172.00	FT
575-005A	TEXTURED CONCRETE SURFACE	174.00	SY
576-005A	(GFRP) REINFORCEMENT GLASS FIBER REINFORCED POLYMER	983.00	FT
578-005A	PRECAST CONCRETE CULVERT (TWIN 12' X 10')	1.00	LS
578-005B	PRECAST CONCRETE CULVERT (14' X 5.5')	1.00	LS
584-005A	TEMPORARY SHORING FT HALL IC BRIDGE	1.00	LS
584-005B	TEMPORARY SHORING ROSS FORK CR	1.00	LS
584-005C	TEMPORARY SHORING TOWN LATERAL	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
602-025A	12" PIPE CULV	40.00	FT
602-045A	24" PIPE CULV	255.00	FT
605-500A	CATCH BASIN TY 1	2.00	EACH
605-630A	INLET TY 8	1.00	EACH
608-025A	12" APRON FOR PIPE	2.00	EACH
608-045A	24" APRON FOR PIPE	1.00	EACH
610-010A	FENCE TY 1 A	200.00	FT
610-030A	FENCE TY 3 B	1,549.00	FT
610-250A	BRACES	25.00	EACH
611-010A	CATTLE GUARD TY A	4.00	EACH
612-150A	CONCRETE BARRIER	240.00	FT
614-015A	SIDEWALK	568.00	SY
614-025A	CURB RAMP	36.00	SY
615-492A	CURB & GUTTER TYPE 2	952.00	FT
616-010A	SIGNS TY B	613.60	SF
616-015A	SIGNS TY C	2,251.60	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	639.40	LB
616-040A	BRKAWY STL SIGN POST TY A	10,450.30	LB
616-045A	BRKAWY STL SIGN POST TY B	4,072.30	LB
616-050A	BRKAWY STL SIGN POST TY E	333.60	LB
616-060A	BRKAWY STL SIGN POST INST TY A	60.00	EACH
616-065A	BRKAWY STL SIGN POST INST TY B	29.00	EACH
616-070A	BRKAWY STL SIGN POST INST TY E	7.00	EACH
617-005A	DELINEATOR TY 1	145.00	EACH
617-010A	DELINEATOR TY 2	12.00	EACH
617-020A	DELINEATOR TY 4	8.00	EACH
617-055A	MILEPOST TY 2	2.00	EACH
618-010A	RIGHT-OF-WAY MARKER	1.00	EACH
618-025A	STREET MONUMENT	1.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
621-005A	SEED BED PREPARATION	7.36	ACRE
621-010A	SEEDING	7.36	ACRE
624-005A	LOOSE RIPRAP	284.50	CY

626-114A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	24,000.00	HR
626-116A	TEMP CONCRETE BARRIER	1,000.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	500.00	FT
626-118A	TEMP CRASH CUSHION	8.00	EACH
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	668.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	223,858.00	FT
640-010A	RIPRAP/EROSION CONT GEOTEXTILE TYPE II NON-WOVEN	2,643.50	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE Woven TY II SLIT FILM	488.00	SY
650-070A	TIME-LAPSE CAMERA	1.00	EACH
650-070B	TIME-LAPSE CAMERA SERVICE	9.00	MO
654-025A	COMPOST	7.36	ACRE
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	20,000.00	CA
675-015A	DIRECTED SURVEYING CREW	20,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S203-21A	OBLITERATION OF PAV MARKINGS	12,000.00	FT
S501-15A	RETAINING WALL GRAVITY LARGE CONCRETE BLOCK	7,200.00	SF
S501-20A	SP BRIDGE PRECAST COLUMNS	6.00	EACH
S501-30A	SP BRIDGE PRECAST PIER CAP	86.30	FT
S501-30B	SP BRIDGE PRECAST ABUTMENT PILE CAP	172.60	FT
S501-35A	SP BRIDGE GEOCELL RAFT	1,867.80	SY
S501-40A	SP BRIDGE HIGH EARLY STRENGTH CONCRETE CLASS 50F	235.80	CY
S501-40B	SP BRIDGE ROCK SLOPE ARMOR	240.50	CY
S501-51A	SP BRIDGE ANTI-GRAFFITI COATING	24,000.00	SF
S626-31A	TRAF CNTL MONITOR	285.00	DAY
S900-50A	CONTINGENCY AMOUNT WEED CONTROL	20,000.00	CA
S900-50B	CONTINGENCY AMOUNT TEMPORARY EROSION CONTROL	30,000.00	CA
S900-50C	CONTINGENCY AMOUNT INCIDENTAL TRAFFIC CONTROL	30,000.00	CA
S900-50D	CONTINGENCY AMOUNT DIRECTED LANDSCAPING	100,000.00	CA
S900-50E	CONTINGENCY AMOUNT SP GRAVITY WALL AESTHETIC ART TREATMENT	50,000.00	CA
S900-50F	CONTINGENCY AMOUNT TERO TRAINING FEES	469,510.00	CA
S901-05A	SP TYPE C JUNCTION BOX	22.00	EACH
S901-05B	SP TYPE D JUNCTION BOX	6.00	EACH
S904-05A	SP TEMPORARY TRAFFIC CONTROL DESIGN AND OPE RATION	1.00	LS
S904-05B	SP AUTOMATIC TRAFFIC RECORDER	1.00	LS
S904-05C	SP RWIS-SENSOR, TOWER AND CABINET RELOCATIO N	1.00	LS
S904-05E	SP PORTNEUF RIVER WETLAND MITIGATION	1.00	LS
S904-05F	SP UTILITY CORRIDOR	1.00	LS
S911-05A	SP SLIPLNE 24" CONCRETE PIPE SIPHON	430.00	FT
S911-05B	SP INSTALL 2-2" PVC SCH 40 CONDUIT	1,470.00	FT
S911-05C	SP INSTALL 2" HDPE SCH 80 CONDUIT	5,395.00	FT
S911-05D	SP FENCE DECORATIVE PANELS	514.00	FT
S912-05A	SP PERMEABLE DRAINAGE GEOCELL	678.00	SY
S912-05B	SP PERMEABLE SLOPE GEOCELL	305.00	SY
S912-05C	SP IMPERMEABLE SCOUR GEOCELL	488.00	SY

Z629-05A	MOBILIZATION	1.00	LS
----------	--------------	------	----