

Key No. 20230 - EASTSIDE DRIVE BRIDGE  
Valley County

Item No	Description	QTY	Unit
201-010A	CLEARING & GRUBBING	1.00	LS
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	54.00	EACH
203-020A	REM OF BRIDGE	1.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	10,000.00	CA
203-125C	REM OF MISCELLANEOUS ITEMS (48" CMP)	74.00	FT
203-135A	REMOVAL OF SIGN	8.00	EACH
205-005A	EXCAVATION	525.00	CY
205-040A	GRANULAR BORROW	40.00	CY
205-060A	WATER FOR DUST ABATEMENT	18.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	40.00	CY
210-005A	STR EXCAVATION SCH NO. 1	250.00	CY
210-005B	STR EXCAVATION SCH NO. 1 CULVERT	245.00	CY
210-005B	STR EXCAVATION SCH NO. 1 ROCK	63.00	CY
210-015A	COMPACTING BACKFILL CULVERT	40.00	CY
210-015A	COMPACTING BACKFILL	124.00	CY
212-011A	FIBER WATTLE	1,368.00	FT
212-020A	SILT FENCE	50.00	FT
212-060A	STABILIZED CONST ENTRANCE	2.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	5,000.00	CA
301-005A	GRANULAR SUBBASE	6,300.00	TON
303-022A	3/4" AGGR TY B FOR BASE	1,350.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	20.00	GAL
405-425A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-2	130.00	TON
502-140A	CONC CL 40-A SCH NO. 1	70.00	CY
502-310A	CONC CL 40 AF SCH NO. 2	30.00	CY
502-385A	PRESTR DECK BULB TEE GIRDER 80 1/2" TOP FLANGE, 49" DEPTH	565.00	FT
503-010A	METAL REINF SCH NO. 1	11,900.00	LB
503-015A	METAL REINF SCH NO. 2	2,944.00	LB
503-020A	EPOXY COATED METAL REINF	947.00	LB
504-035A	PEDESTRIAN / BICYCLE RAILING	63.00	FT
505-100A	PROV&DRIV 12" DIA STEEL SHELL PILE	469.00	FT
507-005A	BRIDGE BEARINGS PLAIN (Size__ ) 10"x22"x1/2"	10.00	EA
511-005A	CONC WATERPROOF SYS TYPE D	61.00	SY
511-005B	CONC WATERPROOF SYS TYPE D	385.00	SY
520-005A	PREDRILLING FOR PILING IN SOIL	196.00	FT
520-010A	PREDRILLING FOR PILING IN ROCK	266.00	FT
560-005A	DEWATERING FOUNDATION	1.00	LS
575-005A	TEXTURED CONCRETE SURFACE	80.00	SY
578-005A	PRECAST CONCRETE CULVERT	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
616-010A	SIGNS TY B	12.00	SF
616-055A	BRKAWY WOOD SIGN POST TY D	0.06	MFBM

616-080A	REINSTALL SIGNS	6.00	EACH
621-010A	SEEDING	0.27	ACRE
621-025A	MULCH ANCHORING (TACKIFIER) TEMP	0.27	ACRE
624-005A	LOOSE RIPRAP D=1.5 FT	7.50	CY
624-005B	LOOSE RIPRAP	95.00	CY
624-005B	LOOSE RIPRAP D=0.5 FT	5.10	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	282.00	SF
626-040A	BARRICADE TY 3	6.00	EACH
626-100B	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	250.00	HR
626-114A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	400.00	HR
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	340.50	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE TYPE III	546.00	SY
641-005A	BIAXIAL GEOGRID TYPE II	850.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	2,000.00	CA
675-015A	DIRECTED SURVEYING CREW	2,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-30A	SP BRIDGE THREE TUBE CURB MOUNT RAIL	230.00	FT
S501-30B	SP BRIDGE ROCK SOCKETED PILES	441.00	FT
S501-51A	SP BRIDGE ANTI-GRAFFITI COATING	740.00	SF
S501-95A	GEOSYNTHETIC REINFORCED ABUT BACKFILL	333.00	CY
S900-50A	CONTINGENCY AMOUNT MISC WORK	10,000.00	CA
S913-05A	SP ROCK MULCH	220.00	CY
S913-05B	SP REINFORCED ROCK FILL PAD	176.00	CY
Z629-05A	MOBILIZATION	1.00	LS