

Key No. 20384 - SH-55 FLEMING CR BR  
Boise County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	20,000.00	CA
107-019A	MONUMENT PRESERVATION	2,000.00	CA
110-005A	TRAINING	700.00	HR
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	12.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	3,000.00	SY
203-020A	REM OF BRIDGE	1.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	10,000.00	CA
203-130A	REMOVAL OF PAV MARKINGS	6,400.00	FT
205-005A	EXCAVATION	6,500.00	CY
205-005B	EXCAVATION ROCK	700.00	CY
205-060A	WATER FOR DUST ABATEMENT	130.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	100.00	CY
210-005A	STR EXCAVATION SCH NO. 1	2,400.00	CY
210-005B	STR EXCAVATION SCH NO. 1 (ROCK)	30.00	CY
210-015A	COMPACTING BACKFILL	704.00	CY
212-011A	FIBER WATTLE	340.00	FT
212-020A	SILT FENCE	1,669.00	FT
212-060A	STABILIZED CONST ENTRANCE	2.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	2,500.00	CA
301-005A	GRANULAR SUBBASE	5,200.00	TON
303-022A	3/4" AGGR TY B FOR BASE	3,000.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	680.00	GAL
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	2,000.00	TON
431-005A	COLD MILLING	2,000.00	SY
502-430A	CONC PARAPET	120.00	FT
502-465A	PRESTR SLAB PRECAST VOIDED SLAB (2'-2")	720.00	FT
505-030A	PROV&DRIV STEEL H PILE (12 X 74)	176.00	FT
505-185A	PROV&DRIV TEST PILE (HP-12 x 74)	44.00	FT
507-005A	BRIDGE BEARINGS PLAIN (Size__ ) (1/2"x6"x40")	24.00	EA
511-005A	CONC WATERPROOF SYS TYPE D	56.00	SY
520-010A	PREDRILLING FOR PILING IN ROCK	150.00	FT
521-005A	DYNAMIC PILE TESTING	2.00	EA
521-010A	CAPWAP ANALYSIS	2.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY	301.00	SY
551-010A	PPC OVERLAY MATERIAL	8.00	CY
560-005A	DEWATERING FOUNDATION	1.00	LS
577-005A	PILE SLEEVES CASING FOR INTEGRAL ABUT PILES	54.00	FT
584-005A	TEMPORARY SHORING FOR BRIDGE	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
612-005D	W-BEAM GUARDRAIL	1,366.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH

613-020A	CRASH CUSHION, SACRIFICIAL-WATER FILLED	4.00	EACH
615-260A	CURB TYPE 5	25.00	FT
616-010A	SIGNS TY B	57.50	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	145.90	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.15	MFBM
617-005A	DELINEATOR TY 1	5.00	EACH
617-045A	DELINEATOR TY 9	45.00	EACH
621-005A	SEED BED PREPARATION	0.44	ACRE
621-010A	SEEDING	0.44	ACRE
621-015A	MULCHING	0.44	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	0.44	ACRE
624-005A	LOOSE RIPRAP	168.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	485.00	SF
626-050A	DRUMS	32.00	EACH
626-100B	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	2,160.00	HR
626-115C	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	1.00	LS
626-116A	TEMP CONCRETE BARRIER	2,548.00	FT
626-120A	FLAGGER CONTROL	200.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	22.00	EACH
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	18,642.00	FT
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	466.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	1,800.00	CA
675-015A	DIRECTED SURVEYING CREW	2,300.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-17A	MSE RETAINING WALL WELDED WIRE	11,288.00	SF
S501-25A	SP BRIDGE PRECAST ABUT PILE CAP AND WING WALLS	1.00	LS
S501-40A	SP BRIDGE PARTIALLY GROUTED RIPRAP	215.00	CY
S501-40B	SP BRIDGE UHPC	2.00	CY
S501-95A	GEOSYNTHETIC REINFORCED ABUT BACKFILL	225.00	CY
S626-41A	PORTABLE TRAFFIC SIGNAL	45.00	DAY
S900-50A	CONTINGENCY AMOUNT MISC WORK	5,000.00	CA
S900-50B	CONTINGENCY AMOUNT DIRECTED SIGNAL TIMING MONITOR	10,000.00	CA
S900-50C	CONTINGENCY AMOUNT PARTNERING	10,000.00	CA
S904-05A	SP TURBIDITY & PH MONITORING	1.00	LS
S904-05B	SP TEMPORARY SHORING	1.00	LS
S914-05A	SP ROCK CAP	100.00	TON
Z629-05A	MOBILIZATION	1.00	LS