

Key No. 20404 - SH-21, QUARTZ CR (JAYPE) BRIDGE  
Clearwater County

Item No	Description	QTY	Unit
104-005A	PARTNERING	30,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	10,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	5,000.00	CA
201-005A	CLEARING & GRUBBING	1.00	ACRE
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-010A	ASBESTOS REMOVAL AND DISPOSAL	5,000.00	CA
203-020A	REMOVAL OF BRIDGE - FULL	1.00	EACH
205-005A	EXCAVATION	860.00	CY
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	282.00	CY
210-015A	COMPACTING BACKFILL	13.50	CY
212-011A	FIBER WATTLE	630.00	FT
212-020A	SILT FENCE	2,040.00	FT
212-105A	WATER AND POLLUTION	30,000.00	CA
215-005A	GEOSYNTH REINFORCED ABUTMENT BACKFILL	234.00	CY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	3,280.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	120.00	GAL
405-245A	APPROACH	1.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	560.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	86.30	CY
502-430A	CONCRETE PARAPET 42" SINGLE SLOPE	96.60	FT
502-465A	PRESTRESSED SLAB 48" WIDTH X 18" DEPTH	434.80	FT
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	11,795.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	497.00	LB
505-110A	PROVIDE & DRIVE 16" DIA STEEL SHELL PILE	630.00	FT
505-215B	SPLICE STEEL PILE DURING DRIVING	24.00	EACH
551-005A	PREPARED & PLACED PPC OVERLAY	178.50	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	5.40	CY
560-005A	DEWATERING FOUNDATION	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
602-045A	24" PIPE CULVERT	100.00	FT
612-005A	W-BEAM GUARDRAIL	512.50	FT
612-115B	GUARDRAIL TERMINAL, FLARED	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
618-025A	STREET MONUMENT	3.00	EACH
621-005A	SEED BED PREPARATION	0.25	ACRE
621-010A	SEEDING	0.25	ACRE
621-015A	MULCHING	0.25	ACRE
621-035A	FERTILIZING	0.25	ACRE
624-005A	LOOSE RIPRAP	230.00	CY
626-100B	MISC TEMPORARY TRAF CONT ITEMS	15,000.00	CA
630-025A	LONG PAV MKG - WATERBORNE	10,000.00	FT
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	340.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE TYPE III	3,000.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	15,000.00	CA

677-005A	RECORD DRAWINGS	1.00	LS
S501-25A	SP BRIDGE TEMPORARY SHOOFLY & TEMPORARY BRIDGE	1.00	LS
S501-40A	SP BRIDGE UHPC	2.90	CY
S904-05A	SP TEMPORARY TRAFFIC CONTROL DESIGN AND OPE RATIONS	1.00	LS
S904-05B	SP VEGETATED RIPRAP - LIVE WILLOW & BIRCH P LANTIGS	1.00	LS
Z629-05A	MOBILIZATION	1.00	LS