

Key No. 20506 - SH-55C, STATE ST TO PAYETTE RV BR
Boise and Ada County

Item No	Description	QTY	Unit
104-005A	PARTNERING	20,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	13,000.00	CA
201-005A	CLEARING & GRUBBING	4.36	ACRE
203-006A	REMOVAL OF SIGN	8.00	EACH
203-060A	REMOVAL OF CONCRETE SIDEWALK	117.00	SY
203-070A	REMOVAL OF CURB & GUTTER	196.00	FT
203-080A	REMOVAL OF GUARDRAIL	920.00	FT
203-123A	REMOVAL OF MISCELLANEOUS ITEMS PAVEMENT MARKINGS	200.00	FT
205-005A	EXCAVATION	12,750.00	CY
205-040A	GRANULAR BORROW	4,952.00	CY
205-100A	GUARDRAIL TERMINAL GRADING	3.00	EACH
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	7,135.00	CY
210-015A	COMPACTING BACKFILL	3,252.00	CY
212-011A	FIBER WATTLE	2,805.00	FT
212-095A	INLET PROTECTION	70.00	EACH
212-105A	WATER AND POLLUTION	20,000.00	CA
301-005A	GRANULAR SUBBASE	18,532.73	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	4,798.53	TON
304-020A	EXCAVATION OF SOFT SPOTS	20.00	CY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	52,081.00	GAL
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	74,673.77	TON
431-005A	COLD MILLING	424,000.00	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	87,628.81	LB
505-105A	PROVIDE & DRIVE 14" DIA STEEL SHELL PILE	6,050.00	FT
505-155A	PROV&DRIV TEST STEEL SHELL PILE (14")	163.00	FT
505-215A	SPLICE STEEL PILE BEFORE DRIVING	2.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING	224.00	EACH
511-005A	CONCRETE WATERPROOF SYSTEM	995.00	SY
521-005A	DYNAMIC PILE TESTING	114.00	EA
521-010A	CAPWAP ANALYSIS	116.00	EA
574-005A	ANTI-GRAFFITI COATING	11,423.00	SF
578-005A	PRECAST CONCRETE CULVERT	1.00	LS
584-005A	TEMPORARY SHORING APPROX 3700 SF	1.00	LS
605-455A	MANHOLE TYPE A	1.00	EACH
605-635A	ADJUST MANHOLE COVERS	4.00	EACH
612-005A	W-BEAM GUARDRAIL	2,463.18	FT
612-050A	GUARDRAIL TERMINAL	6.00	EACH
612-115B	GUARDRAIL TERMINAL, FLARED	3.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
612-150A	CONCRETE BARRIER	138.00	FT
614-015A	SIDEWALK	34.00	SY
614-025A	CURB RAMP	100.00	SY

615-257A	CURB TYPE 2	431.68	FT
615-492A	CURB & GUTTER TYPE 2	196.00	FT
616-010A	SIGNS TY B	167.00	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	347.00	LB
616-045A	BRKAWY STL SIGN POST TY B	750.00	LB
616-050A	BRKAWY STL SIGN POST TY E	25.00	LB
616-055A	BRKAWY WOOD SIGN POST TY D	1.75	MFBM
616-065A	BRKAWY STL SIGN POST INST TY B	7.00	EACH
616-080A	REINSTALL SIGNS	9.00	EACH
621-005A	SEED BED PREPARATION	4.36	ACRE
621-010A	SEEDING	4.36	ACRE
621-015A	MULCHING	4.36	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	4.36	ACRE
624-005A	LOOSE RIPRAP	5.33	CY
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	940.00	SF
630-020A	LONG PAV MKG- PREFORMED THERMOPLASTIC	360.00	FT
630-025A	LONG PAV MKG - WATERBORNE	21,000.00	FT
645-015A	C4 SP3 & SP5 FIELD LAB	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	20,000.00	CA
675-010A	DIRECTED SURVEYING FIELD MEASUREMENT AND OFFICE COMPUTATION	20,000.00	CA
676-005A	RECORD AND REESTABLISH PAV MARKINGS - W	800,000.00	FT
676-010B	RECORD AND REESTABLISH PAV MARKINGS - PT	2,000.00	SF
S501-17A	MSE RETAINING WALL	2,673.00	SF
S501-18A	COPING FOR MSE WALL	335.00	FT
S501-40A	SP BRIDGE CONCRETE CLASS 60A SCH. NO. 1	451.10	CY
S501-40B	SP BRIDGE CONCRETE CLASS 65A SCH. NO. 1	17.80	CY
S900-50A	CONTINGENCY AMOUNT DIRECTED TRAFFIC CONTROL	40,000.00	CA
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
Z629-05A	MOBILIZATION	1.00	LS