

Key No. 20513 - US-12 CLEARWATER RV MEMORIAL BRIDGE
Nez Perce County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	45,000.00	CA
110-005A	TRAINING	4,296.00	HR
201-010A	CLEARING & GRUBBING	1.00	LS
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS INCLUDING STUMPS	9.00	EACH
203-020A	REM OF BRIDGE SUPERSTRUCTURE AND ABUTMENTS ONLY (87,000 SF)	1.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	50,000.00	CA
203-055A	REM OF CONC PAV	1,685.00	SY
203-060A	REM OF CONC SIDEWALK	410.00	SY
203-070A	REM OF CURB & GUTTER	580.00	FT
203-135A	REMOVAL OF SIGN	8.00	EACH
205-005A	EXCAVATION	1,052.00	CY
205-060A	WATER FOR DUST ABATEMENT	86.00	MG
212-011A	FIBER WATTLE	1,190.00	FT
212-060A	STABILIZED CONST ENTRANCE	2.00	EACH
212-095A	INLET PROTECTION	9.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	25,000.00	CA
303-022A	3/4" AGGR TY B FOR BASE	1,186.00	TON
411-005A	URBAN CONC PAV 1.10' DEPTH	2,003.00	SY
502-140A	CONC CL 40-A SCH NO. 1	67.00	CY
502-150A	CONC CL 60 SCH NO. 1(Obsolete)	41.00	CY
502-310A	CONC CL 40 AF SCH NO. 2	3,149.00	CY
502-430A	CONC PARAPET	2,811.00	FT
502-435A	APPROACH SLAB	375.00	SY
503-010A	METAL REINF SCH NO. 1	29,573.00	LB
503-015A	METAL REINF SCH NO. 2	128,992.00	LB
503-020A	EPOXY COATED METAL REINF	458,622.00	LB
504-005A	STL BRIDGE (APPROX WT) (APPROX WT 2,591,000 LB)	1.00	LS
504-035A	PEDESTRIAN / BICYCLE RAILING	3,000.00	FT
505-040A	PROV&DRIV STEEL H PILE (14 X 102)	864.00	FT
505-195A	PROV&DRIV TEST PILE (HP-14 x 102)	216.00	FT
505-205A	PROV&INST PILE SHOES OR TIPS	28.00	EACH
507-010A	BRIDGE BEARINGS LAMINATED (Size__) SIZE VARIES	128.00	EA
521-005A	DYNAMIC PILE TESTING	4.00	EA
521-010A	CAPWAP ANALYSIS	8.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY	9,994.00	SY
551-010A	PPC OVERLAY MATERIAL	208.00	CY
567-005A	STRIP SEAL EXPANSION JOINT SIZE VARIES	398.00	FT
576-005A	(GFRP) REINFORCEMENT	820.00	FT
579-005A	BOND REINFORCING STEEL	1.00	LS
582-005A	PATCH AND REPAIR SURFACE	100.00	SF
584-005A	TEMPORARY SHORING	1.00	LS

586-005A	UTILITY CONDUIT	1.00	LS
605-025A	12" STORM SEWER PIPE	245.00	FT
605-035A	18" STORM SEWER PIPE	97.00	FT
605-455A	MANHOLE TY A	1.00	EACH
605-525A	CATCH BASIN TY 3A	6.00	EACH
605-615A	INLET TY 3	1.00	EACH
609-025A	MINOR STR CONCRETE HEADWALL	1.00	EACH
610-005A	FENCE A ORANGE SAFETY	997.00	FT
612-175A	CAST-IN-PLACE CONCRETE BARRIER	149.00	FT
614-015A	SIDEWALK	196.00	SY
616-010A	SIGNS TY B	30.00	SF
616-080A	REINSTALL SIGNS	1.00	EACH
617-050A	MILEPOST TY 1	2.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
623-005A	CONC SLOPE PAVING	30.00	SY
624-005A	LOOSE RIPRAP D50=12"	45.00	CY
626-100B	MISC TEMPORARY TRAF CONT ITEMS DIRECTED TRAFFIC CONTROL	20,000.00	CA
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	96.00	SF
630-025B	LONGITUDINAL PAV MKG- PREFORMED THERMO	13,332.00	FT
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	111.00	SY
650-070A	TIME-LAPSE CAMERA	2.00	EACH
650-070B	TIME-LAPSE CAMERA SERVICE	36.00	MO
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	2,500.00	CA
675-015A	DIRECTED SURVEYING CREW	10,000.00	CA
676-005A	RECORD OF EXISTING PAVEMENT MARKINGS	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S501-17A	MSE RETAINING WALL	3,871.00	SF
S501-18A	COPING FOR MSE WALL	166.00	FT
S501-20A	SP BRIDGE PRECAST PIER CAP	22.00	EACH
S501-30A	SP BRIDGE SIDEWALK AND COPING FOR MSE RETAINING WALL	189.00	FT
S501-40A	SP BRIDGE RIPRAP	3,235.00	CY
S501-40B	SP BRIDGE FILTER LAYER	785.00	CY
S501-51B	SP BRIDGE ANTI-GRAFFITI COATING	86,300.00	SF
S900-50A	CONTINGENCY AMOUNT EXISTING JOINT REPLACEMENT WORK	135,000.00	CA
S900-50B	CONTINGENCY AMOUNT CONCRETE PIER REPAIR WORK	15,000.00	CA
S900-50D	CONTINGENCY AMOUNT RAILROAD SERVICES	150,000.00	CA
S900-50E	CONTINGENCY AMOUNT FORMAL PARTNERING	25,000.00	CA
S900-50F	CONTINGENCY AMOUNT DIRECTED WINTER MAINTENANCE	100,000.00	CA
S901-05A	SP SPLICE VAULT	2.00	EACH
S901-05B	SP INFILTRATOR MANHOLE	1.00	EACH
S901-05C	SP FUSION SPLICE	2.00	EACH
S901-05D	SP TEST FIBER OPTIC CABLE	2.00	EACH
S901-05E	SP LEWISTON TYPE 1A CATCH BASIN	3.00	EACH
S901-05F	SP TEST FIBER OPTIC WORKSHEET	2.00	EACH
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS

S904-05B	SP NAVIGATION LIGHTING	1.00	LS
S904-05C	SP WATER QUALITY ECOLOGY BLOCK SYSTEM	1.00	LS
S904-05D	SP INSTALL RADAR TYPE AUTOMATIC TRAFFIC REC ORDER	1.00	LS
S904-05G	SP WATER VESSEL DIVERSION REQUIREMENTS	1.00	LS
S904-05H	SP MIGRATORY BIRD COMPLIANCE	1.00	LS
S904-05J	SP BRIDGE IDENTIFICATION PLAQUES	1.00	LS
S904-05K	SP PEDESTRIAN AND BICYCLE SHUTTLE	1.00	LS
S911-05A	SP CURB & GUTTER TYPE 2 (MOD)	332.00	FT
S911-05B	SP CONDUIT (2" RPC)	360.00	FT
S911-05C	SP INSTALL 12-FIBER CABLE	2,000.00	FT
S914-05A	SP Superpave HMA Pav CL SP-T	53.00	TON
S915-05A	SP LANDSCAPE ROCK	24,459.00	SF
Z629-05A	MOBILIZATION	1.00	LS