

Key No. 20547, 20186, 21872 - I-15 INKOM CORRIDOR IMPROVEMENTS
Bannock County

Item No	Description	QTY	Unit
104-005A	PARTNERING	90,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	70,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	40,000.00	CA
110-005A	TRAINING	4,450.00	HR
201-005A	CLEARING & GRUBBING	17.16	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	36.00	EACH
203-002A	REMOVAL OF OBSTRUCTIONS (CATTLE GUARD)	2.00	EACH
203-006A	REMOVAL OF SIGN	65.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	94,438.00	SY
203-020A	REMOVAL OF BRIDGE - FULL (UPRR BRIDGES)	2.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL (WEST INKOM IC)	2.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL (MAIN STREET BRIDGES)	2.00	EACH
203-060A	REMOVAL OF CONCRETE SIDEWALK	375.00	SY
203-065A	REMOVAL OF CURB	562.00	FT
203-070A	REMOVAL OF CURB & GUTTER	701.00	FT
203-075A	REMOVAL OF FENCE	21,846.00	FT
203-080A	REMOVAL OF GUARDRAIL	14,734.00	FT
203-080B	REMOVAL OF BARRIER	680.00	FT
203-090A	REMOVAL OF INLET	10.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (PIPE)	1,597.70	FT
203-123B	REMOVAL OF MISCELLANEOUS ITEMS (CABLE BARRIER)	986.00	FT
203-130B	REMOVAL OF PAVEMENT MARKINGS	7,703.00	SF
205-005A	EXCAVATION	67,803.00	CY
205-040A	GRANULAR BORROW	68,451.00	CY
205-060A	WATER FOR DUST ABATEMENT	8,930.00	MG
205-095A	SOFT SPOT REPAIR	35,000.00	CA
209-005A	SMALL DITCH	370.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1 (PLAN QUANTITY)	1,121.00	CY
210-015A	COMPACTING BACKFILL (PLAN QUANTITY)	779.00	CY
212-011A	FIBER WATTLE	17,536.00	FT
212-020A	SILT FENCE	2,164.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	5.00	EACH
212-095A	INLET PROTECTION (INSERT)	25.00	EACH
212-105A	WATER AND POLLUTION	50,000.00	CA
212-110A	WATER POLLUTION CONTROL MANAGER	1.00	LS
213-010A	TOPSOIL	52,624.40	SY
215-005A	GEOSYNTH REINFORCED ABUTMENT BACKFILL (PLAN QUANTITY)	614.00	CY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	27,000.00	CA
301-005A	GRANULAR SUBBASE	81,199.00	TON
301-010A	GRANULAR SUBBASE (PLAN QUANTITY)	779.00	CY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	95,395.00	TON
308-005A	CEMENT RECYCLED ASPHALT BASE STAB (CLASS I)	41,827.00	SY
405-245A	APPROACH	5.00	EACH
405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T	1,060.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	4,066.00	TON

405-455A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5	70,130.00	TON
409-015A	CONCRETE PAVEMENT	400.00	SY
420-015A	GRIND CONCRETE PAVEMENT	400.00	SY
431-005A	COLD MILLING	41,827.00	SY
502-065A	CONCRETE CLASS 40 AF	41.00	CY
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1 (PLAN QUANTITY)	637.80	CY
502-145A	CONCRETE CLASS 50 SCHEDULE NO. 1 (CLASS 50 A) (PLAN QUANTITY)	172.30	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2 (PLAN QUANTITY)	2,590.50	CY
502-340A	CONCRETE CLASS 60 F SCHEDULE NO. 2 (CLASS 60 AF) (PLAN QUANTITY)	461.70	CY
502-375A	PRESTRESSED BULB TEE GIRDER (37" TOP FLANGE 30" DEPTH) (PLAN QUANTITY)	760.00	FT
502-430A	CONCRETE PARAPET (42" SINGLE SLOPE) (PLAN QUANTITY)	3,123.00	FT
502-435A	APPROACH SLAB (PLAN QUANTITY)	1,239.90	SY
502-515A	THERMAL CONTROL PLAN	1.00	LS
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1 (PLAN QUANTITY)	253,479.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2 (PLAN QUANTITY)	305,074.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT (PLAN QUANTITY)	313,728.00	LB
504-005A	STEEL BRIDGE (APPROXIMATE WEIGHT 196,100 LBS, MAIN ST REET BRIDGES)	1.00	LS
504-005A	STEEL BRIDGE (APPROXIMATE WEIGHT 2,629,334 LBS, UPRR BRIDGES)	1.00	LS
505-045A	PROVIDE & DRIVE STEEL H PILE (14 X 117)	3,685.00	FT
505-100A	PROVIDE & DRIVE 12" DIA STEEL SHELL PILE	1,428.00	FT
505-150A	PROV&DRIV TEST STEEL SHELL PILE (12")	273.00	FT
505-197A	PROVIDE & DRIVE TEST PILE (HP-14 x 117)	321.00	FT
505-205C	PROVIDE & INSTALL PILE SHOES OR TIPS	80.00	EACH
505-215A	SPLICE STEEL PILE BEFORE DRIVING (HP 14 x 117)	26.00	EACH
505-215A	SPLICE STEEL PILE BEFORE DRIVING (STEEL SHELL PILE)	4.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING (HP 14 x 117)	145.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING (STEEL SHELL PILE)	64.00	EACH
506-005A	PRESTRESSING CAST-IN-PLACE CONCRETE (POST-TENSIONING BARS)	1.00	LS
507-005A	ELASTOMERIC BEARINGS PLAIN (6" X 16" X 1/2")	24.00	EA
507-005A	ELASTOMERIC BEARINGS PLAIN (8" x 24 1/2" x 1/2")	24.00	EA
507-010A	ELASTOMERIC BEARINGS LAMINATED (14" X 18" X 5.188")	16.00	EA
511-005A	CONCRETE WATERPROOF SYSTEM TYPE C	400.00	SY
520-005A	PREDRILLING FOR PILING IN SOIL	1,491.00	FT
521-005A	DYNAMIC PILE TESTING	8.00	EA
521-010A	CAPWAP ANALYSIS	16.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY (PLAN QUANTITY)	8,261.10	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	200.80	CY
566-005A	COMPRESSION EXPANSION JOINT (2") (PLAN QUANTITY)	193.90	FT
567-005A	STRIP SEAL EXPANSION JOINT (PLAN QUANTITY)	201.50	FT
574-005A	ANTI-GRAFFITI COATING (PLAN QUANTITY)	57,163.00	SF
575-005A	TEXTURED CONCRETE SURFACE (PLAN QUANTITY)	1,189.00	SY
576-005A	(GFRP) REINFORCEMENT (PLAN QUANTITY)	2,040.00	FT
577-005A	PILE SLEEVES (30" CMP) (PLAN QUANTITY)	1,020.60	FT

584-005A	TEMPORARY SHORING (MAIN STREET BRIDGES)	1.00	LS
584-005A	TEMPORARY SHORING (UPRR BRIDGES)	1.00	LS
584-005A	TEMPORARY SHORING (W. INKOM I.C. BRIDGES)	1.00	LS
586-005A	UTILITY CONDUIT (APPROX. 4904 FT, UPRR BRIDGES)	1.00	LS
586-005A	UTILITY CONDUIT (MAIN STREET BRIDGES)	1.00	LS
603-045A	24" PIPE SIPHON	62.00	FT
605-025A	12" STORM SEWER PIPE	68.00	FT
605-035A	18" STORM SEWER PIPE	1,076.00	FT
605-045A	24" STORM SEWER PIPE	180.00	FT
605-055A	30" STORM SEWER PIPE	220.00	FT
605-065A	36" STORM SEWER PIPE	184.70	FT
605-455A	MANHOLE TYPE A	3.00	EACH
605-470A	SEDIMENT & OIL TRAP MANHOLE	1.00	EACH
605-616A	INLET TYPE 3A	2.00	EACH
605-630A	INLET TYPE 8	12.00	EACH
605-635A	ADJUST MANHOLE COVERS	2.00	EACH
605-640A	ADJUST VALVE COVERS	3.00	EACH
605-655A	DRYWELL	2.00	EACH
608-035A	18" APRON FOR PIPE	3.00	EACH
608-045A	24" APRON FOR PIPE	2.00	EACH
608-055A	30" APRON FOR PIPE	1.00	EACH
608-065A	36" APRON FOR PIPE	1.00	EACH
610-035A	FENCE TYPE 4 (8')	590.00	FT
610-045A	FENCE TYPE 5 B	26.00	FT
610-200A	GATE TYPE 3 (8'X18')	1.00	EACH
610-250A	BRACES	23.00	EACH
612-005A	W-BEAM GUARDRAIL	18,064.00	FT
612-010A	CONCRETE BARRIER TRANSITION	1.00	EACH
612-115B	GUARDRAIL TERMINAL, FLARED	7.00	EACH
612-115C	GUARDRAIL TERMINAL, TANGENT	31.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	42.00	EACH
612-150A	CONCRETE BARRIER	513.00	FT
612-155A	CONCRETE TERMINAL TYPE A	1.00	EACH
612-156A	CONCRETE TERMINAL TYPE B	10.00	EACH
614-015A	SIDEWALK	567.00	SY
614-025A	CURB RAMP	43.00	SY
615-255A	CURB (CURB TYPE 5 ASPHALT)	187.40	FT
615-260A	CURB TYPE 5	3,285.00	FT
615-492A	CURB & GUTTER TYPE 2	710.00	FT
615-494A	CURB & GUTTER TYPE 4	236.00	FT
616-010A	SIGN TYPE B-1	790.50	SF
616-015A	SIGN TYPE C-1	1,035.70	SF
616-040A	STEEL SIGN POST TYPE A-1	134.70	FT
616-040B	STEEL SIGN POST TYPE A-2	33.00	FT
616-040D	STEEL SIGN POST TYPE A-4	531.80	FT
616-040G	STEEL SIGN POST TYPE B-2	295.50	FT
616-040H	STEEL SIGN POST TYPE B-3	87.30	FT
616-040I	STEEL SIGN POST TYPE B-4	35.00	FT
616-040J	STEEL SIGN POST TYPE E-1	36.60	FT

616-040k	STEEL SIGN POST TYPE E-2	109.80	FT
616-055C	WOOD SIGN POST TYPE D-3 .	43.00	FT
616-080A	REINSTALL SIGN FACE	2.00	EACH
616-095A	SIGN BRACKETS	316.29	LB
616-100A	SIGN BRACES	165.55	LB
617-005A	DELINEATOR TYPE 1 (R)	44.00	EACH
617-010A	DELINEATOR TYPE 2 (R)	31.00	EACH
617-020A	DELINEATOR TYPE 4 (R)	1.00	EACH
617-045A	DELINEATOR TYPE 9	76.00	EACH
617-050A	MILEPOST TYPE 1	3.00	EACH
618-020A	WITNESS POST	8.00	EACH
619-010A	ILLUMINATION TYPE 2	1.00	LS
619-010B	ILLUMINATION TYPE 2 (OVERHEAD)	1.00	LS
621-005A	SEED BED PREPARATION	15.95	ACRE
621-010A	SEEDING	16.12	ACRE
621-035A	FERTILIZING	15.95	ACRE
621-050A	SOIL AMENDMENT	15.95	ACRE
621-060A	MULCH PLUS TACKIFIER	16.12	ACRE
621-075A	ROLLED EROSION CONTROL PRODUCTS (RECP)	425.00	SY
624-005A	LOOSE RIPRAP	114.10	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	3,708.70	SF
626-035A	BARRICADE TYPE 2	2.00	EACH
626-040A	BARRICADE TYPE 3	40.00	EACH
626-050A	DRUMS	818.00	EACH
626-065B	ARROW BOARD	964.00	DAY
626-085B	RADAR SPEED FEEDBACK TRAILER	347.00	DAY
626-092A	TEMPORARY PAVEMENT MARKING TAPE	3,600.00	FT
626-093A	TEMP PAV MARKING - WATERBORNE	242,668.00	FT
626-100A	MISC TEMPORARY TRAF CONT ITEMS	80,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	4,880.00	HR
626-111A	TEMP RIGID RAISED PAVEMENT MARKERS	7,540.00	EACH
626-112B	FLOOD LIGHTS	367.00	DAY
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	1,756.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER	9,888.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	9,035.00	FT
626-118A	TEMPORARY CRASH CUSHION	5.00	EACH
626-120A	FLAGGER CONTROL	1,450.00	HR
626-121A	R&R TEMP CRASH CUSHION	4.00	EACH
626-130B	TEMPORARY TRAFFIC CONTROL SIGNAL	347.00	DAY
626-135A	WEIGHTED BASE TUBULAR MARKERS	33.00	EACH
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	720.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	398.00	SF
630-025A	LONG PAV MKG - WATERBORNE	224,154.30	FT
631-010A	RUMBLE STRIPS	11.65	MILE
634-005A	MAILBOX (TYPE A WITH NEWSPAPER BOX)	2.00	EACH
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	13,317.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE (TYPE II, WOVEN)	16,198.00	SY
640-015B	SUBGRADE SEPARATION GEOTEXTILE (TYPE III, NON-WOVEN)	12,683.00	SY
650-005A	TIME-LAPSE CAMERA	6.00	EACH

650-010A	TIME-LAPSE CAMERA SERVICE	120.00	MO
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	60,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-15A	RETAINING WALL (WELDED WIRE MSE) (PLAN QUANTITY)	5,978.00	SF
S501-15B	RETAINING WALL (GRAVITY LARGE CONCRETE BLOCK) (PLAN QUANTITY)	1,575.00	SF
S501-15F	SOLDIER PILE WALL (PLAN QUANTITY)	2,680.00	SF
S501-17A	MSE RETAINING WALL (1-STAGE) (PLAN QUANTITY)	8,752.00	SF
S501-17B	MSE RETAINING WALL (2-STAGE) (PLAN QUANTITY)	12,933.00	SF
S501-20A	SP BRIDGE DRILLED SHAFT - CROSSHOLE SONIC LOG (CSL) TEST	4.00	EACH
S501-20B	SP BRIDGE DRILLED SHAFT - THERMAL INTEGRITY PROFILING (TIP) TEST	4.00	EACH
S501-25A	SP BRIDGE ARTWORK AESTHETICS	1.00	LS
S501-25B	SP BRIDGE SETTLEMENT MONITORING	1.00	LS
S501-30A	SP BRIDGE DRILLED SHAFT (10 FT DIAMETER) (PLAN QUANTITY)	414.00	FT
S501-30B	SP BRIDGE PROTECTIVE FENCE FOR CONCRETE PARAPET (PLAN QUANTITY)	2,277.00	FT
S501-30C	SP BRIDGE FENCE DECORATIVE PANELS (PLAN QUANTITY)	2,277.00	FT
S501-40A	SP BRIDGE ROCK SLOPE ARMOR (PLAN QUANTITY)	1,016.00	CY
S900-50A	CONTINGENCY AMOUNT DIRECTED REPAIRS	250,000.00	CA
S900-50B	CONTINGENCY AMOUNT PREDRILLING FOR PILING IN SOIL	30,000.00	CA
S900-50C	CONTINGENCY AMOUNT DRILLED SHAFT - REMOVAL OF OBSTRUCTIONS	115,000.00	CA
S901-05A	SP INLET PIPE CONNECTION	1.00	EACH
S901-05B	SP SIDEWALK UNDERDRAIN	1.00	EACH
S901-05C	SP AREA DRAIN	1.00	EACH
S901-05D	SP WILDLIFE RAMP A (PERPENDICULAR)	11.00	EACH
S901-05E	SP WILDLIFE RAMP B (CORNER)	3.00	EACH
S901-05G	SP WILDLIFE GUARD	2.00	EACH
S904-05A	SP REMOVE AND RESET WEIGH IN MOTION	1.00	LS
S904-05B	SP DROP INLET/JUNCTION BOX	1.00	LS
S904-05C	SP GUARDRAIL LAPPING	1.00	LS
S911-05A	SP REMOVE AND RESET CABLE BARRIER SYSTEM	3,867.00	FT
S911-05B	SP REMOVE AND RESET CONCRETE BARRIER	644.00	FT
S911-05C	SP WILDLIFE FENCE - STANDARD (PLAN QUANTITY)	6,229.90	FT
S911-05D	SP WILDLIFE FENCE - MODERATE (PLAN QUANTITY)	6,683.00	FT
S911-05E	SP WILDLIFE FENCE - DIFFICULT (PLAN QUANTITY)	2,175.00	FT
S911-05F	SP WILDLIFE FENCE - MODIFIED CHAIN LINK	4,469.00	FT
S911-05G	SP UTILITY TRENCH	491.00	FT
S911-05H	SP PAVEMENT JOINT ADHESIVE	624.00	FT
S913-05A	SP STORMWATER BERM	57.90	CY
S913-05B	SP ROCK MULCH (MEDIAN)	2,077.00	CY
S913-05C	SP ROCK MULCH (SHOULDER)	1,100.00	CY
S916-05A	SP TRAFFIC CONTROL SUPERVISOR	420.00	DAY
Z629-05A	MOBILIZATION	1.00	LS