

Key No. 20662 - US-95, Mc ARTHUR LAKE
Boundary County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	1.00	CA
201-005A	CLEARING & GRUBBING	5.55	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	30.00	EACH
203-005A	REM OF OBSTRUCTIONS	1.00	LS
203-015A	REM OF BITUMINOUS SURF	9,910.30	SY
203-035A	REM OF CONC CULV (MONOLITHIC)	1.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	10,000.00	CA
203-080A	REM OF GUARDRAIL/BARRIER	1,348.80	FT
203-090A	REM OF INLET	2.00	EACH
203-130A	REMOVAL OF PAV MARKINGS	23,737.00	FT
203-135A	REMOVAL OF SIGN	15.00	EACH
205-005A	EXCAVATION	81,230.00	CY
205-040A	GRANULAR BORROW	83.00	CY
205-060A	WATER FOR DUST ABATEMENT	1,661.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	1,500.00	CY
210-005A	STR EXCAVATION SCH NO. 1	160.00	CY
210-015A	COMPACTING BACKFILL	83.00	CY
212-011A	FIBER WATTLE	4,426.00	FT
212-060A	STABILIZED CONST ENTRANCE	2.00	EACH
212-095A	INLET PROTECTION	2.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	20,000.00	CA
251-005A	MIGRATORY BIRD COMPLIANCE	10,000.00	CA
301-005A	GRANULAR SUBBASE	38,598.00	TON
303-021A	3/4" AGGR TY A FOR BASE	10,262.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	1,458.00	GAL
405-245A	APPROACH	1.00	EACH
405-325A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP- 3T	2,166.00	TON
405-455A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5	4,091.00	TON
431-005A	COLD MILLING	103.70	SY
502-140A	CONC CL 40-A SCH NO. 1	126.80	CY
502-310A	CONC CL 40 AF SCH NO. 2	496.70	CY
502-435A	APPROACH SLAB	193.30	SY
503-010A	METAL REINF SCH NO. 1	31,088.00	LB
503-015A	METAL REINF SCH NO. 2	52,023.00	LB
503-020A	EPOXY COATED METAL REINF	104,504.00	LB
504-005A	STL BRIDGE (APPROX WT) 553,337 LBS	1.00	LS
505-115C	PROV&DRIV 30" DIA STEEL SHELL PILE	776.00	FT
505-165C	PROV&DRIV TEST STEEL SHELL PILE (30")	1,176.00	FT
505-215A	SPLICE STEEL PILE BEFORE DRIVING	17.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING	34.00	EACH
507-010A	BRIDGE BEARINGS LAMINATED (Size__) 12"x22"	8.00	EA
521-005A	DYNAMIC PILE TESTING	36.00	EA

521-010A	CAPWAP ANALYSIS	36.00	EA
567-005A	STRIP SEAL EXPANSION JOINT	87.00	FT
576-005A	(GFRP) REINFORCEMENT	420.00	FT
584-005A	TEMPORARY SHORING TYPE A	1.00	LS
584-005B	TEMPORARY SHORING TYPE B	1.00	LS
602-025A	12" PIPE CULV	96.00	FT
602-125A	72" PIPE CULV	76.00	FT
605-615A	INLET TY 3	2.00	EACH
606-005A	4" PIPE UNDERDRAIN	318.00	FT
606-120A	RURAL EDGE DRAIN	1,106.20	FT
611-010A	CATTLE GUARD TY A	2.00	EACH
612-005D	W-BEAM GUARDRAIL	563.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
616-010A	SIGNS TY B	121.00	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	305.62	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.48	MFBM
617-010A	DELINEATOR TY 2	39.00	EACH
617-045A	DELINEATOR TY 9	9.00	EACH
617-060A	MILEPOST TY 3	1.00	EACH
621-005A	SEED BED PREPARATION	6.08	ACRE
621-010A	SEEDING	5.34	ACRE
621-010B	SEEDING - WETLANDS	0.74	ACRE
621-015A	MULCHING	4.39	ACRE
621-020A	MULCH ANCHORING (MECHANICAL)	3.83	ACRE
621-035A	FERTILIZING	6.08	ACRE
621-065A	HYDRA APPLIED EROSION CONTROL PROD	2.25	ACRE
624-005A	LOOSE RIPRAP	188.80	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	576.00	SF
626-040A	BARRICADE TY 3	12.00	EACH
626-050A	DRUMS	200.00	EACH
626-093A	TEMP PAV MARKING - WATERBORNE	27,552.00	FT
626-105A	TRAF CNTL MAINTENANCE	460.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	860.00	DAY
626-116A	TEMP CONCRETE BARRIER	4,008.00	FT
626-118A	TEMP CRASH CUSHION	7.00	EACH
626-120A	FLAGGER CONTROL	1,024.00	HR
626-121A	R&R TEMP CRASH CUSHION	3.00	EACH
626-135A	WEIGHTED BASE TUBULAR MARKERS	50.00	EACH
630-020A	PAV MKG - WATERBORNE	64.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	32,691.00	FT
631-010A	RUMBLE STRIPS	1.51	MILE
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	1,137.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	29,951.00	SY
645-004A	C1 AGG & SOILS FIELD LAB	1.00	LS
650-070A	TIME-LAPSE CAMERA	1.00	EACH

650-070B	TIME-LAPSE CAMERA SERVICE	8.00	MO
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	10,000.00	CA
675-015A	DIRECTED SURVEYING CREW	20,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-17A	MSE RETAINING WALL	864.00	SF
S501-25A	SP BRIDGE UTILITY CONDUIT	1.00	LS
S501-30A	SP BRIDGE 3 TUBE METAL RAILING	674.00	FT
S501-30B	SP BRIDGE CMP PILE SLEEVE	30.00	FT
S501-70A	PAINTING STEEL SHELL PILES	357.00	SF
S619-05A	JUNCTION BOX	2.00	EACH
S640-05A	GEOGRID UNIAXIAL	8,340.00	SY
S901-05A	SP JUMP-OUT STRUCTURE	5.00	EACH
S901-05B	SP SINGLE WIRE 4-FT GATE	2.00	EACH
S901-05C	SP VERTICAL INCLINOMETER CASING	1.00	EACH
S901-05D	SP SETTLEMENT PLATE	18.00	EACH
S901-05E	SP SETTLEMENT POINT	5.00	EACH
S901-05F	SP FLASHING SIGN REMOVAL	2.00	EACH
S901-05G	SP ROCK CHECK DAM	15.00	EACH
S904-05A	SP PLANTINGS	1.00	LS
S908-05A	SP TEMPORARY SOIL STABILIZATION AND EROSION CONTROL	5.72	ACRE
S911-05A	SP WILDLIFE FENCE	6,235.00	FT
S911-05B	SP CONSTRUCTION FENCE	5,453.00	FT
S911-05C	SP PAVEMENT JOINT ADHESIVE	3,106.00	FT
S913-05B	SP ROCK MULCH	3,056.70	CY
S913-05C	SP SURCHARGE PLACEMENT AND REMOVAL	1,145.00	CY
Z629-05A	MOBILIZATION	1.00	LS