

Key No. 20666, 22003, 23737 - SHOE STRING RD REHABILITATION
Gooding County

Item No	Description	QTY	Unit
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
205-005A	EXCAVATION	5,080.00	CY
205-060A	WATER FOR DUST ABATEMENT	1,350.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	170.00	CY
205-090A	SHOULDER GRADING	8.70	MILE
212-011A	FIBER WATTLE	4,328.00	FT
212-105A	WATER AND POLLUTION	10,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	34,360.00	TON
308-005A	CEMENT RECYCLED ASPHALT BASE STAB	51,500.00	SY
308-010A	PORTLAND CEMENT	450.00	TON
308-015A	PULVERIZE EXISTING SURFACE	51,500.00	SY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	4,120.00	GAL
402-020A	EMULSIFIED ASPHALT FOR PRIME COAT	61.00	TON
402-030A	BLOTTER	260.00	TON
405-245A	APPROACH - PRIVATE	57.00	EACH
405-245B	APPROACH - PUBLIC	6.00	EACH
405-260A	WEDGE MILLING	1,420.00	SY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	11,740.00	TON
616-010A	SIGNS TY B	52.00	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	99.70	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.17	MFBM
618-025A	STREET MONUMENT	9.00	EACH
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,107.00	SF
626-050A	DRUMS	50.00	EACH
626-100B	MISC TEMPORARY TRAF CONT ITEMS	20,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	120.00	HR
626-120A	FLAGGER CONTROL	1,840.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	200.00	EACH
630-025A	LONG PAV MKG - WATERBORNE	125,673.00	FT
634-005A	MAILBOX	11.00	EACH
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	65,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT - MISC WORK	65,785.50	CA
S901-05A	SP - EARTHEN CHECK DAM	3.00	EACH
Z629-05A	MOBILIZATION	1.00	LS