

Key No. 20675 - I-84, KIMBERLY IC (SH-50)
Jerome County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	24,500.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
201-005A	CLEARING & GRUBBING	11.21	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	5.00	EACH
203-002A	REMOVAL OF OBSTRUCTIONS (BOLLARD)	20.00	EACH
203-003A	REMOVAL OF OBSTRUCTIONS (PIPE)	607.00	FT
203-006A	REMOVAL OF SIGN	43.00	EACH
203-007A	REMOVAL OF SIGN (OVERHEAD)	1.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL (MULTI-SPAN)	1.00	EACH
203-025A	REMOVAL OF CATCH BASIN	2.00	EACH
203-050A	REMOVAL OF CONCRETE HEADWALL	1.00	EACH
203-065A	REMOVAL OF CURB	414.00	FT
203-070A	REMOVAL OF CURB & GUTTER	209.00	FT
203-075A	REMOVAL OF FENCE	2,275.00	FT
203-080A	REMOVAL OF GUARDRAIL	3,731.00	FT
203-080B	REMOVAL OF BARRIER	60.00	FT
203-090A	REMOVAL OF INLET	3.00	EACH
203-122A	REMOVAL OF MISCELLANEOUS ITEMS (LUMINAIRE)	4.00	EACH
203-124A	REMOVAL OF MISCELLANEOUS ITEMS (PAV MARKINGS)	3,313.00	SF
203-125A	REMOVAL OF MISCELLANEOUS ITEMS (OH SIGN BRIDGE)	1.00	LS
204-006A	OBLITERATION OF OLD ROAD	1.00	LS
205-005A	EXCAVATION	31,650.00	CY
205-030A	BORROW (T)	6,500.00	CY
205-040A	GRANULAR BORROW	1,142.00	CY
205-060A	WATER FOR DUST ABATEMENT	2,955.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	2,700.00	CY
209-005A	SMALL DITCH	664.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	468.00	CY
210-015A	COMPACTING BACKFILL	1,427.00	CY
212-011A	FIBER WATTLE	13,726.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	6.00	EACH
212-095A	INLET PROTECTION	1.00	EACH
212-105A	WATER AND POLLUTION	2,000.00	CA
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	10,000.00	CA
301-005A	GRANULAR SUBBASE	27,997.00	TON
301-005B	GRANULAR SUBBASE (T)	6,100.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	23,098.00	TON
303-052A	3/4" AGGREGATE TYPE B FOR BASE (T)	2,200.00	CY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	4,392.00	GAL
405-240A	MISCELLANEOUS PAVEMENT	24.00	SY
405-245A	APPROACH (COMMERCIAL)	1.00	EACH
405-245B	APPROACH (FARM/FIELD)	3.00	EACH

405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T (SP-5)	2,000.00	TON
405-455A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5	11,925.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	479.40	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	841.00	CY
502-425A	PRESTRESSED STRINGER (WF50G)	2,317.40	FT
502-435A	APPROACH SLAB	497.10	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	104,164.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	68,451.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	101,360.00	LB
504-040A	COMB PED/BICYCLE & TRAF RAILING	503.80	FT
504-040B	COMB PED/BICYCLE & TRAF RAILING (W/PROTECTIVE FENCE)	504.50	FT
505-045A	PROVIDE & DRIVE STEEL H PILE (14 X 117)	1,958.00	FT
505-197A	PROVIDE & DRIVE TEST PILE (HP-14 x 117)	81.00	FT
505-205A	PROV&INST 14" DIA PILE SHOES OR TIPS	70.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN (SIZE 3/4"x9"x36")	44.00	EA
509-010A	NON-STRUCTURAL CONCRETE (CLASS 30)	472.00	SY
520-010A	PREDRILLING FOR PILING IN ROCK	400.00	FT
521-005A	DYNAMIC PILE TESTING	2.00	EA
521-010A	CAPWAP ANALYSIS	2.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY	2,662.50	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	64.80	CY
566-005A	COMPRESSION EXPANSION JOINT (2.5")	231.60	FT
575-005A	TEXTURED CONCRETE SURFACE	101.00	SY
576-005A	(GFRP) REINFORCEMENT (GLASS FIBER REINFORCED POLYMER)	1,160.00	FT
577-005A	PILE SLEEVES (30" DIAMETER)	544.10	FT
584-005A	TEMPORARY SHORING	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
602-035A	18" PIPE CULVERT	110.00	FT
602-045A	24" PIPE CULVERT	143.00	FT
605-630A	INLET TYPE 8	1.00	EACH
605-635A	ADJUST MANHOLE COVERS	1.00	EACH
608-035A	18" APRON FOR PIPE	4.00	EACH
608-045A	24" APRON FOR PIPE	1.00	EACH
609-025A	MINOR STR (CONC HEADWALL)	1.00	EACH
610-030A	FENCE TY 3 B	2,215.00	FT
610-250A	BRACES	24.00	EACH
612-005A	W-BEAM GUARDRAIL	1,306.00	FT
612-050A	GUARDRAIL TERMINAL (TANGENT)	8.00	EACH
612-110A	GUARDRAIL ANCHOR	2.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
612-156A	CONCRETE TERMINAL TY B	3.00	EACH
613-035A	CRASH CUSHION, LOW MAINTENANCE	4.00	EACH
614-015A	SIDEWALK	837.50	SY
614-025A	CURB RAMP	141.90	SY
615-256A	CURB TYPE 1	796.00	FT
615-260A	CURB TYPE 5 (ASPHALT)	52.00	FT

615-491A	CURB & GUTTER TYPE 1	1,398.00	FT
616-010A	SIGNS TY B	523.00	SF
616-015A	SIGNS TY C	881.00	SF
616-031A	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-031B	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-035A	SIGN BRACKETS & BRACE ANGLES	1,104.00	LB
616-040A	BRKAWY STL SIGN POST TY A	1,297.00	LB
616-045A	BRKAWY STL SIGN POST TY B	4,247.00	LB
616-050A	BRKAWY STL SIGN POST TY E	342.00	LB
616-060A	BRKAWY STL SIGN POST INST TY A	10.00	EACH
616-065A	BRKAWY STL SIGN POST INST TY B	37.00	EACH
616-070A	BRKAWY STL SIGN POST INST TY E	8.00	EACH
616-080A	REINSTALL SIGNS	20.00	EACH
617-005A	DELINEATOR TY 1	70.00	EACH
617-060A	MILEPOST TY 3	1.00	EACH
619-010A	ILLUMINATION TY 2	1.00	LS
621-005A	SEED BED PREPARATION	12.80	ACRE
621-010A	SEEDING (TYPE 1)	9.92	ACRE
621-010B	SEEDING (TYPE 2)	2.88	ACRE
624-005A	LOOSE RIPRAP	12.80	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	3,412.00	SF
626-040A	BARRICADE TY 3	23.00	EACH
626-050A	DRUMS	503.00	EACH
626-076A	ARROW BOARD TY C	5,760.00	HR
626-085B	RADAR SPEED FEEDBACK TRAILER	1,400.00	DAY
626-093A	TEMP PAV MARKING - WATERBORNE	76,343.00	FT
626-105A	TRAF CNTL MAINTENANCE	1,182.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	80.00	DAY
626-116A	TEMP CONCRETE BARRIER	3,675.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	650.00	FT
626-118A	TEMP CRASH CUSHION	12.00	EACH
626-120A	FLAGGER CONTROL	1,060.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	272.00	EACH
626-140A	SURFACE-MOUNTED TUBULAR MARKERS (18" CHANNELIZER)	14.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	2,251.00	SF
630-020A	LONG PAV MKG- PREFORMED THERMOPLASTIC	90,704.00	FT
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	56.40	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	39,400.00	SY
645-010A	C3 FIELD LAB	1.00	LS
654-025A	COMPOST (UNGULATE MANURE)	22.71	ACRE
656-005A	TRAF SIGNAL INSTALLATION (SH-50 AND I-84 EB RAMPS)	1.00	LS
656-005B	TRAF SIGNAL INSTALLATION (SH-50 AND I-84 WB RAMPS)	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	10,400.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-17A	MSE RETAINING WALL	7,477.00	SF

S501-18A	COPING FOR MSE WALL	450.00	FT
S501-51A	SP BRIDGE ANTI-GRAFFITI COATING	11,696.00	SF
S901-05A	SP REM & RESET CATTLE GUARD TY A	3.00	EACH
S901-05B	SP EXTEND CATTLE GUARD TY A	2.00	EACH
S901-05D	SP FIBER OPTIC JUNCTION BOX	3.00	EACH
S901-05E	SP FIBER OPTIC SPLICE VAULT	2.00	EACH
S901-05F	SP 24 POSTION TERMINATION PANEL	2.00	EACH
S901-05G	SP TERMIINATE FIBER OPTIC CABLE	2.00	EACH
S901-05H	SP TEST FIBER OPTIC CABLE	2.00	EACH
S901-05I	SP TEMPORARY ILLUMINATION	6.00	EACH
S911-05A	SP 2" PC CONDUIT	1,077.00	FT
S911-05B	SP INSTALL 12-FIBER OPTIC CABLE	1,009.00	FT
S913-05A	SP STORMWATER BERM	5.00	CY
Z629-05A	MOBILIZATION	1.00	LS