

Key No. 20678 - FY23 BRIDGE REPAIR  
Shoshone County

Item No	Description	QTY	Unit
107-019A	MONUMENT PRESERVATION	10,000.00	CA
110-005A	TRAINING	321.00	HR
212-105A	WATER POLLUTION AND EROSION CONTROL	10,000.00	CA
214-005A	ROADSIDE CLEANUP	5,000.00	CA
251-005A	MIGRATORY BIRD COMPLIANCE	5,000.00	CA
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	50.00	GAL
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	200.00	TON
431-005A	COLD MILLING	850.00	SY
510-005A	CONC OVERLAY	266.70	CY
511-005A	CONC WATERPROOF SYS , TYPE C	3,079.80	SY
553-005A	EPOXY OVERLAY	120,423.80	SF
565-005A	EXPANSION JOINT SYSTEM Asphaltic Plug	382.00	CF
566-005A	COMPRESSION EXPANSION JOINT , 1.5" INVERTED SEAL	381.30	FT
566-005B	COMPRESSION EXPANSION JOINT , 1"	120.00	FT
566-005C	COMPRESSION EXPANSION JOINT , 1.5"	99.00	FT
566-005D	COMPRESSION EXPANSION JOINT , 3" SEAL	282.60	FT
568-005A	ELASTOMERIC CONCRETE HEADER	2.10	CY
569-005A	REMOVAL OF EXPANSION JOINT	1,048.00	FT
580-005A	REMOVAL OF ASPHALT OVERLAY	257.80	SY
581-005A	CONCRETE CRACK REPAIR PREP	176.00	FT
581-010A	CONC CRACK EPOXY INJECTION	1.00	GAL
582-005A	PATCH AND REPAIR SURFACE , CONCRETE	178.00	SF
582-010A	PATCH AND REPAIR DECK	900.00	SF
612-005D	W-BEAM GUARDRAIL	1,600.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	11.00	EACH
612-120A	GUARDRAIL TRANSITION, LOW SPEED	6.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	2.00	EACH
616-015A	SIGNS TY C	116.00	SF
623-005A	CONC SLOPE PAVING	90.00	SY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,425.67	SF
626-040A	BARRICADE TY 3	12.00	EACH
626-050A	DRUMS	300.00	EACH
626-076B	ARROW BOARD TY C	600.00	DAY
626-100B	MISC TEMPORARY TRAF CONT ITEMS	2,500.00	CA
626-105A	TRAF CNTL MAINTENANCE	1,500.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	266.00	DAY
626-118A	TEMP CRASH CUSHION	19.00	EACH
626-119A	TRUCK ATTENUATOR	3.00	EACH
626-120A	FLAGGER CONTROL	1,325.00	HR
626-121A	R&R TEMP CRASH CUSHION	38.00	EACH
626-135A	WEIGHTED BASE TUBULAR MARKERS	350.00	EACH
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	8,251.50	FT

632-005A	CONC BRIDGE DECK REM CL A	3,719.80	SY
632-010A	CONC BRIDGE DECK REM CL B	173.10	SY
676-005A	RECORD OF EXISTING PAVEMENT MARKINGS	8,251.50	LS
S501-20A	SP BRIDGE , INSTALL SIGN	6.00	EACH
S626-30A	TRAF CNTL MANAGER	110.00	DAY
S900-50B	CONTINGENCY AMOUNT HAZARD MATERIAL REMOVAL DISPOSAL	5,000.00	CA
S900-50C	CONTINGENCY AMOUNT DECK REMOVAL WASTE DISPOSAL	5,000.00	CA
S900-50D	CONTINGENCY AMOUNT EMERGENCY RESPONSE PLAN	10,000.00	CA
Z629-05A	MOBILIZATION	1.00	LS