

Key No. 21798 & 21799  
 JCT US-20 (IC 333), REXBURG  
 Madison County

Item No	Description	QTY	Unit
104-005A	PARTNERING	15,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	30,000.00	CA
110-005A	TRAINING	600.00	HR
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	10.00	EACH
203-005A	REMOVAL OF OBSTRUCTIONS (SLOPE PAVING)	1.00	LS
203-015A	REMOVAL OF BITUMINOUS SURFACE	37,077.00	SY
203-050A	REMOVAL OF CONCRETE HEADWALL	1.00	EACH
203-055A	REMOVAL OF CONCRETE PAVEMENT	90.00	SY
203-060A	REMOVAL OF CONCRETE SIDEWALK	2,268.42	SY
203-070A	REMOVAL OF CURB & GUTTER	5,009.96	FT
203-075A	REMOVAL OF FENCE	1,723.14	FT
203-090A	REMOVAL OF INLET	19.00	EACH
203-122A	REMOVAL OF MISCELLANEOUS ITEMS (IRR STR)	3.00	EACH
203-122B	REMOVAL OF MISCELLANEOUS ITEMS (ILLUMINATION)	4.00	EACH
203-122C	REMOVAL OF MISCELLANEOUS ITEMS (SIGN)	6.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (PIPE)	1,081.00	FT
203-125A	REMOVAL OF MISCELLANEOUS ITEMS	1.00	LS
205-005A	EXCAVATION (PLAN QUANTITY)	44,809.00	CY
205-005B	EXCAVATION (STORM SEWER PIPE)	1,250.00	CY
205-030A	BORROW (PLAN QUANTITY)	1,229.00	CY
205-040A	GRANULAR BORROW (PLAN QUANTITY)	22,091.00	CY
205-060A	WATER FOR DUST ABATEMENT	1,600.00	MG
210-010A	STRUCTURE EXCAVATION SCHEDULE NO. 2 (PLAN QUANTITY)	5,222.00	CY
210-015A	COMPACTING BACKFILL (PLAN QUANTITY)	3,274.00	CY
212-011A	FIBER WATTLE	22,289.00	FT
212-105A	WATER AND POLLUTION	10,000.00	CA
301-010A	GRANULAR SUBBASE (PLAN QUANTITY)	2,756.00	CY
307-012A	OPEN-GRADED BASE CLASS III	27,231.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	6,915.00	GAL
405-245A	APPROACH	2.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 (PLAN QUANTITY)	16,314.00	TON
409-015A	CONCRETE PAVEMENT	90.00	SY
504-035A	PEDESTRIAN / BICYCLE RAILING (PLAN QUANTITY)	1,364.10	FT
574-005A	ANTI-GRAFFITI COATING (PLAN QUANTITY)	15,200.00	SF
575-005A	TEXTURED CONCRETE SURFACE (PLAN QUANTITY)	1,124.00	SY
584-005A	TEMPORARY SHORING	1.00	LS
604-010A	6" IRRIGATION PIPE	1,813.00	FT
604-045A	24" IRRIGATION PIPE	481.00	FT
604-055A	30" IRRIGATION PIPE	109.00	FT
605-025A	12" STORM SEWER PIPE	3,251.00	FT
605-035A	18" STORM SEWER PIPE	383.00	FT
605-215A	8" SANITARY SEWER PIPE	466.00	FT

605-465A	MANHOLE TYPE C	10.00	EACH
605-467A	MANHOLE TYPE D	9.00	EACH
605-470A	SEDIMENT & OIL TRAP MANHOLE	5.00	EACH
605-505A	CATCH BASIN TYPE 1A	44.00	EACH
605-630A	INLET TYPE 8	11.00	EACH
605-635A	ADJUST MANHOLE COVERS	7.00	EACH
608-025A	12" APRON FOR PIPE	6.00	EACH
608-035A	18" APRON FOR PIPE	2.00	EACH
609-025A	MINOR STR (PUMP BOX)	1.00	EACH
609-025B	MINOR STR (24" CONC HEADWALL)	2.00	EACH
609-025C	MINOR STR (DIVERSION BOX)	1.00	EACH
614-015A	SIDEWALK	4,354.50	SY
614-020A	DRIVEWAY	84.00	SY
614-025A	CURB RAMP	31.00	SY
614-025B	CURB RAMP	142.24	SY
615-256A	CURB TYPE 1	2,309.08	FT
615-492A	CURB & GUTTER TYPE 2	7,787.99	FT
616-010A	SIGNS TY B	947.00	SF
616-015A	SIGNS TY C	4,372.80	SF
616-030A	OVERHEAD BRIDGE SIGN STRUCTURE	4.00	EACH
616-031A	OVERHEAD CANTILEVER SIGN STRUCTURE (21799)	2.00	EACH
616-035A	SIGN BRACKETS & BRACE ANGLES	729.41	LB
616-040A	BRKAWY STL SIGN POST TY A	10,985.50	LB
616-045A	BRKAWY STL SIGN POST TY B	4,814.30	LB
616-050A	BRKAWY STL SIGN POST TY E	1,913.26	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.26	MFBM
616-060A	BRKAWY STL SIGN POST INST TY A	52.00	EACH
616-065A	BRKAWY STL SIGN POST INST TY B	42.00	EACH
616-070A	BRKAWY STL SIGN POST INST TY E	44.00	EACH
619-010A	ILLUMINATION TY 2 (21798)	1.00	LS
619-010B	ILLUMINATION TY 2 (21799)	1.00	LS
621-005A	SEED BED PREPARATION	9.30	ACRE
621-010A	SEEDING	9.30	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	9.30	ACRE
621-050A	SOIL AMENDMENT	9.30	ACRE
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	5,031.00	SF
626-040A	BARRICADE TY 3	36.00	EACH
626-050A	DRUMS	475.00	EACH
626-076B	ARROW BOARD TY C	140.00	DAY
626-080A	TEMPORARY CURB RAMP	8.00	EACH
626-092A	TEMPORARY PAVEMENT MARKING TAPE	1,341.00	FT
626-100A	MISC TEMPORARY TRAF CONT ITEMS	20,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	1,160.00	HR
626-112B	FLOOD LIGHTS	144.00	DAY
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	812.00	DAY
626-120A	FLAGGER CONTROL	2,900.00	HR

626-135A	WEIGHTED BASE TUBULAR MARKERS	227.00	EACH
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	709.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	4,925.00	SF
630-025A	LONG PAV MKG - WATERBORNE	50,850.00	FT
634-005A	MAILBOX TYPE A	2.00	EACH
640-005A	DRAINAGE GEOTEXTILE	3,420.00	SY
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	5,150.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE TYPE III	31,700.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE TYPE III	26,696.00	SY
650-005A	TIME-LAPSE CAMERA	4.00	EACH
650-010A	TIME-LAPSE CAMERA SERVICE	32.00	MO
651-010A	LAWN CONSTRUCTION (SODDED) (21798)	6,201.00	SF
652-005A	UNDERGROUND SPRINKLER SYS	1.00	LS
654-025A	COMPOST	9.30	ACRE
656-005A	TRAF SIGNAL INSTALLATION (21798)	1.00	LS
656-005B	TRAF SIGNAL INSTALLATION (21799)	1.00	LS
656-005C	TRAF SIGNAL INSTALLATION (21798 - EXIT 337)	1.00	LS
656-005D	TRAF SIGNAL INSTALLATION (TEMP EXIT 333 WB RAMPS)	1.00	LS
656-005E	TRAF SIGNAL INSTALLATION (TEMP EXIT 333 EB RAMPS)	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	10,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-15A	RETAINING WALL (CAST IN PLACE) (PLAN QUANTITY)	11,555.00	SF
S501-25A	SP BRIDGE ABUTMENT MOVEMENT MONITORING	1.00	LS
S501-35A	SP BRIDGE ROCK SLOPE ARMOR (PLAN QUANTITY)	5,150.00	SY
S656-10A	MULTIPLE APPROACH VIDEO DETECTION SYSTEM (21798)	1.00	LS
S656-10B	MULTIPLE APPROACH VIDEO DETECTION SYSTEM (21799)	1.00	LS
S656-10C	MULTIPLE APPROACH VIDEO DETECTION SYSTEM (21798 - EXIT 337)	1.00	LS
S900-50A	CONTINGENCY AMOUNT DIRECTED LANDSCAPING	30,000.00	CA
S900-50C	CONTINGENCY AMOUNT DIRECTED REPAIRS	80,000.00	CA
S901-05A	SP RELOCATE SIGN	2.00	EACH
S901-05B	SP RELOCATE ILLUMINATION	2.00	EACH
S901-05C	SP SWALE OUTLET STRUCTURE	2.00	EACH
S901-05D	SP REXBURG CITY SIGN	4.00	EACH
S901-07A	SP GPS INSPECTION UNIT	2.00	EACH
S904-05A	SP RELOCATE PUMP AND POWER	1.00	LS
S904-05B	SP LANDSCAPE	1.00	LS
S904-05C	SP STORM SEWER REPAIR	1.00	LS
S904-05D	SP SEWER VALVE	1.00	LS
S904-06A	SP AUTOMATED MACHINE GUIDANCE	1.00	LS
S911-05A	SP CAST IN PLACE CONCRETE BARRIER, MEDIAN	512.00	FT
S911-05B	SP CAST IN PLACE CONCRETE BARRIER, WITH GUT TER	1,237.00	FT
S911-05C	SP CAST IN PLACE CONCRETE BARRIER, SEPARATE D	1,731.00	FT
S911-05D	SP PEDESTRIAN SAFETY WALL	4,968.00	FT
S912-05A	SP ROCK MULCH	1,463.00	SY
S913-05A	SP DRAIN ROCK CHANNEL	1,532.00	CY

S913-05B	SP STORMWATER INFILTRATION BED	90.00	CY
S913-05C	SP FILTER SAND	2,228.00	CY
S915-05A	SP LANDSCAPE ROCK TY 1	51,375.00	SF
S916-05A	SP TRAF CNTL MONITOR	215.00	DAY
Z629-05A	MOBILIZATION	1.00	LS