

Key No. 21895 - US-30, NOUNAN RD TO BENNINGTON
Bear Lake County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	8,500.00	CA
107-019A	MONUMENT PRESERVATION	2,000.00	CA
203-135A	REMOVAL OF SIGN	47.00	EACH
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	500.00	CY
205-090A	SHOULDER GRADING	9.84	MILE
212-095A	INLET PROTECTION	4.00	EACH
212-105A	WATER POLLUTION AND EROSION CONTROL	5,000.00	CA
308-005A	CEM RECYCLED ASPH BASE STAB	131,879.00	SY
308-010A	PORTLAND CEM	1,369.00	TON
308-015A	PULVERIZE EXISTING SURF	131,879.00	SY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	12,608.00	GAL
403-300A	CHIP SEAL WARRANTY	157,590.00	SY
405-245A	APPROACH	12.00	EACH
405-455A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5	41,160.00	TON
431-005A	COLD MILLING	157,539.00	SY
616-010A	SIGNS TY B	459.00	SF
616-020A	SIGNS TY E	46.50	SF
616-035A	SIGN BRACKETS & BRACE ANGLES	632.40	LB
616-045A	BRKAWY STL SIGN POST TY B	3,311.40	LB
616-065A	BRKAWY STL SIGN POST INST TY B	40.00	EACH
617-005A	DELINEATOR TY 1 (White)	170.00	EACH
617-020A	DELINEATOR TY 4 (White)	24.00	EACH
617-060A	MILEPOST TY 3	6.00	EACH
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	82.00	DAY
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	795.50	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	131,880.00	FT
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	2,000.00	CA
675-015A	DIRECTED SURVEYING CREW	2,000.00	CA
676-005A	RECORD OF EXISTING PAVEMENT MARKINGS	1.00	LS
S626-31A	TRAF CNTL MONITOR	75.00	DAY
S900-50A	CONTINGENCY AMOUNT ADDITIONAL TRAFFIC CONTROL	5,000.00	CA
S900-50B	CONTINGENCY AMOUNT CURB & GUTTER REPLACEMENT	10,000.00	CA
S904-05A	SP TEMPORARY TRAFFIC CONTROL DESIGN AND OPE RATIONS	1.00	LS
S904-05B	SP AUTOMATIC TRAFFIC RECORDER	1.00	LS
S904-05C	SP WEIGH-IN-MOTION STATION	1.00	LS
S904-05D	SP MODIFIED CATTLE GUARD BOX	1.00	LS
S912-05A	SP ON-SITE CEMENT TREATED BASE STABILIZATIO N	25,660.00	SY
Z629-05A	MOBILIZATION	1.00	LS