

Key No. 21984 - MOODY ROAD BRIDGE  
Madison County

Item No	Description	QTY	Unit
110-005A	TRAINING	420.00	HR
201-005A	CLEARING & GRUBBING	0.37	ACRE
203-015A	REMOVAL OF BITUMINOUS SURFACE	3,254.00	SY
203-020A	REMOVAL OF BRIDGE - FULL	1.00	EACH
203-075A	REMOVAL OF FENCE	475.00	FT
203-080A	REMOVAL OF GUARDRAIL	673.00	FT
205-005A	EXCAVATION	1,200.00	CY
205-040A	GRANULAR BORROW	2,110.00	CY
205-060A	WATER FOR DUST ABATEMENT	64.00	MG
205-095A	SOFT SPOT REPAIR	20,000.00	CA
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	211.19	CY
210-015A	COMPACTING BACKFILL	633.73	CY
212-011A	FIBER WATTLE	1,633.00	FT
212-020A	SILT FENCE	289.00	FT
212-105A	WATER AND POLLUTION	5,000.00	CA
213-005A	TOPSOIL	385.60	CY
301-005A	GRANULAR SUBBASE	2,473.00	TON
303-021A	3/4" AGGREGATE TYPE A FOR BASE	1,591.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	856.50	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	69.29	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	162.73	CY
502-380A	PRESTRESSED WF GIRDER WF58 GIRDERS 58" DEPTH	728.00	FT
502-430A	CONCRETE PARAPET (42")	324.00	FT
502-435A	APPROACH SLAB	199.26	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	9,387.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	34,580.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	20,035.00	LB
505-045A	PROVIDE & DRIVE STEEL H PILE (14 X 117)	1,125.00	FT
505-197A	PROVIDE & DRIVE TEST PILE (HP-14 x 117)	140.00	FT
507-005A	ELASTOMERIC BEARINGS PLAIN	12.00	EA
511-005A	CONCRETE WATERPROOF SYSTEM TYPE C	153.00	SY
566-005A	COMPRESSION EXPANSION JOINT	89.67	FT
574-005A	ANTI-GRAFFITI COATING	1,134.00	SF
576-005A	(GFRP) REINFORCEMENT	460.00	FT
586-005A	UTILITY CONDUIT	1.00	LS
610-015A	FENCE TY 1 B	508.00	FT
610-250A	BRACES	8.00	EACH
612-005A	W-BEAM GUARDRAIL	965.00	FT
612-050A	GUARDRAIL TERMINAL	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
621-005A	SEED BED PREPARATION	0.37	ACRE
621-010A	SEEDING	0.74	ACRE
621-035A	FERTILIZING	0.37	ACRE
621-065A	HYDRA APPLIED EROSION CONTROL PROD	0.37	ACRE
624-005A	LOOSE RIPRAP	987.58	CY

626-100A	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
630-025A	LONG PAV MKG - WATERBORNE	3,396.00	FT
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	1,398.03	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	15,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S501-25A	SP BRIDGE DEWATERING FOUNDATION - COFFERDAMS	1.00	LS
S610-05A	REM & RESET FENCE	492.00	FT
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	19,915.20	CA
S900-50B	CONTINGENCY AMOUNT - FENCE MODIFICATIONS	30,000.00	CA
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
Z629-05A	MOBILIZATION	1.00	LS