

Key No. 22102 - FRANKLIN BLVD & KARCHER RD INTERSECTION
Canyon County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
110-005A	TRAINING	388.00	HR
201-005A	CLEARING & GRUBBING	0.20	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	7.00	EACH
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-006A	REMOVAL OF SIGN	11.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	7,134.00	SY
203-060A	REMOVAL OF CONCRETE SIDEWALK	622.00	SY
203-070A	REMOVAL OF CURB & GUTTER	1,512.00	FT
203-090A	REMOVAL OF INLET	7.00	EACH
203-095A	REMOVAL OF MANHOLE	7.00	EACH
203-122A	REMOVAL OF MISCELLANEOUS ITEMS (IRRIGATION STRUCTURE)	2.00	EACH
203-122B	REMOVAL OF MISCELLANEOUS ITEMS (FIRE HYDRANT)	2.00	EACH
203-122C	REMOVAL OF MISCELLANEOUS ITEMS (WATER METER)	2.00	EACH
203-122D	REMOVAL OF MISCELLANEOUS ITEMS (WATER VALVE)	4.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (PIPE)	1,245.00	FT
205-005A	EXCAVATION	5,700.00	CY
205-040A	GRANULAR BORROW	3,300.00	CY
205-060A	WATER FOR DUST ABATEMENT	180.00	MG
205-095A	SOFT SPOT REPAIR	5,000.00	CA
212-011A	FIBER WATTLE	419.00	FT
212-095A	INLET PROTECTION (FILTER INSERT)	18.00	EACH
212-105A	WATER AND POLLUTION	5,000.00	CA
213-005A	TOPSOIL (6")	154.00	CY
301-005A	GRANULAR SUBBASE	6,300.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	3,470.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	850.00	GAL
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	2,160.00	TON
409-015A	CONCRETE PAVEMENT (RED PCC PAVEMENT)	547.00	SY
604-025A	12" IRRIGATION PIPE	594.00	FT
605-015A	8" STORM SEWER PIPE	11.00	FT
605-025A	12" STORM SEWER PIPE	222.00	FT
605-035A	18" STORM SEWER PIPE	606.00	FT
605-215A	8" SANITARY SEWER PIPE	67.00	FT
605-455A	MANHOLE TYPE A	1.00	EACH
605-465A	MANHOLE TYPE C	10.00	EACH
605-467A	MANHOLE TYPE D	1.00	EACH
605-470A	SEDIMENT & OIL TRAP MANHOLE	1.00	EACH
605-515A	CATCH BASIN TYPE 2A	8.00	EACH
605-635A	ADJUST MANHOLE COVERS	10.00	EACH
605-640A	ADJUST VALVE COVERS	3.00	EACH
610-035A	FENCE TYPE 4 (48")	190.00	FT
614-015A	SIDEWALK	1,494.00	SY
614-020A	DRIVEWAY (DIPPED SIDEWALK)	308.00	SY
614-025A	CURB RAMP (PERPENDICULAR)	113.00	SY

615-255A	CURB (TYPE 1 MOD)	384.00	FT
615-256A	CURB TYPE 1	1,231.00	FT
615-257A	CURB TYPE 2	322.00	FT
615-331A	GUTTER TYPE 1	13.00	FT
615-492A	CURB & GUTTER TYPE 2	1,685.00	FT
615-494A	CURB & GUTTER TYPE 4	10.00	FT
616-010A	SIGN TYPE B-1	188.00	SF
616-040G	STEEL SIGN POST TYPE B-2 (B-2)	12.00	FT
616-040J	STEEL SIGN POST TYPE E-1 (E-1)	120.00	FT
616-040k	STEEL SIGN POST TYPE E-2 (E-2)	137.00	FT
616-080A	REINSTALL SIGN FACE	3.00	EACH
616-085A	REINSTALL SIGN POST	3.00	EACH
616-100A	SIGN BRACES	197.00	LB
619-010A	ILLUMINATION TYPE 2	1.00	LS
626-100A	MISC TEMPORARY TRAF CONT ITEMS	12,500.00	CA
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	963.00	SF
630-025A	LONG PAV MKG - WATERBORNE	13,864.00	FT
634-005A	MAILBOX	3.00	EACH
640-015A	SUBGRADE SEPARATION GEOTEXTILE (TYPE III)	8,600.00	SY
657-015A	RRFB, AC POWERED	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	15,000.00	CA
S501-15A	RETAINING WALL (CONCRETE WALL)	520.00	SF
S600-20A	FIRE HYDRANT ASSEMBLY	1.00	EACH
S600-45A	WATER LINE (8")	39.00	FT
S600-45B	WATER LINE (12")	354.00	FT
S600-45C	WATER LINE (6")	14.00	FT
S901-05A	SP TRUNCATED DOMES	6.00	EACH
S901-05B	SP IRRIGATION BOX W/ SLIDE GATES	2.00	EACH
S901-05C	SP WATERLINE CONNECTION	3.00	EACH
S901-05D	SP 12" GATE VALVE	4.00	EACH
S901-05E	SP HOT TAP W/ 8" GATE VALVE	1.00	EACH
S901-05F	SP 2" BLOWOFF ASSEMBLY	1.00	EACH
S901-05G	SP 2" PI SERVICE	2.00	EACH
S901-05H	SP LANDSCAPE BOULDER	59.00	EACH
S901-05I	SP CLEANOUT (SANITARY)	1.00	EACH
S901-05J	SP WATERLINE ADJUSTMENT	1.00	EACH
S901-05K	SP RELOCATE POST LIGHTING	1.00	EACH
S901-05L	SP SEDIMENT & OIL TRAP (1000 GAL)	1.00	EACH
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
S904-05B	SP SEEPAGE BED	1.00	LS
S911-05A	SP ORANGE SAFETY FENCE	500.00	FT
S911-05B	SP CONDUIT (2")	220.00	FT
S911-05C	SP 1" WATER SERVICE CONNECTION	23.00	FT
S912-05A	SP STAMPED RED CONCRETE	591.00	SY
S912-05B	SP LANDSCAPE & IRRIGATION REPAIR	1,272.00	SY
S913-05A	SP ROCK MULCH (3" DEPTH)	53.00	CY
Z629-05A	MOBILIZATION	1.00	LS