

Key No. 22165 - US-20, US-26, CHINDEN BLVD; I-84 to MIDDLETON RD  
Canyon County

Item No	Description	QTY	Unit
105-010A	DISPUTE REVIEW BOARD-3 MEMBER(CONT ITEM)	17,000.00	CA
201-005A	CLEARING & GRUBBING	30.00	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	111.00	EACH
202-010A	SELECTIVE REM OF STUMPS	4.00	EACH
203-015A	REM OF BITUMINOUS SURF	60,838.00	SY
203-025A	REM OF CATCH BASIN	33.00	EACH
203-035A	REM OF CONC CULV (MONOLITHIC) (SOLOMON DRAIN)	1.00	EACH
203-035B	REM OF CONC CULV (MONOLITHIC) (NOBLE DRAIN)	1.00	EACH
203-050B	REM AND DISPOSE ASBESTOS	30,000.00	CA
203-055A	REM OF CONC PAV	6,882.00	SY
203-060A	REM OF CONC SIDEWALK	4,535.00	SY
203-065A	REM OF CURB	6,087.00	FT
203-070A	REM OF CURB & GUTTER	6,938.00	FT
203-075A	REM OF FENCE	2,688.00	FT
203-080A	REM OF GUARDRAIL/BARRIER	1,084.00	FT
203-085A	REM OF GUTTER	117.00	FT
203-095A	REM OF MANHOLE	11.00	EACH
203-105A	REM OF MISC IRR STR	15.00	EACH
203-125A	REM OF MISCELLANEOUS ITEMS (TRAFFIC SIGNALS)	1.00	LS
203-125B	REM OF MISCELLANEOUS ITEMS (ILLUMINATION)	22.00	EA
203-125C	REM OF MISCELLANEOUS ITEMS (PIPE)	2,525.00	FT
203-130A	REMOVAL OF PAV MARKINGS	22,080.00	FT
203-135A	REMOVAL OF SIGN	84.00	EACH
205-005A	EXCAVATION	173,200.00	CY
205-005B	EXCAVATION (DRAINAGE)	1,275.00	CY
205-040A	GRANULAR BORROW	28,300.00	CY
205-060A	WATER FOR DUST ABATEMENT	8,500.00	MG
209-005A	SMALL DITCH	3,187.00	FT
210-005A	STR EXCAVATION SCH NO. 1	3,749.00	CY
210-015A	COMPACTING BACKFILL	1,395.00	CY
212-011A	FIBER WATTLE	2,534.00	FT
212-020A	SILT FENCE	4,904.00	FT
212-095A	INLET PROTECTION	23.00	EACH
301-005A	GRANULAR SUBBASE	174,100.00	TON
303-022A	3/4" AGGR TY B FOR BASE	86,400.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	17,500.00	GAL
405-240A	MISC PAV	244.00	SY
405-245A	APPROACH	29.00	EACH
405-260A	WEDGE MILLING	7,329.00	SY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	42,900.00	TON
411-005A	URBAN CONC PAV CONCRETE DEPTH 12"	4,815.00	SY
511-005A	CONC WATERPROOF SYS TY D	795.00	SY

560-005A	DEWATERING FOUNDATION	1.00	LS
578-005A	PRECAST CONCRETE CULVERT HEIGHT=15'-0", WIDTH=19'-0", LENGTH=198' -7 3/4"	1.00	LS
578-005B	PRECAST CONCRETE CULVERT HEIGHT=9'-11", WIDTH=14'-0", LENGTH=127' -0"	1.00	LS
579-005A	BOND REINFORCING STEEL	1.00	LS
584-005A	TEMPORARY SHORING (SOLOMON DRAIN)	1.00	LS
584-005B	TEMPORARY SHORING (NOBLE DRAIN)	1.00	LS
584-005C	TEMPORARY SHORING (MSE WALL)	1.00	LS
602-025A	12" PIPE CULV	1,319.00	FT
602-105A	60" PIPE CULV	28.00	FT
603-035A	18" PIPE SIPHON	417.00	FT
603-075A	42" PIPE SIPHON	264.00	FT
603-105A	60" PIPE SIPHON	224.00	FT
604-025A	12" IRR PIPE	1,382.00	FT
604-030A	15" IRR PIPE	2,172.00	FT
604-035A	18" IRR PIPE	1,038.00	FT
604-075A	42" IRR PIPE	18.00	FT
604-105A	60" IRR PIPE	14.00	FT
605-025A	12" STORM SEWER PIPE	1,727.00	FT
605-035A	18" STORM SEWER PIPE	1,245.00	FT
605-045A	24" STORM SEWER PIPE	320.00	FT
605-455A	MANHOLE TY A	13.00	EACH
605-470A	SEDIMENT & OIL TRAP MANHOLE	9.00	EACH
605-500A	CATCH BASIN TY 1	41.00	EACH
605-630A	INLET TY 8	2.00	EACH
605-635A	ADJUST MANHOLE COVERS	41.00	EACH
605-640A	ADJUST VALVE COVERS	34.00	EACH
608-025A	12" APRON FOR PIPE	40.00	EACH
608-035A	18" APRON FOR PIPE	1.00	EACH
608-045A	24" APRON FOR PIPE	3.00	EACH
609-025A	MINOR STR A - 60" CULVERT HEADWALL	2.00	EACH
609-025B	MINOR STR B - 4'x4' IRRIGATION BOX	13.00	EACH
609-025C	MINOR STR C - OUTLET STRUCTURE	1.00	EACH
609-025D	MINOR STR D - 8'x8' IRRIGATION BOX	2.00	EACH
609-025E	MINOR STR E - 6'x6' IRRIGATION BOX	2.00	EACH
609-025F	MINOR STR F - 42" CULVERT HEADWALL	2.00	EACH
609-025G	MINOR STR G - 4'x4' IRRIGATION BOX WITH WEIR	1.00	EACH
609-025H	MINOR STR H - INLET STRUCTURE	1.00	EACH
609-025I	MINOR STR I - STORMWATER STRUCTURE	3.00	EACH
610-035A	FENCE TY 4	1,090.00	FT
610-045A	FENCE TY 5 B	1,449.00	FT
610-101A	GATE TY 1A	1.00	EACH
612-005D	W-BEAM GUARDRAIL	1,516.50	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	2.00	EACH

612-150A	CONCRETE BARRIER	309.00	FT
612-156A	CONCRETE TERMINAL TY B (TEMP)	10.00	EACH
614-015A	SIDEWALK	25,405.00	SY
614-020A	DRIVEWAY	473.80	SY
614-025A	CURB RAMP	516.00	SY
615-256A	CURB TYPE 1	18,703.00	FT
615-258A	CURB TYPE 3	3,065.00	FT
615-331A	GUTTER TYPE 1	157.00	FT
615-491A	CURB & GUTTER TYPE 1	7,935.00	FT
615-492A	CURB & GUTTER TYPE 2	1,185.00	FT
615-651A	TRAFFIC SEPARATOR TYPE 1	654.00	FT
616-010A	SIGNS TY B	480.00	SF
616-015A	SIGNS TY C	170.00	SF
616-031A	OVERHEAD CANTILEVER SIGN STRUCTURE	1.00	EACH
616-035A	SIGN BRACKETS & BRACE ANGLES	530.00	LB
616-045A	BRKAWY STL SIGN POST TY B	1,050.00	LB
616-050A	BRKAWY STL SIGN POST TY E	2,860.00	LB
616-055A	BRKAWY WOOD SIGN POST TY D	0.17	MFBM
616-065A	BRKAWY STL SIGN POST INST TY B	9.00	EACH
616-070A	BRKAWY STL SIGN POST INST TY E	86.00	EACH
616-080A	REINSTALL SIGNS	7.00	EACH
617-005A	DELINEATOR TY 1	7.00	EACH
617-015A	DELINEATOR TY 3	8.00	EACH
617-055A	MILEPOST TY 2	2.00	EACH
618-010A	RIGHT-OF-WAY MARKER	53.00	EACH
618-025A	STREET MONUMENT	4.00	EACH
620-020A	PLANTING TREE (SEEDLING or CONTAINER)	36.00	EACH
621-005A	SEED BED PREPARATION	15.23	ACRE
621-010A	SEEDING	14.51	ACRE
621-010B	SEEDING	0.72	ACRE
621-015A	MULCHING	15.23	ACRE
621-020A	MULCH ANCHORING (MECHANICAL)	14.51	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	0.72	ACRE
621-035A	FERTILIZING	16.14	ACRE
624-005A	LOOSE RIPRAP (12")	129.00	CY
624-010A	LOOSE RIPRAP	2,470.00	TON
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	2,900.00	SF
626-035A	BARRICADE TY 2	30.00	EACH
626-040A	BARRICADE TY 3	30.00	EACH
626-050A	DRUMS	800.00	EACH
626-076A	ARROW BOARD TY C	26,400.00	HR
626-100B	MISC TEMPORARY TRAF CONT ITEMS	10,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	9,060.00	HR
626-113A	FLOOD LIGHTS	1.00	LS
626-114A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	66,000.00	HR
626-116A	TEMP CONCRETE BARRIER	10,500.00	FT

626-117A	R&R TEMP CONCRETE BARRIER	9,900.00	FT
626-118A	TEMP CRASH CUSHION	20.00	EACH
626-120A	FLAGGER CONTROL	2,020.00	HR
626-121A	R&R TEMP CRASH CUSHION	30.00	EACH
626-135A	WEIGHTED BASE TUBULAR MARKERS	1,370.00	EACH
630-020A	PAV MKG - WATERBORNE	6,820.00	SF
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	2,910.00	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	175,200.00	FT
630-025B	LONGITUDINAL PAV MKG- PREFORMED THERMO	19,540.00	FT
634-005A	MAILBOX	11.00	EACH
640-005A	DRAINAGE GEOTEXTILE	19,105.00	SY
640-010A	RIPRAP/EROSION CONT GEOTEXTILE	1,704.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	191,000.00	SY
651-010A	LAWN CONST (SODDED)	39,431.00	SF
656-005A	TRAF SIGNAL INSTALLATION (RAMPS)	1.00	LS
656-005B	TRAF SIGNAL INSTALLATION (AVIATION)	1.00	LS
656-005C	TRAF SIGNAL INSTALLATION (SMEED)	1.00	LS
656-005D	TRAF SIGNAL INSTALLATION (KCID)	1.00	LS
656-005E	TRAF SIGNAL INSTALLATION (WARD)	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	10,000.00	CA
675-015A	DIRECTED SURVEYING CREW	25,000.00	CA
A100-70A	FUEL ADJUSTMENT	238,840.00	CA
A100-80A	ASPHALT ADJUSTMENT	48,255.00	CA
A303-05A	QA -AGGR FOR BASE	41,040.00	CA
A405-05A	QA- PL MIX PAV	343,200.00	CA
A405-10A	PL MIX SMOOTHNESS	44,000.00	CA
A409-10A	CONC THICKNESS	28,890.00	CA
S209-05A	DITCH (CONC)	773.00	FT
S501-15A	RETAINING WALL SEGMENTAL BLOCK	5,672.00	SF
S501-15B	RETAINING WALL (GRAVITY CONCRETE BLOCK)	3,434.00	SF
S501-25A	SP BRIDGE CAST-IN-PLACE CULVERT CLOSURE (SOLOMON D RAIN)	1.00	LS
S501-25B	SP BRIDGE CAST-IN-PLACE CULVERT CLOSURE (NOBLE DRAIN)	1.00	LS
S610-10A	SPECIAL GATE	3.00	EACH
S626-31A	TRAF CNTL MONITOR	500.00	DAY
S656-15A	MULTIPLE APPROACH RADAR DETECTION SYSTEM (RAMPS)	1.00	LS
S656-15B	MULTIPLE APPROACH RADAR DETECTION SYSTEM (AVIATION)	1.00	LS
S656-15C	MULTIPLE APPROACH RADAR DETECTION SYSTEM (SMEED)	1.00	LS
S900-10A	CLEANOUT	4.00	EACH
S900-50A	CONTINGENCY AMOUNT DRILLED SHAFT - REMOVAL OF OBSTRUCTIONS	20,000.00	CA
S900-51A	CONTINGENCY AMOUNT PEDESTRIAN TEMPORARY TRAFFIC CONTROL PLAN	25,000.00	CA
S901-05C	SP ABANDON WELL	5.00	EACH
S901-05D	SP EMERGENCY BOLLARD	3.00	EACH
S901-05F	SP IRRIGATION VALVE	3.00	EACH

S901-05G	SP RELOCATE BUSINESS SIGN	4.00	EACH
S901-05I	SP REM SEPTIC TANK & DRAINFIELD	1.00	EACH
S901-05J	SP SURFACE MOUNTED ROADWAY DELINEATOR	82.00	EACH
S901-05K	SP RELOCATE GATE	4.00	EACH
S904-05A	SP REM & RESET EXISTING ILLUMINATION	1.00	LS
S904-05B	SP ILLUMINATION TY 2 - FUTURE USE	1.00	LS
S904-05C	SP PRIVATE SEWER LINE	1.00	LS
S904-05D	SP ITD FIBER OPTIC SYSTEM	1.00	LS
S904-05E	SP CALDWELL FIBER OPTIC SYSTEM	1.00	LS
S904-05F	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 22)	1.00	LS
S904-05G	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 24)	1.00	LS
S904-05H	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 25)	1.00	LS
S904-05I	SP AUTOMATIC TRAFFIC RECORDER (RADAR TYPE)	1.00	LS
S904-05J	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 26)	1.00	LS
S904-05K	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 27)	1.00	LS
S904-05L	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 28)	1.00	LS
S904-05M	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 43)	1.00	LS
S904-05N	SP BUILDING REMOVAL AND SITE CLEANUP (PARCE L 51)	1.00	LS
S904-06C	SP TRAFFIC SIGNAL INSTALLATION (MIDDLETON)	1.00	LS
S904-06D	SP MULTIPLE APPROACH RADAR DETECTION SYSTEM (KCID)	1.00	LS
S904-06E	SP MULTIPLE APPROACH RADAR DETECTION SYSTEM (WARD)	1.00	LS
S904-06F	SP MULTIPLE APPROACH RADAR DETECTION SYSTEM (MIDDLETON)	1.00	LS
S904-06G	SP PREEMPTIVE DETECTION SYSTEM (AVIATION)	1.00	LS
S904-06H	SP PREEMPTIVE DETECTION SYSTEM (SMEED)	1.00	LS
S904-06I	SP PREEMPTIVE DETECTION SYSTEM (KCID)	1.00	LS
S904-06J	SP PREEMPTIVE DETECTION SYSTEM (WARD)	1.00	LS
S904-06K	SP PREEMPTIVE DETECTION SYSTEM (MIDDLETON)	1.00	LS
S904-06L	SP PREEMPTIVE DETECTION SYSTEM (RAMPS)	1.00	LS
S904-06M	SP TEMP TRAFFIC SIGNAL - I-84	1.00	LS
S904-06N	SP TEMP TRAFFIC SIGNAL - AVIATION	1.00	LS
S904-06O	SP TEMP TRAFFIC SIGNAL - SMEED	1.00	LS
S904-06P	SP TEMP TRAFFIC SIGNAL - MIDDLETON	1.00	LS
S911-05A	SP PEDESTRIAN RAILING	1,047.00	FT
S911-05B	SP INSTALL CONDUIT	2,050.00	FT
S911-05C	SP SEEPAGE BED	530.00	FT
S911-05D	SP WOOD FENCE - POLE	280.00	FT
S911-05E	SP WOOD FENCE - FLAT PANEL	286.00	FT
S912-05A	SP PEDESTRIAN LANDING	1,128.00	SY
S912-05B	SP STAMPED CONCRETE FOR MEDIAN	21,865.00	SY
S913-05A	SP 2" DRAIN ROCK	7,295.50	CY
Z629-05A	MOBILIZATION BRIDGE	1.00	LS
Z629-05A	MOBILIZATION ROADWAY	1.00	LS