

Key No. 22195 - US-93, CAREY TO HOTSPRINGS
Blaine County

Item No	Description	QTY	Unit
104-005A	PARTNERING	16,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
203-010A	ASBESTOS REMOVAL AND DISPOSAL	10,000.00	CA
203-025A	REMOVAL OF CATCH BASIN	1.00	EACH
203-030A	REMOVAL OF CONCRETE CULVERT	2.00	EACH
203-045A	REMOVAL OF CONCRETE HEADGATE	2.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS PIPE CULVERT	140.00	FT
203-123B	REMOVAL OF MISCELLANEOUS ITEMS STORM PIPE	72.00	FT
205-005A	EXCAVATION	20,400.00	CY
205-060A	WATER FOR DUST ABATEMENT	2,190.00	MG
205-090A	SHOULDER GRADING	4.80	MILE
205-095A	SOFT SPOT REPAIR	500.00	CA
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	898.00	CY
210-015A	COMPACTING BACKFILL	384.00	CY
212-020A	SILT FENCE	9,341.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	4.00	EACH
212-105A	WATER AND POLLUTION	5,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	24,160.00	TON
308-005A	CEMENT RECYCLED ASPHALT BASE STAB	71,800.00	SY
308-010A	PORTLAND CEMENT	540.00	TON
308-015A	PULVERIZE EXISTING SURFACE	71,800.00	SY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	14,900.00	GAL
402-020A	EMULSIFIED ASPHALT FOR PRIME COAT	100.00	TON
405-245A	APPROACH	142.00	EACH
405-260A	WEDGE MILLING	921.00	SY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	34,300.00	TON
431-005A	COLD MILLING	60,900.00	SY
511-005A	CONCRETE WATERPROOF SYSTEM	258.00	SY
578-005A	PRECAST CONCRETE CULVERT STIFF LEG	1.00	LS
578-005B	PRECAST CONCRETE CULVERT	1.00	LS
584-005A	TEMPORARY SHORING	1.00	LS
602-025A	12" PIPE CULVERT	120.00	FT
602-035A	18" PIPE CULVERT	65.00	FT
602-045A	24" PIPE CULVERT	140.00	FT
605-630A	INLET TYPE 8	1.00	EACH
605-655A	DRYWELL	1.00	EACH
608-035A	18" APRON FOR PIPE	2.00	EACH
608-045A	24" APRON FOR PIPE	4.00	EACH
617-005A	DELINEATOR TYPE 1	200.00	EACH
617-020A	DELINEATOR TYPE 4	30.00	EACH
621-005A	SEED BED PREPARATION	0.49	ACRE
621-010A	SEEDING PERMANENT	0.47	ACRE
621-010B	SEEDING WETLAND	0.02	ACRE
624-005A	LOOSE RIPRAP	50.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,973.00	SF

626-040A	BARRICADE TYPE 3	6.00	EACH
626-050A	DRUMS	50.00	EACH
626-093A	TEMP PAV MARKING - WATERBORNE	2,000.00	FT
626-100A	MISC TEMPORARY TRAF CONT ITEMS	50,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	330.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	220.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER	150.00	FT
626-118A	TEMPORARY CRASH CUSHION	4.00	EACH
626-120A	FLAGGER CONTROL	3,520.00	HR
626-125A	PILOT CAR	880.00	HR
626-130A	TEMPORARY TRAFFIC CONTROL SIGNAL	5,280.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	400.00	EACH
626-145A	TEMPORARY RUMBLE STRIPS	7.74	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	414.00	SF
630-025A	LONG PAV MKG - WATERBORNE	151,526.00	FT
631-010A	RUMBLE STRIPS	7.70	MILE
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	3,000.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	38,900.00	SY
645-010A	C3 FIELD LAB - AGG, SOILS, SP 3 & SP 5	1.00	LS
654-025A	COMPOST	0.47	ACRE
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	30,000.00	CA
676-015A	RECORD AND REESTABLISH PAV MARKINGS	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S901-05E	SP 18" HEADGATE	1.00	EACH
Z629-05A	MOBILIZATION	1.00	LS