Bid Items List

Key No. 22208 - SH 3, MIDDLE FK POTLATCH CR BR TO BOTTOM OF BEAR RIDGE

Latah County

Item No	Description	QTY	Unit
104-005A	PARTNERING	10,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
203-006A	REMOVAL OF SIGN	38.00	EACH
203-080A	REMOVAL OF GUARDRAIL (METAL)	5,481.00	FT
203-121A	REMOVAL OF MISCELLANEOUS ITEMS (SIDEWALK & DRIVEWAY)	422.00	SY
205-085A	SHOULDER AGGREGATE	700.00	TON
205-090A	SHOULDER GRADING	6.00	MILE
205-100A	GUARDRAIL TERMINAL GRADING	16.00	EACH
212-095A	INLET PROTECTION	26.00	EACH
212-105A	WATER AND POLLUTION	10,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	1,000.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	7,540.00	GAL
405-245A	APPROACH	40.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	18,000.00	TON
431-005A	COLD MILLING	85,682.00	SY
605-635A	ADJUST MANHOLE COVERS	32.00	EACH
605-640A	ADJUST VALVE COVERS	35.00	EACH
612-005A	W-BEAM GUARDRAIL	5,481.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	16.00	EACH
614-015A	SIDEWALK	368.00	SY
614-020A	DRIVEWAY	55.00	SY
616-010A	SIGN TYPE B-1	328.56	SF
616-015A	SIGN TYPE C-1	66.00	SF
616-020A	SIGN TYPE E	11.25	SF
616-040G	STEEL SIGN POST TYPE B-2 .	292.50	FT
616-040H	STEEL SIGN POST TYPE B-3 .	40.90	FT
616-040J	STEEL SIGN POST TYPE E-1 .	11.30	FT
616-040K	STEEL SIGN POST TYPE E-2 .	74.50	FT
616-095A	SIGN BRACKETS	92.92	LB
616-100A	SIGN BRACES	294.00	LB
617-005A	DELINEATOR TYPE 1 (RIGID)	183.00	EACH
617-020A	DELINEATOR TYPE 4 (RIGID)	6.00	EACH
617-060A	MILEPOST TYPE 3	4.00	EACH
618-025A	STREET MONUMENT	6.00	EACH
626-100B	MISC TEMPORARY TRAF CONT ITEMS	20,000.00	CA
630-005A	T,W,S,A PAVEMENT MARKINGS - WATERBORNE	2,264.00	SF
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	550.00	SF
630-020A	LONG PAV MKG- PREFORMED THERMOPLASTIC	1,400.00	FT
630-025A	LONG PAV MKG - WATERBORNE	314,457.80	FT
631-010A	RUMBLE STRIPS	5.50	MILE
634-005A	MAILBOX	1.00	EACH
676-015A	RECORD AND REESTABLISH PAV MARKINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT SP MISCELLANEOUS EROSION AND	15,000.00	CA

	POLLUTION C ONTROL (HAZMAT)		
S900-50B	CONTINGENCY AMOUNT MISCELLANEOUS WORK	15,000.00	CA
S901-05A	SP CURB RAMP (URBAN APPROACHES)	29.00	EACH
S904-05A	SP TEMPORARY TRAFFIC CONTROL DESIGN & OPERA TIONS	1.00	LS
S904-05B	SP DRYWELL TYPE A	1.00	LS
S904-05C	SP AGGREGATE PRODUCTION QUALITY TESTING	1.00	LS
S912-05B	SP SOFT SPOT REPAIR	135.00	SY
S915-05A	SP SIDEWALK GRINDING	307.00	SF
S916-05A	SP TRAFFIC CONTROL SUPERVISOR	50.00	DAY
Z629-05A	MOBILIZATION	1.00	LS