Bid Items List

Key No. 22390 - VISTA AVE, OVERLAND RD to ROSE HILL ST, BOISE

Ada County

Item No	Description	QTY	Unit
104-005A	PARTNERING	40,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
110-005A	TRAINING	954.00	HR
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	5.00	EACH
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-006A	REMOVAL OF SIGN	37.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	18,969.00	SY
203-025A	REMOVAL OF CATCH BASIN	26.00	EACH
203-060A	REMOVAL OF CONCRETE SIDEWALK	5,310.00	SY
203-065A	REMOVAL OF CURB	398.00	FT
203-070A	REMOVAL OF CURB & GUTTER	8,722.00	FT
203-085A	REMOVAL OF GUTTER	182.00	FT
203-095A	REMOVAL OF MANHOLE	3.00	EACH
203-130A	REMOVAL OF PAVEMENT MARKINGS	1,520.00	FT
205-005A	EXCAVATION	6,460.00	CY
205-060A	WATER FOR DUST ABATEMENT	145.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	1,820.00	CY
212-095A	INLET PROTECTION	36.00	EACH
212-105A	WATER AND POLLUTION	10,000.00	CA
213-010A	TOPSOIL	264.00	SY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	5,000.00	CA
301-005A	GRANULAR SUBBASE	7,090.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	11,200.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	3,620.00	GAL
405-240A	MISCELLANEOUS PAVEMENT	3,701.00	SY
405-245A	APPROACH	19.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 (NMAS 1/2", PG 70-28)	6,820.00	TON
431-005A	COLD MILLING	23,380.00	SY
605-025A	12" STORM SEWER PIPE	1,064.00	FT
605-035A	18" STORM SEWER PIPE	625.00	FT
605-045A	24" STORM SEWER PIPE	20.00	FT
605-450A	MANHOLE (TYPE ACHD SD-611)	17.00	EACH
605-555A	CATCH BASIN (TYPE ACHD SD-601)	28.00	EACH
605-635A	ADJUST MANHOLE COVERS	33.00	EACH
610-255A	TEMPORARY CONSTRUCTION FENCE	700.00	FT
614-015A	SIDEWALK (5" THICKNESS)	4,943.00	SY
614-020A	DRIVEWAY (TYPE ACHD SD-710B)	2,057.00	SY
614-025A	CURB RAMP (PERPENDICULAR)	525.00	SY
614-025C	CURB RAMP (COMBO)	95.00	SY
615-255A	CURB (TYPE ISPWC SD-701A - 6" VERTICAL CURB (NO GUTTER))	1,566.00	FT
615-330A	GUTTER (TYPE ACHD SD-708)	343.00	FT
615-490A	CURB & GUTTER (TYPE ACHD SD-701)	8,839.00	FT
616-010A	SIGN TYPE B-1	419.00	SF

616-040J	STEEL SIGN POST TYPE E-1	20.00	FT
616-040K	STEEL SIGN POST TYPE E-2	186.00	FT
616-080A	REINSTALL SIGN FACE	9.00	EACH
616-090A	SPECIAL INSTALL SIGN	19.00	EACH
619-010A	ILLUMINATION TYPE 2	1.00	LS
620-010A	MULCH (3")	27.00	CY
626-005A	PEDESTRIAN CHANNELIZING DEVICES	2,070.00	FT
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	3,260.00	SF
626-035A	BARRICADE TYPE 2	30.00	EACH
626-040A	BARRICADE TYPE 3	20.00	EACH
626-050A	DRUMS	380.00	EACH
626-076B	ARROW BOARD TYPE C	400.00	DAY
626-080A	TEMPORARY CURB RAMP	70.00	EACH
626-093A	TEMP PAV MARKING - WATERBORNE	39,600.00	FT
626-100B	MISC TEMPORARY TRAF CONT ITEMS	10,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	3,000.00	HR
626-112A	FLOOD LIGHTS	1,100.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	1,000.00	DAY
626-120A	FLAGGER CONTROL	2,000.00	HR
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	110.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	4,860.00	SF
630-025A	LONG PAV MKG - WATERBORNE	15,260.00	FT
640-015A	SUBGRADE SEPARATION GEOTEXTILE (TYPE II)	12,820.00	SY
640-015B	SUBGRADE SEPARATION GEOTEXTILE (TYPE III)	2,340.00	SY
656-010A	SIGNAL HOUSING	56.00	EACH
656-015A	INTERSECTION PREEMPTION DETECTION SYSTEM	3.00	EACH
656-020C	INT DETECTION SYSTEM - VIDEO (TYPE FISHEYE)	3.00	EACH
656-025C	ELECTRICAL SERVICE PEDESTAL TYPE 3	3.00	EACH
656-030A	INTERSECTION SIGNAL STRUCTURE (VISTA/OVERLAND)	1.00	EACH
656-030B	INTERSECTION SIGNAL STRUCTURE (VISTA/KOOTENAI)	1.00	EACH
656-030C	INTERSECTION SIGNAL STRUCTURE (VISTA/CASSIA)	1.00	EACH
656-035A	INTERSECTION PEDESTRIAN SYSTEM (VISTA/OVERLAND)	1.00	EACH
656-035B	INTERSECTION PEDESTRIAN SYSTEM (VISTA/KOOTENAI)	1.00	EACH
656-035C	INTERSECTION PEDESTRIAN SYSTEM (VISTA/CASSIA)	1.00	EACH
656-040A	SIGNAL CABINET	3.00	EACH
656-045A	SIGNAL CONTROLLER	3.00	EACH
656-050A	PED & TRAFF CNTL SIG HEAD FRANG POLES	12.00	EACH
656-065A	COMB CAB & SVS PEDESTAL FOUNDATION	3.00	EACH
656-070A	ADDITIONAL ELECTRICAL ITEMS (VISTA/OVERLAND)	1.00	LS
656-070B	ADDITIONAL ELECTRICAL ITEMS (VISTA/KOOTENAI)	1.00	LS
656-070C	ADDITIONAL ELECTRICAL ITEMS (VISTA/CASSIA)	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	25,000.00	CA
S610-05A	REM & RESET FENCE (CHAIN-LINK)	92.00	FT
S900-50A	CONTINGENCY AMOUNT WATER POLLUTION AND EROSION CONTROL	5,000.00	CA
S900-50B	CONTINGENCY AMOUNT PEDESTRIAN TEMPORARY TRAFFIC CONTROL PLA N	50,000.00	CA
S901-05A	SP TRIM TREE	45.00	EACH
S901-05B	SP CATCH BASIN (TYPE ACHD SD-603)	2.00	EACH

S901-05D	SP ADJUST JUNCTION BOX	1.00	EACH
S901-05E	SP ADJUST MONITORING WELL	1.00	EACH
S901-05G	SP DETECTABLE WARNING FOR PEDESTRIAN ACCESS (TYPE ISPWC SD-712)	4.00	EACH
S901-05H	SP GROUT PIPE AND CATCH BASIN	1.00	EACH
S901-05I	SP ABANDON PIPE	2.00	EACH
S901-06A	SP JUNCTION BOX (TYPE S-45T)	14.00	EACH
S901-06B	SP SPLICE VAULT	1.00	EACH
S901-06C	SP FIBER TERMINATION	96.00	EACH
S901-06D	SP TEST FIBER OPTIC CABLE	96.00	EACH
S901-06E	SP CCTV VIDEO SYSTEM	3.00	EACH
S901-06F	SP TERMINATION PANEL	4.00	EACH
S901-06G	SP ETHERNET SWITCH	3.00	EACH
S901-06H	SP TEMPORARY TRAFFIC SIGNAL	3.00	EACH
S911-05A	SP SPRINKLER REPAIR	485.00	FT
S911-06A	SP CONDUIT (2")	9,400.00	FT
S911-06B	SP 12-FIBER CABLE	4,400.00	FT
S912-05A	SP BRICK PAVER REPAIR	18.00	SY
S912-05B	SP LANDSCAPE REPAIR	1,581.00	SY
S912-05C	SP COLORED AND PATTERNED CONCRETE	65.00	SY
S912-05D	SP GRAVEL APPROACH REPAIR	18.00	SY
S912-05E	SP LANDSCAPE ROCK	89.00	SY
S912-05F	SP CONCRETE REPAIR	56.00	SY
Z629-05A	MOBILIZATION	1.00	LS