

Key No. 22432 - KILPATRICK BRIDGE
Blaine County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	5,000.00	CA
201-010A	CLEARING & GRUBBING	1.00	LS
203-006A	REMOVAL OF SIGN	5.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL	1.00	EACH
205-005A	EXCAVATION	645.00	CY
205-040A	GRANULAR BORROW	850.00	CY
205-060A	WATER FOR DUST ABATEMENT	42.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	100.00	CY
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	89.00	CY
210-015A	COMPACTING BACKFILL	3.00	CY
212-011A	FIBER WATTLE	795.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	2.00	EACH
212-105A	WATER AND POLLUTION	5,000.00	CA
215-005A	GEOSYNTH REINFORCED ABUTMENT BACKFILL	197.00	CY
301-005A	GRANULAR SUBBASE	865.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	460.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	135.00	GAL
405-245A	APPROACH	1.00	EACH
405-425A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-2	160.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	29.00	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	21.00	CY
502-385A	PRESTRESSED DECK BULB TEE GIRDER 67" TOP FLANGE, 43" DEPTH	530.00	FT
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	7,438.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	1,410.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	722.00	LB
504-035A	PEDESTRIAN / BICYCLE RAILING	350.00	FT
504-050A	3-TUBE CURB MOUNT RAIL	216.00	FT
505-045A	PROVIDE & DRIVE STEEL H PILE (14 X 117)	444.00	FT
505-205C	PROVIDE & INSTALL PILE SHOES OR TIPS HP-14x117	8.00	EACH
505-215A	SPLICE STEEL PILE BEFORE DRIVING	4.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING	4.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN GR.4 24" x 12" x 0.5"	10.00	EA
511-005A	CONCRETE WATERPROOF SYSTEM TYPE E	293.00	SY
560-005A	DEWATERING FOUNDATION	1.00	LS
584-005A	TEMPORARY SHORING	1.00	LS
586-005A	UTILITY CONDUIT	1.00	LS
616-010A	SIGN TYPE B-1	14.00	SF
616-040J	STEEL SIGN POST TYPE E-1	60.00	FT
621-025A	MULCH ANCHORING (TACKIFIER) TEMPORARY	0.23	ACRE
624-005A	LOOSE RIPRAP	192.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	272.00	SF
626-040A	BARRICADE TYPE 3	6.00	EACH
626-100A	MISC TEMPORARY TRAF CONT ITEMS	1,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	400.00	HR
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	448.00	SY

675-005A	SURVEY	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S501-15A	RETAINING WALL GRAVITY CONCRETE BLOCK	2,675.00	SF
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	10,000.00	CA
S913-05A	SP ROCK MULCH	160.00	CY
Z629-05A	MOBILIZATION	1.00	LS