

Key No. 22715 - SH-55, FARMWAY RD. TO MIDDLETON RD.
Canyon County

Item No	Description	QTY	Unit
104-005A	PARTNERING	100,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	150,000.00	CA
110-005A	TRAINING	15,973.00	HR
201-010A	CLEARING & GRUBBING	1.00	LS
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	385.00	EACH
202-010A	SELECTIVE REMOVAL OF STUMPS	16.00	EACH
203-006A	REMOVAL OF SIGN	120.00	EACH
203-010A	ASBESTOS REMOVAL AND DISPOSAL	50,000.00	CA
203-015A	REMOVAL OF BITUMINOUS SURFACE	171,723.00	SY
203-020A	REMOVAL OF BRIDGE - FULL ELIJAH DRAIN (APPROX 2808 SF)	1.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL PHYLLIS CANAL (APPROX 1226 SF)	1.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL WILSON DRAIN (APPROX 2496 SF)	1.00	EACH
203-021A	REMOVAL OF BRIDGE - PARTIAL DEER FLAT CANAL (APPROX 1440 SF)	1.00	EACH
203-030A	REMOVAL OF CONCRETE CULVERT FOREST CANAL WEST	1.00	EACH
203-030A	REMOVAL OF CONCRETE CULVERT ISAIAH DRAIN	1.00	EACH
203-030A	REMOVAL OF CONCRETE CULVERT FOREST CANAL EAST	1.00	EACH
203-035A	REMOVAL OF CONCRETE CULVERT (MONOLITHIC) 25.1 LATERAL	1.00	EACH
203-060A	REMOVAL OF CONCRETE SIDEWALK	4,237.00	SY
203-065A	REMOVAL OF CURB	2,313.00	FT
203-070A	REMOVAL OF CURB & GUTTER	6,265.00	FT
203-075A	REMOVAL OF FENCE	8,788.00	FT
203-080A	REMOVAL OF GUARDRAIL	500.00	FT
203-080B	REMOVAL OF BARRIER	77.00	FT
203-090A	REMOVAL OF INLET	23.00	EACH
203-095A	REMOVAL OF MANHOLE	3.00	EACH
203-122A	REMOVAL OF MISCELLANEOUS ITEMS	111.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS	625.00	FT
203-130A	REMOVAL OF PAVEMENT MARKINGS	272,050.00	FT
205-005A	EXCAVATION	191,743.00	CY
205-040A	GRANULAR BORROW	175,195.00	CY
205-060A	WATER FOR DUST ABATEMENT	17.00	MG
205-095A	SOFT SPOT REPAIR	60,000.00	CA
209-005A	SMALL DITCH	688.00	FT
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	10,776.00	CY
210-010A	STRUCTURE EXCAVATION SCHEDULE NO. 2	942.00	CY
210-015A	COMPACTING BACKFILL	11,095.00	CY
212-011A	FIBER WATTLE	3,216.00	FT
212-020A	SILT FENCE	55,553.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	8.00	EACH
212-095A	INLET PROTECTION	177.00	EACH
212-105A	WATER AND POLLUTION	75,000.00	CA
212-110A	WATER POLLUTION CONTROL MANAGER	1.00	LS
212-115A	EROSION CONTROL MAINTENANCE	2,200.00	HR
213-005A	TOPSOIL	7,182.00	CY

251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	75,000.00	CA
301-010A	GRANULAR SUBBASE	98,131.00	CY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	214,950.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	92,290.00	GAL
405-240A	MISCELLANEOUS PAVEMENT	1,873.00	SY
405-245A	APPROACH	100.00	EACH
405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T	16,860.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 1/2" PG 58-28	153.00	TON
405-435B	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 1/2" PG 64-28	8,871.00	TON
405-455B	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-5 1/2" PG 76-28	119,483.00	TON
431-005A	COLD MILLING	274.00	SY
502-025A	CONCRETE CLASS 40-A	583.90	CY
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	530.40	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	202.40	CY
502-385A	PRESTRESSED DECK BULB TEE GIRDER 78" TOP FLANGE X 37" DEPTH	1,266.70	FT
502-385A	PRESTRESSED DECK BULB TEE GIRDER 95" TOP FLANGE X 43" DEPTH	1,284.00	FT
502-435A	APPROACH SLAB	1,434.20	SY
503-005A	METAL REINFORCEMENT	111,605.00	LB
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	75,353.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	18,424.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	46,229.00	LB
504-035A	PEDESTRIAN / BICYCLE RAILING	2,242.60	FT
505-110A	PROVIDE & DRIVE 16" DIA STEEL SHELL PILE	5,844.00	FT
505-160A	PROV&DRIV TEST STEEL SHELL PILE (16")	456.00	FT
505-205B	PROV&INST 16" DIA PILE SHOES OR TIPS	96.00	EACH
505-215A	SPLICE STEEL PILE BEFORE DRIVING	51.00	EACH
505-215B	SPLICE STEEL PILE DURING DRIVING	188.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN ELIJAH DRAIN (1-1/4"x14"x24")	36.00	EA
507-005A	ELASTOMERIC BEARINGS PLAIN WILSON DRAIN (1-1/4"x14"x24")	40.00	EA
511-005A	CONCRETE WATERPROOF SYSTEM TYPE D	2,424.00	SY
521-005A	DYNAMIC PILE TESTING	5.00	EA
521-010A	CAPWAP ANALYSIS	10.00	EA
551-005A	PREPARED & PLACED PPC OVERLAY	2,900.80	SY
551-010A	FURNISHED PPC OVERLAY MATERIAL	70.50	CY
560-005A	DEWATERING FOUNDATION ELIJAH DRAIN	1.00	LS
560-005A	DEWATERING FOUNDATION FOREST CANAL EAST	1.00	LS
560-005A	DEWATERING FOUNDATION FOREST CANAL WEST	1.00	LS
560-005A	DEWATERING FOUNDATION ISAIAH DRAIN	1.00	LS
560-005A	DEWATERING FOUNDATION WILSON DRAIN	1.00	LS
560-005A	DEWATERING FOUNDATION CALDWELL WATERLINE	1.00	LS
560-005A	DEWATERING FOUNDATION DEER FLAT	1.00	LS
560-005A	DEWATERING FOUNDATION PEDESTRIAN UNDERPASS	1.00	LS
560-005A	DEWATERING FOUNDATION PHYLLIS CANAL	1.00	LS
566-010A	COMPRESSION EXPANSION JOINT (PER PLAN) 1"	292.50	FT
566-010A	COMPRESSION EXPANSION JOINT (PER PLAN) 1.5"	349.40	FT
574-005A	ANTI-GRAFFITI COATING	65,811.00	SF
576-005A	(GFRP) REINFORCEMENT	3,080.00	FT

578-005A	PRECAST CONCRETE CULVERT FOREST CANAL EAST 4' X 4' X 212' BOX	1.00	LS
578-005A	PRECAST CONCRETE CULVERT FOREST CANAL WEST 5' X 5' X 199' BOX	1.00	LS
578-005A	PRECAST CONCRETE CULVERT ISAIAH DRAIN 4' X 4' X 234' BOX	1.00	LS
578-005A	PRECAST CONCRETE CULVERT PHYLLIS CANAL 17'x8.5'x212' STIFFLEG	1.00	LS
578-005A	PRECAST CONCRETE CULVERT DEER FLAT 18'x7.58'x181' STIFFLEG	1.00	LS
584-005A	TEMPORARY SHORING ELIJAH DRAIN (APPROX 1320 SF)	1.00	LS
584-005A	TEMPORARY SHORING FOREST CANAL EAST 4' BOX (APPROX 299 SF)	1.00	LS
584-005A	TEMPORARY SHORING ISAIAH DRAIN 4' BOX (APPROX 338 SF)	1.00	LS
584-005A	TEMPORARY SHORING PEDESTRIAN UNDERPASS (APPROX 1442 SF)	1.00	LS
584-005A	TEMPORARY SHORING CALDWELL WATERLINE (APPROX 104 SF)	1.00	LS
584-005A	TEMPORARY SHORING DEER FLAT (APPROX 604 SF)	1.00	LS
584-005A	TEMPORARY SHORING PHYLLIS CANAL (APPROX 1736 SF)	1.00	LS
584-005A	TEMPORARY SHORING WILSON DRAIN (APPROX 901 SF)	1.00	LS
586-005A	UTILITY CONDUIT ELIJAH DRAIN (4 - 4" SCH 80 PVC, APPROX 1280 FT)	1.00	LS
586-005A	UTILITY CONDUIT WILSON DRAIN (4 - 4" SCH 80 PVC, APPROX 1120 FT)	1.00	LS
602-250A	PIPE ARCH 36.25" X 22.5"	227.00	FT
603-035A	18" PIPE SIPHON	224.00	FT
604-015A	8" IRRIGATION PIPE	639.00	FT
604-025A	12" IRRIGATION PIPE	2,000.00	FT
604-035A	18" IRRIGATION PIPE	3,963.00	FT
604-045A	24" IRRIGATION PIPE	3,079.00	FT
604-085A	48" IRRIGATION PIPE	231.00	FT
605-025A	12" STORM SEWER PIPE	9,027.00	FT
605-035A	18" STORM SEWER PIPE	9,884.00	FT
605-045A	24" STORM SEWER PIPE	3,774.00	FT
605-055A	30" STORM SEWER PIPE	62.00	FT
605-465A	MANHOLE TYPE C	120.00	EACH
605-467A	MANHOLE TYPE D	7.00	EACH
605-470A	SEDIMENT & OIL TRAP MANHOLE	12.00	EACH
605-505A	CATCH BASIN TYPE 1A	145.00	EACH
605-520A	CATCH BASIN TYPE 3	18.00	EACH
605-630A	INLET TYPE 8	9.00	EACH
605-635A	ADJUST MANHOLE COVERS	14.00	EACH
605-640A	ADJUST VALVE COVERS	11.00	EACH
608-025A	12" APRON FOR PIPE	14.00	EACH
608-035A	18" APRON FOR PIPE	9.00	EACH
608-045A	24" APRON FOR PIPE	7.00	EACH
608-055A	30" APRON FOR PIPE	1.00	EACH
609-025A	MINOR STRUCTURES 18" IRR HEADWALL	3.00	EACH
609-025A	MINOR STRUCTURES 24" CONCRETE HEADWALL	1.00	EACH
609-025A	MINOR STRUCTURES 25.1 LATERAL IRR INLET STRUCTURE	1.00	EACH
609-025A	MINOR STRUCTURES 5' IRR BOX STRUCTURE	50.00	EACH
609-025A	MINOR STRUCTURES FOREST CANAL LATERAL IRR BOX	1.00	EACH
609-025A	MINOR STRUCTURES LITTLE LATERAL IRR BOX 1	1.00	EACH

609-025A	MINOR STRUCTURES LITTLE LATERAL IRR BOX 2	1.00	EACH
609-025A	MINOR STRUCTURES STONE LATERAL IRR INLET STRUCTURE	1.00	EACH
609-025A	MINOR STRUCTURES 36.25" X 22.5" PIPE ARCH HEADWALL	1.00	EACH
609-025A	MINOR STRUCTURES 48" CULVERT HEADWALL	1.00	EACH
609-025A	MINOR STRUCTURES STEVENS WEST LATERAL INLET STRUCTURE	1.00	EACH
609-025A	MINOR STRUCTURES STEVENS WEST LATERAL OUTLET STRUCTURE	1.00	EACH
610-015A	FENCE TYPE 1 B	344.00	FT
610-035A	FENCE TYPE 4	500.00	FT
610-035A	FENCE TYPE 4 72"	7,064.00	FT
610-200A	GATE TYPE 3 20 FT DBL LEAF	10.00	EACH
610-250A	BRACES	8.00	EACH
612-150A	CONCRETE BARRIER	1,044.00	FT
612-155A	CONCRETE TERMINAL TYPE A	2.00	EACH
614-015A	SIDEWALK	58,919.00	SY
614-025A	CURB RAMP	1,381.00	SY
615-256A	CURB TYPE 1	37,771.00	FT
615-259A	CURB TYPE 4	396.00	FT
615-331A	GUTTER TYPE 1 MODIFIED	51.00	FT
615-491A	CURB & GUTTER TYPE 1 MODIFIED	651.00	FT
615-494A	CURB & GUTTER TYPE 4	29,906.00	FT
615-651A	TRAFFIC SEPARATOR TYPE 1	2,253.00	FT
616-010A	SIGN TYPE B-1	1,786.00	SF
616-020A	SIGN TYPE E	32.00	SF
616-040G	STEEL SIGN POST TYPE B-2	451.00	FT
616-040H	STEEL SIGN POST TYPE B-3	217.00	FT
616-040J	STEEL SIGN POST TYPE E-1	520.00	FT
616-040k	STEEL SIGN POST TYPE E-2	563.00	FT
616-055B	WOOD SIGN POST TYPE D-2	48.00	FT
616-080A	REINSTALL SIGN FACE	4.00	EACH
616-090A	SPECIAL INSTALL SIGN	27.00	EACH
616-100A	SIGN BRACES	2,072.00	LB
617-005A	DELINEATOR TYPE 1	59.00	EACH
617-010A	DELINEATOR TYPE 2	132.00	EACH
617-045A	DELINEATOR TYPE 9	65.00	EACH
617-055A	MILEPOST TYPE 2	10.00	EACH
619-010A	ILLUMINATION TYPE 2	1.00	LS
620-020A	PLANTING TREE (SEEDLING or CONTAINER) FRAXINUS PENNSYLVANICA	2.00	EACH
620-020B	PLANTING TREE (SEEDLING or CONTAINER) CRABAPPLE	1.00	EACH
620-020C	PLANTING TREE (SEEDLING or CONTAINER) ASH	2.00	EACH
621-005A	SEED BED PREPARATION	9.03	ACRE
621-010A	SEEDING	9.03	ACRE
621-035A	FERTILIZING	9.03	ACRE
621-060A	MULCH PLUS TACKIFIER	9.03	ACRE
624-005A	LOOSE RIPRAP D50 = 9"	1,253.00	CY
624-005A	LOOSE RIPRAP D50=12"	1,771.00	CY
624-005A	LOOSE RIPRAP D50=6"	391.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	5,587.00	SF
626-040A	BARRICADE TYPE 3	122.00	EACH

626-050A	DRUMS	887.00	EACH
626-076A	ARROW BOARD TYPE C	1,000.00	HR
626-100A	MISC TEMPORARY TRAF CONT ITEMS	50,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	14,240.00	HR
626-112A	FLOOD LIGHTS	15,000.00	HR
626-115B	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	2,453.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER	2,279.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	2,279.00	FT
626-118A	TEMPORARY CRASH CUSHION	12.00	EACH
626-120A	FLAGGER CONTROL	11,422.00	HR
626-121A	R&R TEMP CRASH CUSHION	12.00	EACH
626-135A	WEIGHTED BASE TUBULAR MARKERS	720.00	EACH
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	180.00	EACH
626-150A	AUTO FLAGGER ASSITANCE DEVICE (AFAD)	5,711.00	HR
630-005A	T,W,S,A PAVEMENT MARKINGS - WATERBORNE	7,069.00	SF
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	13,272.00	SF
630-025A	LONG PAV MKG - WATERBORNE	955,071.00	FT
640-005A	DRAINAGE GEOTEXTILE	4,032.00	SY
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	8,618.00	SY
640-015A	SUBGRADE SEPARATION GEOTEXTILE	355,575.00	SY
645-010A	C3 FIELD LAB - AGG, SOILS, SP 3 & SP 5	1.00	LS
656-010A	SIGNAL HOUSING	112.00	EACH
656-020B	INT DETECTION SYSTEM - RADAR	4.00	EACH
656-025A	ELECTRICAL SERVICE PEDESTAL TYPE 1	1.00	EACH
656-025C	ELECTRICAL SERVICE PEDESTAL TYPE 3	4.00	EACH
656-030A	INTERSECTION SIGNAL STRUCTURE	5.00	EACH
656-035A	INTERSECTION PEDESTRIAN SYSTEM	6.00	EACH
656-040A	SIGNAL CABINET	4.00	EACH
656-045A	SIGNAL CONTROLLER	4.00	EACH
656-050A	PED & TRAFF CNTL SIG HEAD FRANG POLES	34.00	EACH
656-065A	COMB CAB & SVS PEDESTAL FOUNDATION	4.00	EACH
656-070A	ADDITIONAL ELECTRICAL ITEMS	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	120,000.00	CA
S501-15A	RETAINING WALL CALDWELL MSE WALL	7,141.00	SF
S501-15A	RETAINING WALL	7,070.00	SF
S501-19A	SOUND WALL CRESTWOOD 1	6,216.00	SF
S501-19A	SOUND WALL CRESTWOOD 2	5,782.00	SF
S501-19A	SOUND WALL FIELDCREST	13,527.00	SF
S501-19A	SOUND WALL LAKEVIEW	3,093.00	SF
S501-25A	SP BRIDGE PRE-FABRICATED STEEL TRUSS	1.00	LS
S501-30A	SP BRIDGE SOUND WALL DRILLED SHAFTS (2.5' DIAMETER)	3,974.00	FT
S501-40A	SP BRIDGE HIGH EARLY STRENGTH CONCRETE CLASS 50AF	372.40	CY
S501-75A	ELECTRICAL ITEMS UNDERPASS LIGHTING	1.00	LS
S600-20A	FIRE HYDRANT ASSEMBLY	4.00	EACH
S600-45A	WATER LINE 8" C900 DR-18	173.00	FT
S600-45A	WATER LINE 12" C900 DR-18	11,123.00	FT
S600-45A	WATER LINE 16" C900 DR-18	267.00	FT
S601-05A	SLOTTED DRAIN	38.00	FT

S900-50A	CONTINGENCY AMOUNT UNDERGROUND STRUCTURE REMOVAL	25,000.00	CA
S900-50B	CONTINGENCY AMOUNT LEAD REMOVAL AND DISPOSAL	15,000.00	CA
S900-50C	CONTINGENCY AMOUNT FIELD INVESTIGATION FOR EXISTING PIPES	75,000.00	CA
S901-05A	SP REMOVAL OF SIGNAL SYSTEM	5.00	EACH
S901-05B	SP FIBER OPTIC PULL BOX	52.00	EACH
S901-05C	SP FIBER OPTIC CABLE VAULT	8.00	EACH
S901-05D	SP RELOCATE EXISTING PRE-EMPTION DETECTION SYSTEM	5.00	EACH
S901-05E	SP SURFACE MOUNTED DELINEATORS	769.00	EACH
S901-05F	SP ABANDON AND CAP WELL	7.00	EACH
S901-05G	SP REMOVE SEPTIC SYSTEM	3.00	EACH
S901-05H	SP IRRIGATION SERVICE RELOCATION	1.00	EACH
S901-05I	SP REMOVAL OF IRRIGATION STRUCTURE	36.00	EACH
S901-05J	SP PRE-DEMOLITION ASBESTOS INVESTIGATION AND PAINT SAMPLING	5.00	EACH
S901-05K	SP DITCH BERM	131.00	EACH
S901-05L	SP REMOVE AND RELOCATE MAILBOX	42.00	EACH
S901-05M	SP REMOVE AND RESET SECURITY GATE	1.00	EACH
S901-05N	SP REMOVE AND RESET GATE	3.00	EACH
S901-05O	SP WROUGHT IRON GATE (20')	1.00	EACH
S901-05P	SP ADJUST FIRE HYDRANT	2.00	EACH
S901-05Q	SP IRRIGATION DITCH PIPE CONNECTION	30.00	EACH
S901-05R	SP 8" IRRIGATION GATE VALVE	4.00	EACH
S901-05S	SP HIGH FLOW BYPASS MANHOLE	10.00	EACH
S901-05T	SP 48" MANHOLE	3.00	EACH
S901-05U	SP 72" DOGHOUSE MANHOLE	2.00	EACH
S901-05V	SP REMOVE AND REPLACE FIRE HYDRANT ASSEMBLY	8.00	EACH
S901-05W	SP AIR/VAC COMBINATION VALVE	2.00	EACH
S901-05X	SP WATER & IRRIGATION LINE RELOCATION	11.00	EACH
S901-05Y	SP FLAT-LID MANHOLE COVER	2.00	EACH
S901-05Z	SP RELOCATE LUMINAIRE	4.00	EACH
S901-06A	SP HEAVY DUTY MANHOLE LID	92.00	EACH
S901-06B	SP TRIM TREE	1.00	EACH
S901-06C	SP CALDWELL MANHOLE TYPE A	3.00	EACH
S901-06D	SP 12" GATE VALVE	34.00	EACH
S901-06E	SP BOLLARD	2.00	EACH
S901-06F	SP TEMPORARY BLOW-OFF	1.00	EACH
S901-06G	SP 2" AIR/VAC COMBINATION VALVE	2.00	EACH
S901-06H	SP 3" AIR/VAC COMBINATION VALVE	15.00	EACH
S901-06I	SP WATER LINE RELOCATION	5.00	EACH
S901-06J	SP 16" BUTTERFLY GATE VALVE	2.00	EACH
S901-06K	SP 8" GATE VALVE	1.00	EACH
S904-05A	SP SIGNAL TIMING TEMP MODS	1.00	LS
S904-05B	SP IRRIGATION REPAIR	1.00	LS
S904-05C	SP MAINTAIN EXISTING LANDSCAPING AND SPRINKLER SYSTEM	1.00	LS
S904-05D	SP TEMPORARY SIGNAL - SPAN WIRE	1.00	LS
S904-05E	SP INSTALL RADAR TYPE AUTOMATIC TRAFFIC REC ORDER (1)	1.00	LS
S904-05F	SP INSTALL RADAR TYPE AUTOMATIC TRAFFIC REC ORDER (2)	1.00	LS
S904-05G	SP LAKEVIEW APARTMENTS BUILDING 3 & 4 SEWAGE DISPOSAL DESIGN	1.00	LS

S904-05H	SP LAKEVIEW APARTMENTS BUILDING 5 SEWAGE DI SPOSAL DESIGN	1.00	LS
S904-05I	SP LAKEVIEW WELL NO. 3 ABANDONMENT	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 139)	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 158)	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 159)	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 166)	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 35)	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 143)	1.00	LS
S904-05J	SP STRUCTURE DEMO AND SITE CLEANUP (PARCEL 150)	1.00	LS
S904-05K	SP SECURITY CAMERA SYSTEM	1.00	LS
S904-05L	SP UTILITY COORDINATOR	1.00	LS
S911-05A	SP WROUGHT IRON FENCE (5')	655.00	FT
S911-05B	SP REMOVAL OF PIPE	27,005.00	FT
S911-05C	SP DITCH (CONCRETE)	2,548.00	FT
S911-05D	SP DITCH (FIELD DRAIN)	16,856.00	FT
S911-05E	SP CONDUIT (1-1/4")	163,440.00	FT
S911-05F	SP TEMPORARY FENCING	4,511.00	FT
S911-05G	SP ORANGE SAFETY FENCING	1,500.00	FT
S911-05I	SP INFILTRATION TRENCH (TYPE 1)	15,953.00	FT
S911-05I	SP INFILTRATION TRENCH (TYPE 2)	1,281.00	FT
S911-05I	SP INFILTRATION TRENCH (TYPE 3)	756.00	FT
S911-05I	SP INFILTRATION TRENCH (TYPE 4)	2,080.00	FT
S911-05J	SP REMOVAL OF CONCRETE DITCH	3,051.00	FT
S911-05K	SP REMOVE AND RESET FENCE	405.00	FT
S911-05M	SP VINYL FENCE	601.00	FT
S911-05N	SP WOOD FENCE	345.00	FT
S911-05R	SP 8" GRAVITY SEWER	388.00	FT
S911-05S	SP 24" GRAVITY SEWER	68.00	FT
S911-05T	SP 18" PRESSURE SEWER	480.00	FT
S911-05U	SP 18" STEEL CASING PIPE	405.00	FT
S911-05V	SP 24" STEEL CASING PIPE	85.00	FT
S911-05W	SP 30" STEEL CASING	156.00	FT
S911-05X	SP RELOCATE WATER LINE	336.00	FT
S911-06A	SP 12" SDR-35 SEWER PIPE	267.00	FT
S911-06B	SP 30" STEEL CASING	260.00	FT
S911-06C	SP 28" STEEL CASING	325.00	FT
S911-06D	SP 20" STEEL CASING	2,086.00	FT
S912-05A	SP LANDSCAPE AND IRRIGATION REPAIR	9,790.00	SY
S912-05B	SP MEDIAN CONCRETE	20,622.00	SY
S912-05D	SP SLOPE TREATMENT TYPE I	101,373.00	SY
S912-05E	SP WEED BARRIER	89,421.00	SY
S912-05F	SP SURFACE RESTORATION	18.00	SY
S912-05G	SP SLOPE TREATMENT TYPE 2	89,421.00	SY
S913-05A	SP FILTER SAND	7,298.00	CY
S913-05B	SP STORMWATER SEEPAGE BED	1,194.00	CY
S915-05A	SP STAIRS	768.00	SF
Z629-05A	MOBILIZATION	1.00	LS