

Key No. 22770 - SH-54, SH-41 to GREYSTONE LANE  
Kootenai County

Item No	Description	QTY	Unit
104-005A	PARTNERING	32,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	15,000.00	CA
110-005A	TRAINING	2,609.00	HR
201-010A	CLEARING & GRUBBING	1.00	LS
203-005A	REMOVAL OF OBSTRUCTIONS (DELINEATORS)	1.00	LS
203-006A	REMOVAL OF SIGN	38.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	129,741.30	SY
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (CMP 24" AND SMALLER)	995.50	FT
203-130A	REMOVAL OF PAVEMENT MARKINGS	10,000.00	FT
205-005A	EXCAVATION	153,100.00	CY
205-040A	GRANULAR BORROW	8,300.00	CY
205-060A	WATER FOR DUST ABATEMENT	11,549.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	300.00	CY
212-011A	FIBER WATTLE	14,833.00	FT
212-020A	SILT FENCE	9,146.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	6.00	EACH
212-105A	WATER AND POLLUTION	15,000.00	CA
212-110A	WATER POLLUTION CONTROL MANAGER	1.00	LS
213-005A	TOPSOIL	24,754.00	CY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	5,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	104,200.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	36,750.00	GAL
405-245A	APPROACH	70.00	EACH
405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T	1,000.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	56,800.00	TON
602-035A	18" PIPE CULVERT	1,519.00	FT
602-045A	24" PIPE CULVERT	138.00	FT
608-205A	METAL SAFETY APRON (PARALLEL) (18" parallel 10:1)	47.00	EACH
608-205B	METAL SAFETY APRON (PARALLEL) (18" PARALLEL 6:1)	1.00	EACH
608-210A	METAL SAFETY APRON (CROSS DRAINAGE) (24" CROSS DRAIN 10:1)	3.00	EACH
608-210B	METAL SAFETY APRON (CROSS DRAINAGE) (24" CROSS DRAIN 4:1)	3.00	EACH
616-010A	SIGN TYPE B-1	786.50	SF
616-015A	SIGN TYPE C-1	43.50	SF
616-055A	WOOD SIGN POST TYPE D-1 (4"x4")	10.50	FT
616-055B	WOOD SIGN POST TYPE D-2 (4"x6")	772.50	FT
616-055C	WOOD SIGN POST TYPE D-3 (6"x6")	362.00	FT
616-055D	WOOD SIGN POST TYPE D-4 (6"x8")	164.00	FT
616-080A	REINSTALL SIGN FACE	7.00	EACH
616-100A	SIGN BRACES	1,364.00	LB
617-010A	DELINEATOR TYPE 2	172.00	EACH
617-020A	DELINEATOR TYPE 4	20.00	EACH
617-060A	MILEPOST TYPE 3	6.00	EACH
618-025A	STREET MONUMENT	10.00	EACH
619-010A	ILLUMINATION TYPE 2	1.00	LS
621-005A	SEED BED PREPARATION	33.23	ACRE

621-010A	SEEDING	33.23	ACRE
621-035A	FERTILIZING	33.23	ACRE
621-060A	MULCH PLUS TACKIFIER	33.23	ACRE
621-061A	MULCH PLUS TACKIFIER (TEMPORARY)	65,000.00	SY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	875.00	SF
626-050A	DRUMS	655.00	EACH
626-092A	TEMPORARY PAVEMENT MARKING TAPE	2,500.00	FT
626-093A	TEMP PAV MARKING - WATERBORNE	150,000.00	FT
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	5,000.00	HR
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	500.00	DAY
626-120A	FLAGGER CONTROL	6,200.00	HR
626-125A	PILOT CAR	1,280.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	100.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	1,282.00	SF
630-025A	LONG PAV MKG - WATERBORNE	250,310.00	FT
634-005A	MAILBOX (TYPE A WOOD, SIZE 2)	18.00	EACH
634-005B	MAILBOX (TYPE B, SIZE 2)	13.00	EACH
634-010A	MAILBOX SNOW SHIELD	30.00	EACH
640-015A	SUBGRADE SEPARATION GEOTEXTILE	450.00	SY
641-005A	BIAXIAL GEOGRID	450.00	SY
645-004A	C1 FIELD LAB - AGG & SOILS	1.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	20,000.00	CA
S900-50G	CONTINGENCY AMOUNT MISC WORK	25,000.00	CA
S901-05A	SP STORMWATER BERM	163.00	EACH
S901-05B	SP MOVE AND RESET LUMINAIRE	1.00	EACH
S911-05E	SP PAVEMENT JOINT ADHESIVE	39,766.50	FT
S913-05A	SP ROCK ARMOR	2,154.00	CY
Z629-05A	MOBILIZATION	1.00	LS