

Key No. 22878 - HOMEDALE ROAD CURVE IMPROVEMENTS
Canyon County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	5,000.00	CA
203-006A	REMOVAL OF SIGN	8.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL	1.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS - PIPE	92.00	FT
205-005A	EXCAVATION	870.00	CY
205-040A	GRANULAR BORROW	250.00	CY
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	470.00	CY
210-015A	COMPACTING BACKFILL	376.00	CY
212-011A	FIBER WATTLE	947.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	2.00	EACH
301-005A	GRANULAR SUBBASE	1,000.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	320.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	55.00	GAL
405-245A	APPROACH	4.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	110.00	TON
511-005A	CONCRETE WATERPROOF SYSTEM - TYPE D	220.00	SY
578-005A	PRECAST CONCRETE CULVERT - STIFFLEG	1.00	LS
604-025A	12" IRRIGATION PIPE	112.00	FT
605-460A	MANHOLE TYPE B	2.00	EACH
609-025A	MINOR STRUCTURES	1.00	EACH
615-331A	GUTTER TYPE 1	40.00	FT
616-010A	SIGN TYPE B-1	20.00	SF
616-055A	WOOD SIGN POST TYPE D-1	40.50	FT
616-055B	WOOD SIGN POST TYPE D-2	14.00	FT
621-005A	SEED BED PREPARATION	0.17	ACRE
621-010A	SEEDING	0.17	ACRE
621-060A	MULCH PLUS TACKIFIER	0.17	ACRE
624-005A	LOOSE RIPRAP - D=12"	120.00	CY
624-005B	LOOSE RIPRAP - D=6"	55.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	483.00	SF
626-040A	BARRICADE TYPE 3	9.00	EACH
626-100A	MISC TEMPORARY TRAF CONT ITEMS	1,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	400.00	HR
630-025A	LONG PAV MKG - WATERBORNE	828.00	FT
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	100.00	SY
675-005A	SURVEY	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	5,000.00	CA
Z629-05A	MOBILIZATION	1.00	LS