

Key No. 22882 - INT 3800 N & US-93, FILER HD
Twin Falls County

Item No	Description	QTY	Unit
203-055A	REMOVAL OF CONCRETE PAVEMENT	18.20	SY
205-005A	EXCAVATION	1,266.00	CY
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	70.00	CY
212-011A	FIBER WATTLE	442.00	FT
303-022A	3/4" AGGR TY B FOR BASE	3,370.00	TON
308-005A	CEM RECYCLED ASPH BASE STAB	11,130.00	SY
308-010A	PORTLAND CEM	151.00	TON
308-015A	PULVERIZE EXISTING SURF	10,190.00	SY
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	560.00	GAL
402-020A	EMUL ASPH FOR PRIME COAT	8.60	TON
405-245A	APPROACH (ASPHALT)	14.00	EACH
405-245B	APPROACH (GRAVEL)	3.00	EACH
405-245C	APPROACH (CONCRETE)	1.00	EACH
405-325A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP- 2	2,390.00	TON
502-020A	CONC CL 40	4.00	CY
605-035A	18" STORM SEWER PIPE	97.00	FT
605-630A	INLET TY 8	2.00	EACH
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	429.00	SF
626-040A	BARRICADE TY 3	10.00	EACH
626-100B	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
626-105A	TRAF CNTL MAINTENANCE	54.00	HR
626-120A	FLAGGER CONTROL	40.00	HR
630-020B	PAV MKG - PREFORMED THERMOPLASTIC	103.90	SF
630-025A	LONGITUDINAL PAV MKG- WATERBORNE	7,826.00	FT
634-005A	MAILBOX (TYPE A ASSEMBLY)	3.00	EACH
634-005B	MAILBOX (TYPE B ASSEMBLY)	2.00	EACH
640-015A	SUBGRADE SEPARATION GEOTEXTILE - TYPE III	200.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING OFFICE COMPUTATIONS	5,000.00	CA
675-015A	DIRECTED SURVEYING CREW	5,000.00	CA
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	5,000.00	CA
S915-05A	SP - FULL LANE WIDTH RUMBLE STRIPS	1,350.00	SF
Z629-05A	MOBILIZATION	1.00	LS