Bid Items List

Key No. 23028 - PRAIRIE AVE; MEYER RD TO SH-41

Kootenai County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	5,000.00	CA
201-005A	CLEARING & GRUBBING	7.95	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	8.00	EACH
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-006A	REMOVAL OF SIGN	17.00	EACH
203-055A	REMOVAL OF CONCRETE PAVEMENT	68.00	SY
203-075A	REMOVAL OF FENCE	1,743.00	FT
203-122A	REMOVAL OF MISCELLANEOUS ITEMS GATE STRUCTURE	1.00	EACH
203-122B	REMOVAL OF MISCELLANEOUS ITEMS DELINEATOR	51.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS CULVERT	67.00	FT
203-130A	REMOVAL OF PAVEMENT MARKINGS	6,134.00	FT
205-005A	EXCAVATION	11,714.00	CY
205-040A	GRANULAR BORROW	9,399.00	CY
205-060A	WATER FOR DUST ABATEMENT	14,400.00	MG
205-071A	EXCAVATION AND REPAIR OF SOFT SPOTS	850.00	CY
212-095A	INLET PROTECTION	10.00	EACH
212-105A	WATER AND POLLUTION	10,000.00	CA
213-005A	TOPSOIL	2,459.00	CY
301-005A	GRANULAR SUBBASE	16,524.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	8,107.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	1,867.00	GAL
405-240A	MISCELLANEOUS PAVEMENT	948.90	SY
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 NMAS 1/2", PG 64-28	5,788.00	TON
502-015A	CONCRETE CLASS 30	11.20	CY
605-640A	ADJUST VALVE COVERS	4.00	EACH
610-015A	FENCE TYPE 1 B	1,567.00	FT
610-300A	TEMPORARY FENCE TYPE 1 B	1,645.00	FT
614-015A	SIDEWALK	459.10	SY
614-020A	DRIVEWAY	262.20	SY
614-025A	CURB RAMP PEDESTRIAN	129.40	SY
614-025B	CURB RAMP BICYCLE	95.60	SY
615-256A	CURB TYPE 1	49.00	FT
615-257A	CURB TYPE 2	167.00	FT
615-490A	CURB & GUTTER POST FALLS	7,133.00	FT
615-651A	TRAFFIC SEPARATOR TYPE 1	69.00	FT
616-010A	SIGN TYPE B-1	145.00	SF
616-040J	STEEL SIGN POST TYPE E-1	74.50	FT
616-040K	STEEL SIGN POST TYPE E-2	191.70	FT
619-010A	ILLUMINATION TYPE 2	1.00	LS
621-005A	SEED BED PREPARATION	4.58	ACRE
621-010A	SEEDING	4.58	ACRE
621-035A	FERTILIZING	4.58	ACRE
621-060A	MULCH PLUS TACKIFIER	4.58	ACRE

626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	350.00	SF
626-040A	BARRICADE TYPE 3	6.00	EACH
626-050A	DRUMS	100.00	EACH
626-100A	MISC TEMPORARY TRAF CONT ITEMS	10,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	1,000.00	HR
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	14.00	DAY
626-120A	FLAGGER CONTROL	250.00	HR
626-140A	SURFACE-MOUNTED TUBULAR MARKERS	4.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	962.00	SF
630-020A	LONG PAV MKG- PREFORMED THERMOPLASTIC	2,156.00	FT
630-025A	LONG PAV MKG - WATERBORNE	64,980.00	FT
640-015A	SUBGRADE SEPARATION GEOTEXTILE	25,324.00	SY
657-020A	RRFB, SOLAR POWERED	6.00	LS
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	5,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S637-10A	AGGR BASE FOR SHARED-USE PATH	1,708.00	TON
S637-15A	PLANTMIX FOR SHARED-USE PATH	866.00	TON
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	10,000.00	CA
S901-05A	SP DRAINAGE CURB CUT	82.00	EACH
S901-05B	SP RELOCATE RRFB	4.00	EACH
S901-05C	SP ABANDON DRYWELL	2.00	EACH
S901-05D	SP ADJUST FIRE HYDRANT TO GRADE	2.00	EACH
S901-05E	SP RELOCATE MAILBOX ASSEMBLY	2.00	EACH
S901-05F	SP REMOVE AND RESET GATE	1.00	EACH
S901-05G	SP DRYWELL SINGLE DEPTH	1.00	EACH
S901-05H	SP DRYWELL DOUBLE DEPTH	7.00	EACH
Z629-05A	MOBILIZATION	1.00	LS