Bid Items List

Key No. 23244 - US-20, MP 291 TO IDAHO FALLS

Bonneville County

Item No	Description	QTY	Unit
104-005A	PARTNERING	50,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	140,000.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	20,000.00	CA
110-005A	TRAINING	7,200.00	HR
201-005A	CLEARING & GRUBBING	339.55	ACRE
203-005A	REMOVAL OF OBSTRUCTIONS	1.00	LS
203-006A	REMOVAL OF SIGN	56.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS (PIPE)	4,342.00	FT
203-130A	REMOVAL OF PAVEMENT MARKINGS	122,203.00	FT
203-130B	REMOVAL OF PAVEMENT MARKINGS	256.00	SF
205-005A	EXCAVATION (TYPE A)	645,295.00	CY
205-005B	EXCAVATION (TYPE B)	624,052.00	CY
205-060A	WATER FOR DUST ABATEMENT	46,034.00	MG
205-095A	SOFT SPOT REPAIR	25,000.00	CA
212-011A	FIBER WATTLE	600.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	4.00	EACH
212-095A	INLET PROTECTION	42.00	EACH
213-010A	TOPSOIL	1,148,732.00	SY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	10,000.00	CA
301-005A	GRANULAR SUBBASE	681,657.00	TON
307-012A	OPEN-GRADED BASE CLASS III	207,250.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	40,000.00	GAL
405-245A	APPROACH (PUBLIC, PRIVATE & COMMERCIAL)	30.00	EACH
405-245B	APPROACH (FARM, FIELD)	5.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	118,500.00	TON
408-010A	DILUTED EMULSIFIED ASPHALT FOR FOG COAT	1,500.00	GAL
578-005A	PRECAST CONCRETE CULVERT (#1)	1.00	LS
578-005B	PRECAST CONCRETE CULVERT (#2)	1.00	LS
602-045A	24" PIPE CULVERT	9,040.00	FT
602-055A	30" PIPE CULVERT	1,267.00	FT
602-065A	36" PIPE CULVERT	542.00	FT
602-075A	42" PIPE CULVERT	329.00	FT
602-085A	48" PIPE CULVERT	588.00	FT
605-035A	18" STORM SEWER PIPE	2,584.00	FT
605-045A	24" STORM SEWER PIPE	457.00	FT
605-630A	INLET TYPE 8	38.00	EACH
608-045A	24" APRON FOR PIPE	68.00	EACH
608-205A	METAL SAFETY APRON (PARALLEL) (18")	68.00	EACH
608-205B	METAL SAFETY APRON (PARALLEL) (24")	8.00	EACH
609-025B	MINOR STRUCTURES (30" CONCRETE HEADWALL)	10.00	EACH
609-025C	MINOR STRUCTURES (36" CONCRETE HEADWALL)	4.00	EACH
609-025D	MINOR STRUCTURES (42" CONCRETE HEADWALL)	2.00	EACH
610-010A	FENCE TYPE 1 A	5,910.00	FT

610-101A	GATE TYPE 1A	1.00	EACH
610-250A	BRACES	11.00	EACH
616-010A	SIGN TYPE B-1	1,579.00	SF
616-040H	STEEL SIGN POST TYPE B-3 (5"x5")	257.00	FT
616-055B	WOOD SIGN POST TYPE D-2 (4"x6")	758.00	FT
616-055C	WOOD SIGN POST TYPE D-3 (6"x6")	727.00	FT
616-055D	WOOD SIGN POST TYPE D-4 (6"x8")	204.00	FT
616-080A	REINSTALL SIGN FACE	12.00	EACH
616-100A	SIGN BRACES	2,718.40	LB
617-010A	DELINEATOR TYPE 2	198.00	EACH
617-020A	DELINEATOR TYPE 4	103.00	EACH
617-050A	MILEPOST TYPE 1	20.00	EACH
621-005A	SEED BED PREPARATION	211.53	ACRE
621-010A	SEEDING	211.53	ACRE
621-035A	FERTILIZING	211.53	ACRE
621-060A	MULCH PLUS TACKIFIER	211.53	ACRE
624-005A	LOOSE RIPRAP (CLASS I)	441.20	CY
624-005B	LOOSE RIPRAP (CLASS III)	138.00	CY
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	1,882.00	SF
626-040A	BARRICADE TYPE 3	5.00	EACH
626-050A	DRUMS	16.00	EACH
626-076B	ARROW BOARD TYPE C	800.00	DAY
626-093A	TEMP PAV MARKING - WATERBORNE	100,674.00	FT
626-100A	MISC TEMPORARY TRAF CONT ITEMS	10,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	6,800.00	HR
626-112B	FLOOD LIGHTS	100.00	DAY
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	400.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER	18,765.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	38,100.00	FT
626-118A	TEMPORARY CRASH CUSHION	8.00	EACH
626-120A	FLAGGER CONTROL	1,000.00	HR
626-135A	WEIGHTED BASE TUBULAR MARKERS	250.00	EACH
628-010A	SNOW POLE	301.00	EACH
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	1,854.00	SF
630-025A	LONG PAV MKG - WATERBORNE	534,670.00	FT
631-010A	RUMBLE STRIPS	40.00	MILE
634-005A	MAILBOX	12.00	EACH
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	2,562.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	50,000.00	CA
676-015A	RECORD AND REESTABLISH PAV MARKINGS	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT (DIRECTED REPAIRS)	50,000.00	CA
S901-05A	SP MINOR STR (DUAL 48" CONC HEADWALL)	2.00	EACH
S901-05B	SP CONC JUNCTION BOX	1.00	EACH
S901-05C	SP REMOVE AND RESET ATR	2.00	EACH
S901-05D	SP REMOVE AND RESET LUMINAIRE	1.00	EACH
S901-07A	SP GPS INSPECTION UNIT	2.00	EACH
S904-05A	SP REPLACEMENT OF ATR TRAFFIC SENSOR LOOPS (MP 295.02)	2.00	LS

S904-05C	SP CROSSOVERS	1.00	LS
S904-05D	SP TEMPORARY RAMP	1.00	LS
S904-06A	SP AUTOMATED MACHINE GUIDANCE (AMG)	1.00	LS
S913-05A	SP DITCH BERM	5,651.80	CY
Z629-05A	MOBILIZATION	1.00	LS