Bid Items List

Key No. 23257 - SH-3, ST MARIES RIVER BR

Shoshone County

Item No	Description	QTY	Unit
104-005A	PARTNERING	10,000.00	CA
105-010A	DISPUTE REVIEW BOARD - THREE MEMBER	7,500.00	CA
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
110-005A	TRAINING	665.00	HR
201-005A	CLEARING & GRUBBING	1.40	ACRE
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	1.00	EACH
203-006A	REMOVAL OF SIGN	6.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE	1,346.00	SY
203-020A	REMOVAL OF BRIDGE - FULL	1.00	EACH
203-130A	REMOVAL OF PAVEMENT MARKINGS	2,362.00	FT
205-005A	EXCAVATION	4,500.00	CY
205-040A	GRANULAR BORROW	1,300.00	CY
205-060A	WATER FOR DUST ABATEMENT	100.00	MG
205-095A	SOFT SPOT REPAIR	10,000.00	CA
205-100A	GUARDRAIL TERMINAL GRADING	2.00	EACH
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1	362.00	CY
210-015A	COMPACTING BACKFILL	153.00	CY
212-011A	FIBER WATTLE	748.00	FT
212-020A	SILT FENCE	1,306.00	FT
212-060A	STABILIZED CONSTRUCTION ENTRANCE	4.00	EACH
212-105A	WATER AND POLLUTION	25,000.00	CA
212-110A	WATER POLLUTION CONTROL MANAGER	1.00	LS
213-005A	TOPSOIL	213.00	CY
251-005A	MIGRATORY BIRD TREATY ACT COMPLIANCE	5,000.00	CA
301-010A	GRANULAR SUBBASE	153.00	CY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	1,900.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	200.00	GAL
405-410A	SUPERPAVE HMA PAVEMENT CLASS SP-T	155.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	355.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	96.40	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	206.20	CY
502-435A	APPROACH SLAB	214.50	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	19,275.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	14,636.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	23,661.00	LB
504-005A	STEEL BRIDGE (222,770 LBS)	1.00	LS
504-050A	3-TUBE CURB MOUNT RAIL	321.40	FT
505-045A	PROVIDE & DRIVE STEEL H PILE (14 X 117)	360.00	FT
505-197A	PROVIDE & DRIVE TEST PILE (HP-14 x 117)	72.00	FT
505-205C	PROVIDE & INSTALL PILE SHOES OR TIPS	12.00	EACH
507-005A	ELASTOMERIC BEARINGS PLAIN (1/2" X 14" X 20")	12.00	EA
520-005A	PREDRILLING FOR PILING IN SOIL	348.00	FT
551-005A	PREPARED & PLACED PPC OVERLAY	798.90	SY

551-010A	FURNISHED PPC OVERLAY MATERIAL	19.40	CY
560-005A	DEWATERING FOUNDATION	1.00	LS
566-005A	COMPRESSION EXPANSION JOINT (1 1/2")	95.30	FT
576-005A	(GFRP) REINFORCEMENT	480.00	FT
584-005A	TEMPORARY SHORING (APPROX. 525 SF)	1.00	LS
584-005B	TEMPORARY SHORING (APPROX. 794 SF)	1.00	LS
586-005A	UTILITY CONDUIT (COMPLETE WITH HANGERS APPROX. 760 FT)	1.00	LS
612-005A	W-BEAM GUARDRAIL	189.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	2.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	2.00	EACH
613-030A	CRASH CUSHION, PARTIALLY REUSABLE	2.00	EACH
616-010A	SIGN TYPE B-1	26.00	SF
616-055C	WOOD SIGN POST TYPE D-3 D3	41.00	FT
616-100A	SIGN BRACES	35.00	LB
617-010A	DELINEATOR TYPE 2	2.00	EACH
617-045A	DELINEATOR TYPE 9	9.00	EACH
621-005A	SEED BED PREPARATION	0.27	ACRE
621-010A	SEEDING	0.27	ACRE
621-035C	FERTILIZING	0.27	ACRE
621-065A	HYDRA APPLIED EROSION CONTROL PROD	0.27	ACRE
624-005A	LOOSE RIPRAP (CLASS I)	16.50	CY
624-005B	LOOSE RIPRAP (CLASS V)	1,073.00	CY
626-100A	MISC TEMPORARY TRAF CONT ITEMS	20,000.00	CA
626-130B	TEMPORARY TRAFFIC CONTROL SIGNAL	230.00	DAY
628-006A	SNOW POLE TYPE F	2.00	EACH
630-025A	LONG PAV MKG - WATERBORNE	7,533.00	FT
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE (HIGH STRENGTH)	1,230.00	SY
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	10,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT (DIRECTED LANDSCAPING)	10,000.00	CA
S904-05A	SP TEMPORARY DIVERSION	1.00	LS
S904-05B	SP TURBIDITY MONITORING	1.00	LS
S904-05C	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
S911-05E	SP PAVEMENT JOINT ADHESIVE	500.00	FT
S913-05A	SP STREAMBED MATERIAL	1,330.00	CY
Z629-05A	MOBILIZATION	1.00	LS