

Key No. 23284 - ROADWAY & GUARDRAIL IMPROVEMENTS, LAKES HD  
Kootenai County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	8,000.00	CA
201-010A	CLEARING & GRUBBING	1.00	LS
202-005A	SELECTIVE REM OF TREES INCLUDING STUMPS	1.00	EACH
205-100A	GUARDRAIL TERMINAL GRADING	12.00	EACH
212-105A	WATER AND POLLUTION	5,000.00	CA
612-005A	W-BEAM GUARDRAIL	1,450.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT (TL-2), (TL-3)	12.00	EACH
616-010A	SIGN TYPE B-1	9.00	SF
616-055C	WOOD SIGN POST TYPE D-3 - D-3	20.00	FT
616-100A	SIGN BRACES	19.36	LB
626-100A	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
634-005A	MAILBOX (TYPE B ASSEMBLY) - (5 - SIZE 1, 1 - SIZE 2, BOXES)	2.00	EACH
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	2,000.00	CA
S900-50A	CONTINGENCY AMOUNT - MISCELLANEOUS WORK	5,000.00	CA
S900-50B	CONTINGENCY AMOUNT - UNIDENTIFIED UTILITIES	5,000.00	CA
S900-50C	CONTINGENCY AMOUNT - Directed Traffic Control	60,000.00	CA
S901-05A	SP - LINEAR DELINEATOR	34.00	EACH
S901-05B	SP - RUMBLE STRIPS	5.00	EACH
S901-05C	SP - AGGREGATE APPROACH	1.00	EACH
S904-05A	SP - TEMPORARY TRAFFIC CONTROL	1.00	LS
Z629-05A	MOBILIZATION	1.00	LS