

Key No. 23290 - WAHA & LAPWAI RD CURVES
Nez Perce County

Item No	Description	QTY	Unit
201-010A	CLEARING & GRUBBING	1.00	LS
203-006A	REMOVAL OF SIGN	5.00	EACH
203-015A	REMOVAL OF BITUMINOUS SURFACE ~7"	3,882.00	SY
203-122A	REMOVAL OF MISCELLANEOUS ITEMS DELINEATOR	23.00	EACH
203-123A	REMOVAL OF MISCELLANEOUS ITEMS CULVERT	69.60	FT
203-125A	REMOVAL OF MISCELLANEOUS ITEMS BLOCK WALL	1.00	LS
205-005A	EXCAVATION	1,445.00	CY
212-011A	FIBER WATTLE	584.00	FT
212-020A	SILT FENCE	375.00	FT
212-105A	WATER AND POLLUTION	5,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	4,430.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	762.00	GAL
405-245A	APPROACH	3.00	EACH
405-425A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-2	1,250.00	TON
602-045A	24" PIPE CULVERT	70.00	FT
602-085A	48" PIPE CULVERT	210.00	FT
608-045A	24" APRON FOR PIPE	2.00	EACH
608-085A	48" APRON FOR PIPE	4.00	EACH
616-010A	SIGN TYPE B-1	18.50	SF
616-040G	STEEL SIGN POST TYPE B-2 TYPE B-2	40.00	FT
617-010A	DELINEATOR TYPE 2	39.00	EACH
626-100A	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
630-005A	T,W,S,A PAVEMENT MARKINGS - WATERBORNE	32.00	SF
630-025A	LONG PAV MKG - WATERBORNE	12,172.00	FT
675-005A	SURVEY	1.00	LS
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	5,000.00	CA
S901-05A	SP SOLAR LED SIGN	4.00	EACH
S901-05B	SP SOLAR LED DRIVER SPEED FEEDBACK SIGN	5.00	EACH
S901-05C	SP REMOVE AND RESET SIGN (1 POST)	1.00	EACH
S901-05D	SP REMOVE AND RESET GATE	3.00	EACH
S901-05E	SP CHECK DAM	1.00	EACH
S901-05F	SP REMOVE AND RESET MAILBOX	1.00	EACH
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
S904-05B	SP SEEDING	1.00	LS
S912-05A	SP NX750-FG GEOGRID	8,261.00	SY
Z629-05A	MOBILIZATION	1.00	LS