

Key No. 23719n – I-15, PORTERVILLE BRIDGE REPAIR
Bingham County

Item No	Description	QTY	Unit
203-010A	Asbestos Removal and Disposal	10,000	CA
203-021A	Removal of Bridge – Partial	1	LS
502-310A	Conc Class 40 AF Sch. No. 2	14.0	CY
502-360A	Prestressed AASHTO Girder, Type II	57.6	FT
503-015A	Metal Reinf Sch. No. 2	2,895.0	LB
507-005A	Elastomeric Bearing Plain	2.0	EA
582-005A	Patch and Repair of Concrete Surfaces	50	SF
626-100B	Misc. Temporary Traffic Control	5,000	CA
S501-25A	SP Bridge, Remove and Reinstall Bridge Rail	1	LS
S501-30A	SP Bridge, Silicone Sealant Joint	68.8	Ft
S900-50A	Contingency Amount Directed Repairs	10,000	CA
S904-05A	SP Temporary Traffic Control Design and Operations	1	LS