Bid Items List

Key No. 23880 - SPIRIT LAKE CUTOFF CURVES

Bonner County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	10,000.00	CA
203-003A	REMOVAL OF OBSTRUCTIONS CULVERT	159.40	FT
203-006A	REMOVAL OF SIGN	29.00	EACH
203-075A	REMOVAL OF FENCE	781.00	FT
204-006A	OBLITERATION OF OLD ROAD	1.00	LS
205-005A	EXCAVATION	5,600.00	CY
205-030A	BORROW	1,750.00	CY
212-011A	FIBER WATTLE	570.00	FT
303-005A	2" AGGREGATE FOR BASE	5,985.00	TON
303-022A	3/4" AGGREGATE TYPE B FOR BASE	2,450.00	TON
405-245A	APPROACH	5.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3 PG 58-28	995.00	TON
602-025A	12" PIPE CULVERT	190.00	FT
602-035A	18" PIPE CULVERT	130.00	FT
605-655A	DRYWELL	1.00	EACH
612-005A	W-BEAM GUARDRAIL	1,106.30	FT
612-110A	GUARDRAIL ANCHOR	1.00	EACH
612-115C	GUARDRAIL TERMINAL, TANGENT	3.00	EACH
616-010A	SIGN TYPE B-1	488.00	SF
616-040G	STEEL SIGN POST TYPE B-2	40.00	FT
616-040J	STEEL SIGN POST TYPE E-1 TYPE E-1	212.00	FT
616-040K	STEEL SIGN POST TYPE E-2 TYPE E-2	424.00	FT
616-100A	SIGN BRACES	314.00	LB
617-020A	DELINEATOR TYPE 4	254.00	EACH
621-005A	SEED BED PREPARATION	2.33	ACRE
621-010A	SEEDING	2.33	ACRE
621-015A	MULCHING	4.66	ACRE
621-025A	MULCH ANCHORING (TACKIFIER)	4.66	ACRE
621-035A	FERTILIZING	2.33	ACRE
624-005A	LOOSE RIPRAP	4.08	CY
626-100A	MISC TEMPORARY TRAF CONT ITEMS	5,000.00	CA
630-010A	T,W,S,A PAVEMENT MARKINGS - PREF THERMO	27.00	SF
630-025A	LONG PAV MKG - WATERBORNE	5,985.00	FT
634-005A	MAILBOX	7.00	EACH
675-005A	SURVEY	1.00	LS
675-010A	DIRECTED SURVEYING	5,000.00	CA
677-005A	RECORD DRAWINGS	1.00	LS
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	5,000.00	CA
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
S908-05A	SP TREE REMOVAL (NO GRUBBING)	2.37	ACRE
S908-05B	SP GRUBBING	2.37	ACRE
Z629-05A	MOBILIZATION	1.00	LS