

Key No. 24339 - STC-1888, FERRY BUTTE BRIDGE REHAB  
Bingham County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	2,000.00	CA
203-010A	ASBESTOS REMOVAL AND DISPOSAL	5,000.00	CA
203-080A	REMOVAL OF GUARDRAIL	583.00	FT
212-105A	WATER AND POLLUTION	3,000.00	CA
303-022A	3/4" AGGREGATE TYPE B FOR BASE	100.00	TON
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	82.00	TON
431-005A	COLD MILLING	619.00	SY
553-005A	EPOXY OVERLAY	12,302.00	SF
565-005A	ASPHALTIC PLUG EXPANSION JOINT SYSTEM	42.00	CF
569-005A	REMOVAL OF EXPANSION JOINT	148.10	FT
581-005A	CONCRETE CRACK REPAIR PREPARATION	366.00	FT
581-010A	CONCRETE CRACK EPOXY INJECTION	5.20	GAL
582-005A	PATCH AND REPAIR OF CONCRETE SURFACE	5.00	SF
582-010A	PATCH AND REPAIR OF CONCRETE DECK	197.00	SF
612-005A	W-BEAM GUARDRAIL	637.50	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	4.00	EACH
626-010A	TEMPORARY TRAFFIC CONTROL SIGNS	418.00	SF
626-050A	DRUMS	34.00	EACH
626-092A	TEMPORARY PAVEMENT MARKING TAPE	72.00	FT
626-100A	MISC TEMPORARY TRAF CONT ITEMS	1,000.00	CA
626-105A	TEMPORARY TRAFFIC CONTROL MAINTENANCE	50.00	HR
626-115A	PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)	84.00	DAY
626-116A	TEMPORARY CONCRETE BARRIER	800.00	FT
626-117A	R&R TEMP CONCRETE BARRIER	800.00	FT
626-118A	TEMPORARY CRASH CUSHION	2.00	EACH
626-120A	FLAGGER CONTROL	60.00	HR
626-130B	TEMPORARY TRAFFIC CONTROL SIGNAL	84.00	DAY
626-135A	WEIGHTED BASE TUBULAR MARKERS	40.00	EACH
675-005A	SURVEY	1.00	LS
676-015A	RECORD AND REESTABLISH PAV MARKINGS	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S501-20A	SP BRIDGE DECK DRAIN EXTENSION	48.00	EACH
S501-25A	SP BRIDGE REMOVE DEBRIS FROM BEARING ASSEMBLIES	1.00	LS
S501-30A	SP BRIDGE DELAWARE RAIL RETROFIT	1,104.00	FT
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	5,000.00	CA
Z629-05A	MOBILIZATION	1.00	LS