Bid Items List

Key No. 24341 - SOUTH TETON RIVER BRIDGE

Fremont County

Item No	Description	QTY	Unit
107-019A	SURVEY MONUMENT PRESERVATION	5,000.00	CA
110-005A	TRAINING	640.00	HR
201-005A	CLEARING & GRUBBING	0.44	ACRE
203-006A	REMOVAL OF SIGN	2.00	EACH
203-020A	REMOVAL OF BRIDGE - FULL (APPROX. 5700 SF)	1.00	EACH
203-075A	REMOVAL OF FENCE	71.00	FT
203-080A	REMOVAL OF GUARDRAIL	699.00	FT
203-123A	REMOVAL OF MISCELLANEOUS ITEMS CONCRETE BARRIER	178.00	FT
205-005A	EXCAVATION	1,310.00	CY
205-045A	GRANULAR BORROW	7,373.00	TON
210-005A	STRUCTURE EXCAVATION SCHEDULE NO. 1 (SOIL AND GRAVEL)	251.00	CY
210-015A	COMPACTING BACKFILL	71.00	CY
212-011A	FIBER WATTLE	1,735.00	FT
212-105A	WATER AND POLLUTION	5,000.00	CA
301-005A	GRANULAR SUBBASE	3,190.00	TON
301-010A	GRANULAR SUBBASE	71.00	CY
303-022A	3/4" AGGREGATE TYPE B FOR BASE	1,675.00	TON
401-020A	CSS-1 DIL EMUL ASPH FOR TACK COAT	514.00	GAL
405-245A	APPROACH PAVED	2.00	EACH
405-245B	APPROACH GRAVEL	1.00	EACH
405-435A	SUPERPAVE HMA PAV INCL ASPH&ADD CL SP-3	1,020.00	TON
502-140A	CONCRETE CLASS 40-A SCHEDULE NO. 1	140.30	CY
502-310A	CONCRETE CLASS 40 AF SCHEDULE NO. 2	277.10	CY
502-380A	PRESTRESSED WF GIRDER (TOP FLANGE 49", DEPTH 42")	644.70	FT
502-430A	CONCRETE PARAPET 42" SINGLE SLOPE	488.80	FT
502-435A	APPROACH SLAB	362.30	SY
503-010A	METAL REINFORCEMENT SCHEDULE NO. 1	27,447.00	LB
503-015A	METAL REINFORCEMENT SCHEDULE NO. 2	23,763.00	LB
503-020A	EPOXY COATED METAL REINFORCEMENT	34,497.00	LB
507-005A	ELASTOMERIC BEARINGS PLAIN (0.5"X10"X3'-0")	8.00	EA
507-010A	ELASTOMERIC BEARINGS LAMINATED (1.474"X6"X3'-0")	8.00	EA
566-005A	COMPRESSION EXPANSION JOINT	76.00	FT
576-005A	(GFRP) REINFORCEMENT	400.00	FT
584-005A	TEMPORARY SHORING	1.00	LS
586-005A	UTILITY CONDUIT COMPLETE INSTALLATION (LENGTH 1181')	1.00	LS
587-005A	PAINTING STRUCTURAL STEEL (PILING, APPROX. 1131 SF)	1.00	LS
607-001A	EMBANKMENT PROTECTOR	4.00	EACH
607-035A	DISCHARGE PIPE	74.00	FT
612-005A	W-BEAM GUARDRAIL	420.00	FT
612-115C	GUARDRAIL TERMINAL, TANGENT	4.00	EACH
612-120B	GUARDRAIL TRANSITION, HIGH SPEED	4.00	EACH
621-015A	MULCHING ROCK	0.44	ACRE
624-005A	LOOSE RIPRAP	794.00	CY

626-100A	MISC TEMPORARY TRAF CONT ITEMS	10,000.00	CA
630-025A	LONG PAV MKG - WATERBORNE	4,548.00	FT
640-010A	RIPRAP/EROSION CONTROL GEOTEXTILE	1,358.00	SY
675-005A	SURVEY	1.00	LS
677-005A	RECORD DRAWINGS	1.00	LS
S501-25A	SP BRIDGE DEWATERING FOUNDATIONS	1.00	LS
S501-30A	SP BRIDGE DRILLED-IN CONCRETE PILES	794.00	FT
S900-50A	CONTINGENCY AMOUNT MISCELLANEOUS WORK	10,000.00	CA
S901-05A	SP JUNCTION BOX	4.00	EACH
S904-05A	SP TEMPORARY TRAFFIC CONTROL	1.00	LS
Z629-05A	MOBILIZATION	1.00	LS